

# GOVERNMENT OF ORISSA WORKS DEPARTMENT


## ORISSA STATE ROAD PROJECT

### FEASIBILITY STUDY AND DETAILED PROJECT PREPARATION FOR PHASE-I ROADS

#### FINAL DETAIL ENGINEERING REPORT BERHAMPUR - TAPTAPANI - 41 Kms [OSRP - CW - Y1 - P03]



(APRIL - 2007)

### MAIN REPORT



**CONSULTING  
ENGINEERS GROUP LTD.**

E-12, Moji Colony, Malviya Nagar Jaipur-17  
Tel: +91-141-2520899, 2521899, 2520556  
Fax: 2521348, E-mail: ceg@cegindia.com



## **TABLE OF CONTENTS**

### ***ABBREVIATIONS***

### ***EXECUTIVE SUMMARY***

<b>1</b>	<b>INTRODUCTION</b>	
1.1	GENERAL	1-1
1.2	PROJECT BACKGROUND	1-1
1.3	PRESENT ASSIGNMENT	1-2
1.3	PROJECT ROADS	1-2
1.4	CIVIL CONSTRUCTION PACKAGE	1-3
1.5	COMPOSITION OF REPORT	1-6
<b>2</b>	<b>SURVEY AND INVESTIGATION</b>	
2.1	GENERAL	2-1
2.2	TOPOGRAPHICAL SURVEY	2-1
2.3	GEOTECHNICAL AND MATERIAL INVESTIGATIONS	2-3
2.4	HYDRAULIC AND HYDROLOGICAL INVESTIGATIONS	2-13
2.5	INVESTIGATION FOR BRIDGES AND STRUCTURES	2-17
2.6	PAVEMENT INVESTIGATIONS	2-27
2.7	ROAD SAFETY REVIEW	2-35
2.8	SURVEYING UTILITY SERVICES	2-40
2.9	TRAFFIC SURVEY	2-41
<b>3</b>	<b>DETAIL DESIGN – ROAD ALIGNMENT</b>	
3.1	GENERAL	3-1
3.2	DESIGN STANDARDS	3-1
3.3	GEOMETRIC DESIGN STANDARDS	3-2
3.4	DESIGN SOFTWARES	3-8
3.5	UTILITY SERVICES	3-9
3.6	WAY SIDE AMENITIES	3-9
3.7	DETAIL DRAWINGS	3-9
<b>4</b>	<b>PAVEMENT DESIGN</b>	
4.1	GENERAL	4-1
4.2	IRC METHOD	4-1
4.3	DESIGN METHODOLOGY	4-1
<b>5</b>	<b>DRAINAGE SYSTEM AND PROTECTION WORKS</b>	
5.1	GENERAL	5-1
5.2	EXISTING SCENARIO	5-1
5.3	DETAILED DESIGN	5-1
5.4	DRAINAGE ON HIGH EMBANKMENT	5-5
5.5	LONGITUDINAL GRADIENT	5-5
<b>6</b>	<b>DETAIL DESIGN OF STRUCTURES</b>	
6.1	GENERAL	6-1
6.2	PROPOSED BRIDGES	6-2
6.3	WIDTH	6-2
6.4	DESIGN PHILOSOPHY	6-3
6.5	DESIGN LOADS	6-3
6.6	MATERIAL SPECIFICATIONS	6-4
6.7	DETAIL DESIGN	6-5
6.8	PROPOSED CULVERTS	6-5
6.9	REHABILITATION OF STRUCTURES	6-11

<b>7</b>	<b>ROAD SAFETY MEASURES</b>	
7.1	GENERAL	7-1
7.2	ROAD SAFETY MEASURES	7-1
<b>8</b>	<b>SPECIFICATIONS AND CONSTRUCTION PLANS</b>	
8.1	SPECIFICATIONS	8-1
8.2	CONSTRUCTION PLANS	8-1
8.3	TRAFFIC MANAGEMENT	8-4
8.4	CONSTRUCTION METHODOLOGY	8-6
<b>9</b>	<b>SOCIAL ASSESSMENT AND RESETTLEMENT ACTION PLAN</b>	
9.1	GENERAL	9-1
<b>10</b>	<b>ENVIRONMENTAL ACTION AND ENVIRONMENTAL MANAGEMENT PLAN</b>	
10.1	GENERAL	10-1
<b>11</b>	<b>COST ESTIMATIONS</b>	
11.1	GENERAL	11-1
11.2	METHODOLOGY	11-1
11.3	BILL OF QUANTITIES	11-1
11.4	UNIT RATES	11-1
11.5	COST ESTIMATES	11-2

***ANNEXURE – A (REPLY TO PIU COMMENTS)***

## **LIST OF TABLES**

Table 1.1	List of the project Road	1-2
Table 1.2	List of Civil Construction Package	1-3
Table 2.1	List of TBM	2-2
Table 2.2	Soil Investigation Data of Existing Subgrade	2-5
Table 2.3	Sources of Construction material	2-9
Table 2.4	Sub Soil exploration Test Locations	2-13
Table 2.5	Recommendations from Subsoil Investigations	2-13
Table 2.6	Vertical Clearance	2-17
Table 2.7	Hydraulic Parameters	2-17
Table 2.8	Inventory and condition of Existing Bridges	2-20
Table 2.9	Summary of Existing Bridges	2-20
Table 2.10	Inventory and Existing Culverts	2-25
Table 2.11	Summary of Existing Culverts	2-27
Table 2.12	Pavement Condition	2-29
Table 2.13	Pavement Composition	2-33
Table 2.14	Roughness Value in IRI	2-34
Table 2.15	Characteristic Deflections	2-35
Table 2.16	List of Junctions	2-38
Table 2.17	AADT and PCU	2-41
Table 2.17	Summary of AADT and PCU	2-41
Table 2.18	Design VDF	2-42
Table 2.19	Design MSA	2-42
Table 2.20	Projected Traffic	2-42
Table 3.1	List of IRC Publications	3-2
Table 3.2	Terrain Classifications as per IRC	3-3
Table 3.3	Design Speed for different Terrain Classes	3-3
Table 3.4	Recommended Road Land Width	3-3
Table 3.5	Minimum recommended Sight Distances	3-5
Table 3.6	Absolute Minimum Radius	3-5
Table 3.7	Radius Beyond Which Super Elevation not Required	3-6
Table 3.8	Extra Widening at Curve	3-7
Table 3.9	Gradients for Different Terrain	3-7
Table 3.10	Minimum length of Vertical Curve	3-8
Table 3.11	Side Slope in Embankment	3-8
Table 4.1	Design CBR for Berhampur-Taptapani corridor	4-3
Table 4.2	Crust details for Reconstruction for the Bhawanipatna – Khariar as per IRC method	4-4
Table 4.3	Crust details for Reconstruction/widening for the Berhampur- Taptapani as per Method	4-4
Table 4.4	Crust details for Overlay for the Berhampur-Taptapani as per IRC method (IRC:81-1997)	4-6
Table 5.1	List of Built-up Sections	5-3
Table 6.1	List of IRC Codes	6-1
Table 6.2	Proposed Bridges	6-2
Table 6.3	Proposed Culverts	6-6
Table 6.3a	Summary of proposed culverts	6-11
Table 6.4	Rehabilitation of Minor Bridges	6-12
Table 7.1	Serviceability Criteria	7-2
Table 7.2	List of Junctions	7-3
Table 7.3	Schedule of Bus Bays	7-8
Table 7.4	Location of Guard Posts	7-10
Table 7.5	Schedule of Road Humps	7-11
Table 7.6	schedule of Pedestrian Crossing	7-13

**LIST OF FIGURES**

Figure 2.1	Cracking (%) Variation along the stretch	2-31
Figure 2.2	Raveling (%) Variation along the stretch	2-31
Figure 2.3	Potholing (%) Variation along the stretch	2-32
Figure 2.4	Patching (%) Variation along the stretch	2-32
Figure 2.5	Cross Junction	2-37
Figure 2.6	T-Junction	2-37
Figure 5.1	Road Section at Built-up location	5-3
Figure 5.2	Detailed Urban Drain Section	5-4
Figure 5.3	Road Section at Rural location	5-4
Figure 5.4	Detailed Rural Drain Section	5-5

## **ABBREVIATIONS**

---

**ABBREVIATIONS**

AADT	Annual Average Daily Traffic
AASHTO	American Association of State Highway and Transportation Officials
ADT	Average Daily Traffic
BBD	Bankelman Beam Deflection
BC	Bituminious Concrete
BI	Bump Integrator-Roughness (mm/km)
BOQ	Bill of Quantities
CBR	California Bearing Ratio
CEG	Consulting Engineerws Group Ltd.
CV	Commercial Vechiles
CVD	Commercial Vehicles per Day
DBM	Dense Bituminous Macadam
DFS	Differential Free Swell Index
DLC	Dry Lean Concrete
DTM	Digital Terrain Model
EA	Environment Assessment
EIA	Environment Impact Assessment
EMP	Environment Management Plan
EIRR	Economic Internal Rate of Return
ESMF	Environment and Social Management Framework
ESAL	Equivalent Standard Axle Load
GDP	Gross Domestic Product
GNP	Gross National Product
GOO	Government of Orissa
GOI	Government of India
GSB	Granular Sub Base
HDM-4	Highway Development and Management Model-4
HFL	High Flood Level
HS	Hard Shoulder
IRC	Indian Roads Congress
IRI	International Roughness Index
LSF	Load Safety Factor
MDR	Major District Road
MoSRT&H	Ministry of Shipping, Road Transportation and Highways
MOU	Memoranda Of Understanding
MSA	Million Standard Axles
MTPA	Million Tonnes Per Annum

NGO	Non-Government Organization
NDT	Non-Destructive Test
NH	National Highway
NHAI	National Highway Authority of India
NMT	Non-Motorized Traffic
NNP	Net National Product
NPV	Net Present value
NSDP	Net State Domestic Product
O-D	Origin and Destination
OSRP	Orissa State Roads Project
OWD	Orissa Works Department
PCC	Project Coordinating Consultants
PCNSDP	Per Capita Net State Domestic Product
PCU	Passenger Car Unit
PIA	Project Influence Area
PIU	Project Implementation Unit
PMC	Pre Mix Carpet
SA	Social Assessment
SDBC	Semi Dense Bituminous Concrete
SF	Seasonal Factor
SH	State Highway
SOS	Strategic Option Study
TOR	Terms of Reference
TRRL	Transport and Road Research Laboratory (UK)
VDF	Vehicle Damage Factor
VOC	Vehicle Operating Costs
WB	World Bank
WBM	Water Bound Macadam
WMM	Wet Mix Macadam



# **EXECUTIVE SUMMARY**

---

## EXECUTIVE SUMMARY

1. The Orissa Works Department (OWD) aims to upgrade and widen its vital arterial State roads to 2-lanes to accelerate the overall economic growth as the Orissa has untapped immense potential of development in mining, industry, tourism, ports sectors. The Orissa State has planned to arrange funds from World Bank for developing about 825 km of roads under Phase-I limiting to the amount of US \$250million spread over 5 years.
2. The OWD has engaged M/s CEG Limited for providing the consultancy services for preparation of the Feasibility and Detail Project Report for 825km of roads under Phase-I. This Project also includes network analysis of 3700 km (3955 as per data collected) State Highways to arrive at selection of 1600 km for feasibility studies for subsequent Phases. The Consultancy services were commenced from 6th December 2005.
3. The present submission is the “Final Detailed Engineering Report for Berhampur to Taptapani Road (km 0/0 to km 41/0 of SH-17)” under Phase-I. This is a part of Berhampur - Bangi Junction – Rayagada Corridor. The continuous interaction and joint field inspections of the consultant and PIU during the course of field surveys/ investigations and subsequent verification of actual designs of highway alignments and bridges in the field, has enabled to produce a practical Detailed Engineering Report. This report has been proposed incorporating the comments and discussions of PIU. Reply to PIU comments are appended in Annexure-A enclosed.
4. The earlier submissions of Inception Report, Economic Viability Report, Social Screening and Environmental Screening Reports and Feasibility Report have already been accepted. The structure of this report is in accordance with reporting requirements as per agreement.
5. Detailed Survey and Investigations were carried out for the following:
  - i. Topographical Survey
  - ii. Geotechnical and Material Investigations
  - iii. Hydraulic and Hydrological investigation
  - iv. Investigation for Bridges and Structures
  - v. Pavement Investigations
  - vi. Road Safety Review
  - vii. Surveying Utility Services
6. Topographic survey was conducted with the help of Total Station. Longitudinal section levels were taken at every 25 m interval along the centre line of the existing carriageway. Cross sections were taken at every 50 m interval covering full extent of survey corridor. Longitudinal and cross sections survey for major/minor streams was also carried out as per the requirements. Bench Mark Pillars were erected at an interval of 1 km along the route.

7. The sub-grade soil samples were collected from each km along the existing alignment. The detailed investigations for existing road include both field and laboratory testing. Test pits were excavated at the shoulder adjacent to pavement edge at interval of 1km. Low to high expansive soils of CL-CH group are found in various Sections of SH-17 i.e. km 3/0, 6/0, 9/0, 16/0 - 21/0, 28/0 – 30/0, and 37/0 – 39/0. In these stretches either replace the soil of high expansive properties by importing good soil from borrow area or treat the soil of low to medium expansive soils.
8. To identify potential sources of material for construction, the survey and investigation for different construction materials were carried out in respect of their likely sources and the availability and suitability of various materials. Relevant laboratory tests were conducted on representative samples as per requirement.

**Table 1: Sources of Construction Material**

S.No.	Material	No. of Sources Identified
1	Granular Sub base	4
2	Coarse Aggregate/ Stone	6
3	Sand / Fine Aggregate	3
4	Morrum	4
5	Cement	2
6	Water	3
7	Stone	6

9. Geotechnical investigation for bridges and other structures were carried out to determine the appropriate foundation type and its load carrying capacity.

**Table 2: Recommendations from Subsoil Investigations**

Location	Chainage	Type of foundation	Minimum Depth of Foundation
1	1/915	Open/Pile	3.0m from bed level/13m from Ground Level
2	11/270	Open	3.0m from bed level
3	29/500	Pile	13m from Ground level

10. Hydrological investigations were carried out to determine hydraulic adequacy of the structures. None of the Bridge found inadequate.
11. A detailed inventory and condition survey was carried out for structures. There are total 10 bridges, 1 of them is major and remaining 9 are minor bridges. All bridges and culverts were inspected for their present condition and verified jointly with PIU Engineers. The NDT (Rebound hammer and Ultrasonic pulse velocity) tests were conducted for bridges at chainage 11/660 and 17/900 to study the structural soundness of the structures. The recommendations are as follows.

**Table 3: Inventory and Condition of Existing Bridges**

Sl. No.	Location/Chainage	Existing Span Arrangement	Type of Superstructure	Type of foundation	Overall condition/ Recommendation
1	1/915	2 x 6.6	Solid Slab	Open foundation	Good, Rehabilitation required
2	4/400	3 x 6.75	Solid Slab	Open foundation	Good, Rehabilitation required
3	11/270	1 x 6.35	Iron Joist with Solid Slab	Open foundation	Reconstruction due to poor condition
4	11/660	3 x 6.8	Solid Slab	Open foundation	Rehabilitation required
5	15/185	2 x 6.8	Solid Slab	Open foundation	Good, Rehabilitation required
6	15/680	4 x 6.8	Solid Slab	Open foundation	Good, Rehabilitation required
7	17/900	4 x 6.8	Solid Slab	Open foundation	Good, Rehabilitation required
8	21/850	3 x 10.8	Solid Slab	Open foundation	Good, Rehabilitation required
9	29/230	3 x 42.2	PSC girder with Deck slab	Well foundation	Good, Nothing to do
10	29/500	2 x 7.0	RCC girder with Deck slab	Open foundation	Reconstruction due to narrow in width and poor condition

The total numbers of culverts are 142 in a road length of 41 kms i.e from km 0/0 to 41/0. Details of the Existing and proposed culverts are available in Chapter 2. Following table gives the details of existing culverts.

**Table 4: Summary of existing Culverts**

Type of Culvert	Nos.
Pipe	41
Slab	51
Stone slab	24
Choked	15
Arch	11
<b>Total</b>	<b>142</b>

12. Investigations were carried out on existing pavement condition to determine the most technically sound and economically feasible pavements design. The investigations include:
  - i. Visual Inspection Survey
  - ii. Pavement Composition.
  - iii. Roughness Survey
  - iv. Benkelman Beam Deflection Survey
13. The existing Project Road has sharp horizontal curves and insufficient vertical design standard, which do not provide adequate overtaking sight and stopping distance even for 50 kmph thereby making the accidents more frequent. Existing road junctions are not properly designed. These deficiencies have been properly attended in the design.

14. The traffic surveys were conducted to determine classified traffic volumes in terms of Annual Average Daily Traffic (AADT), directional split, hourly variation, trip length pattern, travel pattern of goods and passenger traffic, commodity flow and axle loads. Traffic Volume Count Survey was conducted at two locations; one VC-7 at km 0/600 near Berhampur and other VC-8 at 22/500 near Digapahandi. Axle load survey was carried out near Berhampur, designated as AL-05 and conducted using Portable Load Pads, developed in Indian Institute Technology, Kharagpur, having platform size 550mm X 700mm X 30mm (weight 30 kg) with digital load indicator. Following tables gives the summary of traffic surveys carried out.

**Table 5: Summary of AADT and PCU**

Count Stn.	Description	Total Motorised Vehicle	Total Comm. Vehicle	Total Non Motorised Vehicle	Total Vehicle
VC-7	AADT	4149	808	4003	8152
	PCU	4285	2277	2362	6647
VC-8	AADT	1432	2398	493	1190
	PCU	1987	2540	1345	687

**Table 6: Design VDF**

Station	Road Section	Recommended values of VDF for				
		LCV	2-Axle Truck		3-Axle Truck	
			2008-13	2013-28	2008-13	2013-28
AL-05	Berhampur - Taptapani	0.18	3.71	3.5	3.71	3.5

**Table 7: Design MSA**

Location	Design Year	Design MSA
VC-7	2028	14.40
VC-8	2028	8.65

**Table 8: Projected Traffic**

Year	AADT		PCU	
	VC-7	VC-8	VC-7	VC-8
2008	9309	4165	7743	3805
2013	11245	5266	9941	5034
2018	13950	6797	13119	6791
2023	17548	8828	17529	9203
2028	22058	11364	23275	12316

15. The existing road is a single lane carriageway road with horizontal and vertical geometric average to poor. Geometric Design Standards as per IRC: 73-1980 "Geometric Design Standards for Rural (Non-urban) Highway" has been generally followed. MX Road, AutoCAD and Autodesk Land Development Desktop softwares have been used for the designing and drafting. The Project road has been designed as a two-lane carriageway with hard shoulders. The width of two lanes has been taken as

7.0m with 2.5m wide hard shoulders on either side. Total roadway width has been taken as 12.00 m. In built up areas, paved shoulder of 1.5m widths shall be provided making total roadway width of 10m. Beyond this, covered drains shall be provided which will be used as walkway.

16. Plan and profile drawings has been prepared separately at scale of 1:2000 horizontal and 1:200 vertical. It shows all existing plan features, toe line of highway embankment, proposed right of way limits, drainage structure locations, existing ground profile, proposed finished profile, intersection layouts, typical cross sections of the main alignment, etc. Bus-bays and Truck Lay-bays have been provided at appropriate locations and specified in schedule of drawings.
17. Designs for new pavement and overlays are worked out in accordance with Indian Standards. The CBR is taken at an interval of 1 Km along the stretch. If the CBR is less than 4%, then new construction is adopted. If the CBR is more than 4% but the deflection value is too high, reconstruction is adopted otherwise overlay is adopted. Crust details for new construction and reconstruction has been given in Chapter 4.
18. Unlined open trapezoidal drains for the rural sections and RCC Box covered drains for the Built-up Sections have been used.
19. Out of the existing 10 bridges, the bridge at location 29/300 is major and remaining 9 are minor. Bridge at location 11/270 is in poor condition and narrow in width, it is recommended for re-construction. The bridge at location 1/915 is slightly realigned and will be widened and the bridge at location 29/500 is realigned and narrow in width is recommended for reconstruction.
20. Culverts in good condition and adequate size, which meets the requirements of plan and profile in respect of highway geometry and levels, have been retained. These have been widened to make full formation width if narrow. The culverts, which need replacement due to poor condition or inadequate size, have already been indicated in Chapter-02. The culverts, which cannot be used due to change in horizontal alignment or change in vertical alignment, also need replacement along new alignment. A summary of retained, widening and new culverts are given in table below.

<b>Type of Culvert</b>	<b>Nos.</b>
Culverts Retained	Nil
Culverts Widened	
Pipe extension	5
Slab widening	12
Culverts Replaced	
New Single Pipe	51
New Double Pipe	9
New Single Box of 1/22/0	24
New Single Box of 1/22/1	1
New Single Box of 1/23/0	20
New Single Box of 1/33/0	12
New Single Box of 1/43/0	2
New Single Box of 1/44/0	1
<b>Total</b>	<b>137</b>

21. To increase the traffic safety and to reduce traffic accidents, every component of the highways and its users has been given equal importance. Road geometric components have been designed to meet the State Highway standards as specified in the IRC: 73-1980. The traffic control devices, which are used to reduce accidents and improve flow conditions, road markings and road signs, have been used as per IRC standards.
22. In general, the specifications laid down in “Specifications for Road and Bridge Works – Fourth Revision - by MoSRT&H” shall be followed. The detailed specifications have been given in Bidding Document prepared separately for each civil construction package. Construction scheme and traffic management system during construction have been described in Chapter 8. All necessary safety measures shall be adopted for safety of moving traffic and working persons engaged in the construction zone.
23. Detail costs have been worked out for the different items of road works and structures. Estimated total cost of this package is Rs 954.70 millions which includes engineering cost as Rs 753.478 millions. Estimated cost for provisional items, social, environmental and utility shifting costs as Rs 63.20 millions.

# **CHAPTER - 1**

## **INTRODUCTION**

---



## **CHAPTER 1**

### **INTRODUCTION**

#### **1.1 GENERAL**

The fast growing Orissa State is one of the major state of India with population 36.8 million persons and ranks 11<sup>th</sup> with population share 3.58% -Census 2001 and having geographical area 0.155 million sq km with 9<sup>th</sup> rank in India. The 480 km coastline with ports also makes Orissa a distinguished State. The Orissa is not only very rich in minerals deposits but also has surplus power and water. The country's over 90% Chromites and Nickel deposits are in Orissa beside over 50% Bauxite, 30% of Manganese, Iron ore and coal. The Orissa is a favoured destination of investment. The road transport is a dominant mode for movement of goods and passengers and need based upgrading of existing road network has been envisioned by the state.

This chapter describes the background of the project, present project roads with contract packages and composition of the Detailed Engineering Report of the contract package Behrampur – Taptapani (SH-17) (km 0/0 to km 41/0) section which is a part of Behrampur – JK pur (Rayagada) 193 km project corridor. The report presents detailed design of road and bridges with cost for upgrading existing road to two lane. Proposals and further details for improving the existing road to two lanes are detailed in the succeeding chapters.

#### **1.2 PROJECT BACKGROUND**

The Orissa Works Department (OWD) had conducted a Strategic Option Study of State Roads, in (1995-1997) which identified 2347 km of State Roads out of 4600 km of State Highways and Major District Roads for improvement based on traffic volume, carriageway width, and pavement condition.

The Government of Orissa contracted a Project Coordinating Consultant (PCC) for feasibility study of 2347 km to identify 700 km in two phases for techno-economic appraisal with detailed project preparation to meet World Bank norms. The PCC had completed detailed engineering design for widening and strengthening for a length of 198 km which was later declared National Highway (NH-224) and as a result of techno-economic studies in this project, 1200 km were prioritized for a four year periodic maintenance programme and but the project was not implemented.

The OWD intends to upgrade and widen its vital arterial State roads to 2-lanes to accelerate the overall economic growth of the State having immense untapped potential in mining, industry, tourism, and ports. The Orissa State has planned to avail loan from World Bank for developing about 825 km of roads under Phase-I limiting to the loan amount of US \$250million spread over five years. This Project also includes network analysis of remaining 3700 km (3900 as per data collected) State Highways based techno-economic approach with an aim to arrive at selection of 1600 km of project routes for feasibility studies for subsequent Phases.

### 1.3 PRESENT ASSIGNMENT

The OWD has engaged M/s CEG Limited for providing the Consultancy Services for preparation of the Feasibility and Detail Project Report for 825 km of roads under Phase-I. The assignment also includes network analysis of 3700 km (3900 as per data collected) State Highways to arrive at selection of 1600 km for feasibility studies for subsequent Phases. The Consultancy services were commenced from 6th December 2005.

The Feasibility Study report for 825 km of roads has been completed and accepted by the OWD. The Draft Network Analysis report and Draft Detailed Engineering for Year- I roads already been submitted

Present submission is Final Detailed Engineering Report of Behrampur - Taptapani (km 0/0 to km 41/0).

### 1.4 PROJECT ROADS UNDER PHASE-I

The Project, with total length 835 km, mostly existing State Highways, is comprising of five corridors which are passing through 14 districts (out of total 30 districts) having 51.7% area and 53.1% population of the State. These corridors provide vital connections with faster mobility within State and out side State for communication, mining, industry, tourism, ports etc. The list of the Project Road Corridors is given in Table 1.1 along with the road designation and total length in km. The Project Roads consist of existing State Highways and MDR. The Project Roads locations are shown in Map 1.1.

**Table 1.1: List of the Project Road**

Sl. No.	Name of Road	SH/MDR	Length (km)	District Crossed
1	<b>Jagatpur - Kendrapada - Chandbali Bhadrak</b>			1.Bhadrak
	a) Jagatpur - Kendrapada - Chadbali	SH-9A	99	2.Cuttack
	b) Chandbali – Bhadrak	SH-9	53	3.Kendrapara
2	<b>Bhadrak - Anandapur - Karanjia - Jashipur</b>			1.Bhadrak
	a) Bhadrak – Anandapur	SH-53	57	2.Keonjhar
	b) Anandapur - Karanjia	SH-53	65	3.Mayurbhanj
	c) Karanjia - Jashipur	SH-49	15	
3	<b>Berhampur - Raygada</b>			1.Gajapati
	a) Berhampur - Bangi Jn.	SH-17	151	2.Ganjam
	b) Bangi Jn. - JK Pur	SH4	52	3.Rayagada
4	<b>Khariar - Bhawanipatna - Muniguda - Kerada</b>			1.Bolangir
	a) Khariar – Bhawanipatna	SH-16	70	2.Kalahandi
	b) Bhawanipatna - Muniguda	SH-6	68	3.Nuapada
	c) Muniguda - J.K.Pur	SH-5	50	4.Rayagada
	d) Raygada - Kerada	MDR-48B	24	
5	<b>Banarpal – Daspalla and Bhanjanagar - Aska</b>			1.Anugul
	a) Banarpal - Daspalla	MDR-18,19 SH-65	89	2.Cuttack
	b) Bhanjanagar - Aska	SH-7	39	3.Dhenkanal
				4.Nyagarh
				5.Ganjam
		<b>TOTAL</b>	<b>832</b>	

### 1.4.1 CONTRACT PACKAGES FOR THE PROJECT ROADS

In consultation with the OWD, the project roads have been divided into 11 (eleven) contract packages for construction and supervision, as shown in Table 1.2. The packaging is based on design, construction and administrative jurisdictions to facilitate effective construction and supervision. The packages with least environmental and social issues have been proposed in 'construction year-1' and remaining road sections in construction year-2 contracts.

**Table 1.2: List of Contract Packages for Construction of the Project Roads**

<b>Construction Year-1 Packages</b>						
<b>Package No.</b>	<b>Road Section</b>	<b>SH/MDR</b>	<b>From</b>	<b>To</b>	<b>Length (km)</b>	<b>Length of Package (km)</b>
1	Chandbali – Bhadrak	SH-9	0	45	45	96
	Bhadrak – Anandpur	SH-53	0	51	51	
2	<b>Berhampur- Taptapani</b>	<b>SH-17</b>	<b>0</b>	<b>41</b>	<b>41</b>	<b>41</b>
3	Khariar- Bhawanipatna	SH-16	2	70	68	68
4	Taptapani-Raipanka	SH-17	41	109	68	68
5	Raipanka-Bangi Jn	SH-17	109	151	42	84
	Bangi Jn-JK Pur	SH-4	161	119	42	
<b>Year-1 Total</b>						<b>357</b>
<b>Construction Year-2 Packages</b>						
<b>Package No.</b>	<b>Road Section</b>	<b>SH/MDR</b>	<b>From</b>	<b>To</b>	<b>Length (km)</b>	<b>Length of Package (km)</b>
6	Jagatpur-Kendrapada-Chandbali	SH-9A	0	99	99	107
	Chandbali – Bhadrak	SH-9	45	53	8	
7	Bhadrak – Anandpur	SH-53	51	57	6	86
	Anandpur – Karanjia	SH-53	0	65	65	
	Karanjia – Jasipur	SH-49	45	60	15	
8	J K Pur – Rayagada	SH-4	119	109	10	84
	Rayagada – Kereda	MDR-48B	0	24	24	
	J.K.Pur – Muniguda	SH-5	0	50	50	
9	Muniguda-Bhawanipatna	SH-6	0	68	68	70
	Bhawanipatna-Khariar	SH-16	0	2	2	
10	Aska - Bhanjnagar	SH-7	0	39	39	39
11	Banarpal - Dapalla	MDR-18&19 SH-65	0	89	89	89
<b>Year-2 Total</b>						<b>475</b>



## **1.5 CONTRACT PACKAGE- BEHRAMPUR-TAPTAPANI (KM 0/0 TO KM 41/0)**

The present submission is the Final Detailed Engineering Report for Berhampur to Taptapani Road (km 0/0 to km 41/0 of SH-17) which is a part of the project corridor Behrampur - JK Pur (Rayagada)-193 km. The road starts from Kolkata - Chennai 4 - lane highway (NH-5) Chainage 19/00. The road starts from km 0/0 to km 41/0 of SH-17. The Berhampur is a district headquarters of Ganjam, is major town and a business hub in the south west coast and very close to fast growing Gopalpur port. The Berhampur to Taptapani section caters the needs of nearest town Digapahandi, is an important road junction.

The road traverses mostly through plains and has mostly flat gradients with good geometry. Geometric of the road are generally mild; nevertheless improvement of the congested reaches is required. Roadside drains are rare, where provided in such areas, are generally choked or is non-functional resulting in water logging. Existing carriageway width varies from 3.6 m to 5.5 m with 1.0 m to 1.5m earthen shoulders on both sides. Riding quality all along the road is from good to poor. There are total 10 existing bridges, one of them is major and remaining 9 are minor bridges and total number of existing culverts are 142. About 25% of the road length passes through built-up area.

The improvement works involves development of existing road to two lanes with 20 years design period.

Map 1.1



## 1.6 COMPOSITION OF REPORT

The Detailing Engineering Report consists of total ten volumes as follows:

- Main Report
- Highway Drawings: Plan, Profile and Schedules.
- Standard Drawings for Highway
- Design Report of Bridge.
- Design Report of Culverts
- Hydrology Report
- Drawings of Bridges and Culverts
- Detail Cost Estimates
- Electrical Utility Shifting Plan
- Utility Shifting Plan (Telephone, OFC and Hand Pump)

The Draft Detailed Engineering Report for this project road have already been submitted vide this office letter no. CEG/OR/001/2007/318 dated Jan 15<sup>th</sup> 2007.

The Geo-technical Investigation Report and Material Report for this project road have already been submitted vide this office letter no. CEG/OR/001/2006/243 dated 3<sup>rd</sup> Oct 2006 and CEG/OR/001/2006/207 dated 3<sup>rd</sup> Aug 2006 respectively.

The main report contains nine Chapters as described below and is in accordance with the requirements of TOR for this project.

Reply to PIU comments are appended in Annexure- A.

**Chapter 1:** Introduces and provides the background to the OSRP. The study area is defined and the corridors selected for the Phase 1 are identified. The Brief description on chapterisation is also provided.

**Chapter 2:** Outlines the various field survey and investigation such as carried out their methodology adopted, findings etc. The various field survey includes, Topographical survey, Geotechnical and Material Investigations, Hydraulic and Hydrological investigation, Investigation for Bridges and Structures, Pavement Investigations, Surveying Utility Services, Road Safety Review, Traffic survey.

**Chapter 3:** Describes the detail design of road geometries, Standards adopted, Realignment, way side amenities etc.

**Chapter 4:** Presents the various aspects of pavement design. The design methodology, calculation of MSA and CBR has been described. The detail designs of overlay and crust for new section has also been discussed in this chapter.

**Chapter 5:** Discuss the detail design of Drainage system and protection works, like longitudinal drains, Embankment Protection and River Training works.

**Chapter 6:** Presents the various aspects of Structures design. The design methodology, design standards adopted and details of structure design for the road.

**Chapter 7:** Outlines the Detail Design – Road Safety Measures, Traffic Control and Other Facilities, which includes, Road Intersections, Road Furniture, Pavement Marking, Road Lighting etc.

**Chapter 8:** Describes the Specifications and Construction Plans for all aspects of the works, based on current and acceptable international standards and work methods for projects of this type. Safety and traffic management plans as well as construction phasing / sequencing to be implemented during construction to ensure minimum hindrance / interruption to traffic flow and road safety.

**Chapter 9:** Social Assessment and Resettlement Action Plan (The report will be submitted in separately volume).

**Chapter 10:** Environmental Action and Environmental Management Plan. (The report will be submitted in separately volume).

**Chapter 11:** Discuss cost estimates for each of the items included in the scope of work. It covers cost of basic inputs - materials, equipment, labor, together with overheads, profit, etc. including rate analysis, quantities, and total estimated cost.

### Reply to PIU comments

S1.No	Comments	Reply	Remarks
1	Please recheck incorporation of comments of review committee intimated earlier as regards pavement crust and lane widths	The comments intimated as per letters dated 15-1-07 and 21-2-2007 are incorporated and the report has been modified accordingly.	
2	Coherence in list of culverts in the drawing, report and schedule for culverts may be maintained with the actual requirement in the filed, with proper design Chainages.	The list of culverts as been reconsiled and presented in report, drawings and schedule.	
3	Cross reference to Environmental features to appear with reference of their detail drawings.	Environmental features have been incorporated.	
4	Name of the villages are to be corrected at certain locations.	The name of the villages has been corrected.	
5	Estimate may be recast considering the bitumen rate already transmitted to you and other parameters as stated above.	The estimate has been revised as per bitumen rates transmitted and other parameter stated above.	
Comments raised during time to time discussion with PIU.			
<ul style="list-style-type: none"> <li>In built up area at Chainage 0/600 (Berhampur to Digapahadi) and at Chainage 22/500 (Digapahandi to Mohana) the carriageway has been modified from 7m+2x1.5 paved shoulder to 7m+2x1.5 paved shoulder+2x0.25m concrete saucer drain.</li> </ul>			
<ul style="list-style-type: none"> <li>The Crash Barriers are replaced by Guard Posts.</li> </ul>			
<ul style="list-style-type: none"> <li>Concrete grade for structures have been modified</li> </ul>			
<ul style="list-style-type: none"> <li>The effect of cost of surcharge soil has been removed in stability check and stress calculations.</li> </ul>			
<ul style="list-style-type: none"> <li>Seismic forces have been considered as per IRC:6-2000 for the bridges for which seismic force is applicable.</li> </ul>			
<ul style="list-style-type: none"> <li>Dirt wall</li> </ul>			
<ul style="list-style-type: none"> <li>Floor protection works for bridges have been revised and necessary modifications have been made.</li> </ul>			
<ul style="list-style-type: none"> <li>Where DFS is more than 50%, proper treatment has been given.</li> </ul>			



## **CHAPTER - 2**

# **SURVEY AND INVESTIGATION**

---

## **CHAPTER – 2**

### **SURVEY AND INVESTIGATION**

#### **2.1 GENERAL**

The primary objective of the survey and investigation is to collect the field data in the required format to use further for detail engineering designs. Following are the various components.

- i. Topographical Survey
- ii. Geotechnical and Material Investigations
- iii. Hydraulic and Hydrological investigation
- iv. Investigation for Bridges and Structures
- v. Pavement Investigations
- vi. Road Safety Review
- vii. Surveying Utility Services

#### **2.2 TOPOGRAPHICAL SURVEY**

##### **2.2.1 Reconnaissance Survey**

The reconnaissance survey was conducted to study various features of the road. An initial assessment of the different features like geometric deficiencies, deficient curves, stretches requiring corrections in alignment/realignment identifications of junctions/intersections needing improved design, etc. were made.

##### **2.2.2 Horizontal and Vertical Control**

Efforts were made to get the GTS benchmarks along the survey route. Client has requested Survey of India, Bhubneshwar to provide GTS benchmarks, as this information can be provided to Government officials only. But the values could not be obtained. In the absence of GTS benchmarks, the horizontal control was fixed by Total Station. The azimuth was determined from magnetic bearings using small sensitive magnetic needles assembled with Total Station. For vertical control, reference was used from the Benchmark located in Berhampur town near km 0/000.

##### **2.2.3 Establishing Temporary Benchmarks**

In order to establish temporary benchmarks (TBM) along the proposed route, reference pillars were erected at an interval of 1 km along the route. Leveling was carried out to connect all the reference pillars along the route. These temporary benchmarks were used for further detail survey. The details of these TBMs from km 0/0 to 41/0 are given in Table 2.1

**Table 2.1: List of TBM**

BM Id	East	North	Elevation	BM Id	East	North	Elevation
BMP0	265618.023	2138204.969	56.000	BMP21	247430.341	2143411.660	89.665
BMP1	264903.382	2138852.769	55.631	BMP22	246468.819	2143498.552	82.518
BMP2	264297.294	2139648.027	59.100	BMP23	245545.608	2143889.047	86.050
BMP3	263679.086	2140383.099	59.812	BMP24	244652.983	2144353.648	88.526
BMP4	263199.812	2141221.695	67.201	BMP25	243775.906	2145031.193	101.202
BMP5	262363.464	2141708.398	78.721	BMP26	243030.346	2145679.577	111.174
BMP6	261424.773	2142006.926	78.091	BMP27	242151.622	2146151.886	108.589
BMP7	260487.198	2142357.602	93.374	BMP28	241267.208	2146634.081	102.154
BMP8	259878.561	2143119.074	89.127	BMP29	240408.788	2147093.214	92.501
BMP9	259173.262	2143807.047	90.186	BMP30	239507.296	2147567.063	94.740
BMP10	258318.766	2144140.430	97.695	BMP31	238627.044	2148031.217	97.730
BMP11	257309.267	2144340.759	83.595	BMP32	237805.213	2148600.812	106.589
BMP12	256308.632	2144126.858	83.202	BMP33	236942.523	2149108.554	111.553
BMP13	255343.760	2143825.989	87.811	BMP34	236167.436	2149739.966	115.852
BMP14	254357.958	2143801.349	86.790	BMP35	235327.794	2150238.197	119.737
BMP15	253367.857	2143707.826	90.264	BMP36	234461.966	2150740.416	127.663
BMP16	252379.542	2143595.763	90.678	BMP37	233737.502	2151421.463	127.241
BMP17	251386.350	2143529.124	90.547	BMP38	233007.735	2152098.379	134.487
BMP18	250396.673	2143474.725	82.567	BMP39	232345.807	2152837.323	145.003
BMP19	249395.470	2143404.516	94.353	BMP40	231689.974	2153604.663	152.775
BMP20	248404.200	2143502.182	94.649	BMP41	230883.528	2154175.722	163.056

## 2.2.4 Total Station Traverse

Leveling was carried out from the known Benchmarks to the reference pillars along the route. All the coordinates i.e. x, y and z were fixed at the temporary benchmarks by close traversing. Leveling adjustments were also been made for horizontal as well as vertical co-ordinates with normal process for error distribution. These coordinates were used for further detail survey.

## 2.2.5 L-Section and X-Section Survey

Longitudinal section levels were taken at every 25 m interval along the centre line of the existing carriageway. Cross sections were taken at every 50 m interval covering full extent of survey corridor with nos. of spot levels on the ground to give existing ground levels for widening purpose. Longitudinal section for cross roads was taken for a length of 100 m with adjacent spot levels of the ground on both sides to design intersections. Longitudinal and cross sections survey for major/minor streams was also carried out as per the requirements.

## 2.2.6 Detail Survey

The detailed field Surveys within road corridor was carried out using high precision and sophisticated instruments like Total Stations and Auto level. The output data from the topographical survey are in (x, y, z) format for use in a sophisticated digital terrain model (DTM). Road corridor was taken as 15m on either side of existing center line i.e. total width of 30m. Additional survey was carried out at the location of realignments and streams. Various features were recorded in x, y, z co-ordinates, along the existing road and also on both sides of the existing road within road

corridor. The features include ROW, existing carriageway, Km stones, buildings, structures, monuments, places of worship, railway lines, streams, rivers, canals, culverts, trees, plantations, utility services such as electric power lines, electric poles, telephone posts and telephone lines and cross roads etc. The recorded survey data were later downloaded to computer and converted to text files as well as AutoCAD drawings using appropriate software.

## **2.3 GEOTECHNICAL AND MATERIAL INVESTIGATIONS**

### **2.3.1 General**

This para covers the details of tests and investigations carried out for evaluating the characteristics of the sub-grade along the project road Berhampur to Taptapani on SH-17 (km 0/000 to km 41/000) to establish the basis for the design of various elements of the highway including pavement and sub-grade, embankment and structures.

In order to widening, strengthening and reconstruction of the roads and bridges, various kinds of materials shall be required. To identify potential sources of material for construction, the survey of following materials have been carried out in the months of Jan 06– Feb 06 in respect of their likely sources and the availability and suitability of various materials. This chapter includes detailed investigation of materials and their potential sources with the relevant laboratory tests conducted on representative samples as per IRC: SP -19.

The main tasks carried out for soil and material investigations include:

- i. Investigation for road for sub-grade soil below existing pavement for strengthening, widening and reconstruction design.
- ii. Investigation for construction materials including identification and inspection of potential sources of construction material and extraction sites, testing and evaluating of construction materials for suitability for project road construction.
- iii. Geotechnical investigation for bridges and other structures.

### **2.3.2 Investigation for road**

The detailed investigations include both field and laboratory testing. Test pits were excavated at the shoulder adjacent to pavement edge at interval of 1km. Fieldwork covered field density and in-situ moisture content test, sub-grade soil sampling, while laboratory tests included the determination of relevant engineering properties of the sub-grade soil.

The sub-grade soil samples were collected at each km along the existing alignment. For the roads along new alignments, the test pits for sub-grade soil have been excavated at every 1 km. The representative samples have been tested corresponding to each segment. The testing for sub-grade soil includes.

- i. Gradation (IS: 2720 (Part 5) – 2001)
- ii. Atterberg's Limits (IS: 2720 (Part 5) – 2001)
- iii. Modified Proctor Test (IS: 2720 (Part 8) – 2001)
- iv. California Bearing Ratio (CBR Soaked) (IS: 2720 (Part 16) – 2001)

- v. Field density and In-situ moisture content (IS:2720, Part XXIX & Part II)
- vi. Free Swell Index (IS: 2720, Part XXXX)

The results of the above field and laboratory investigations for various test pits are reported in Table 2.2 of Material Report – Part I, reproduced here also in Table 2.2.

**Table 2.2: Soil Investigation Data of Existing Subgrade**

Location (Km.)	Description of soil	Gradation: Percent by weight retained the Sieve (IS:2720-IV)				Clay and silt content %	Atterberg Limits [ IS :2720-Pt-V]			Modified Proctor Test (IS:2720-VIII)		Field dry density at subgrade level gm/cc	In-situ Moisture content %	CBR Soaked %	DFS	Group of soil (IS:1498)
		4.75 mm	2.0 mm	425 micron	75 micron		Liquid Limit (LL) %	Plastic Limit (PL) %	Plasticity Index (PI)	Max. dry density gm/cc.	OMC %					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
1/0	Clayey sand with silt & gravel	13.6	8.89	9.915	29.955	37.64	27	18	9	-	-	1.78	7.0	-	-	SC
2/0	Clayey sand with silt & gravel	8.6	17.195	14.625	22.95	36.63	26	17	9	1.98	9.5	1.72	9.2	9.2	-	SC
3/0	Silty clay with sand	4.175	5.285	11.095	27.19	52.355	32	18	14	1.84	15.05	1.71	13.7	6.2	28	CL
4/0	Clayey sand with silt	0.47	1.525	23.435	36.985	37.585	29	21	8	1.88	12.75	1.75	10.00	6.8	18	SC
5/0	Clayey sand with silt	0.3	0.735	14.76	47.11	37.095	30	22	8	-	-	1.80	11.40	-	-	SC
6/0	Sandy Clay with Silt	0.23	2.7	25.55	14.79	56.73	35	18	17	1.87	17.8	1.69	13.00	5.0	20	CI
7/0	Silty sand	0.435	4.685	25.17	40.36	29.35	21	NP	NIL	1.92	12.05	1.69	12.60	15.0	11	SM
8/0	Silty sand with clay	0	3.105	23.5	35.095	38.65	28	21	7	1.83	13.1	1.68	14.5	8.0	25	SM-SC
9/0	Sandy Clay with Silt	1.105	7.32	14.24	12.095	65.24	38	17	21	1.79	17.05	1.62	16.20	5.8	38	CI
10/0	Clayey sand with silt	3.715	6.62	22.38	31.92	35.365	33	22	11	1.88	10.2	1.75	12.50	8.5	27	SC
11/0	Silty sand with clay	3.265	6.105	22.95	31.37	36.31	29	22	7	1.84	12.95	1.78	13.50	9.2	26	SM-SC
12/0	Clayey sand with silt	0.52	7.07	21.565	24.135	46.71	30	19	11	-	-	1.69	14.75	-	-	SC
13/0	Clayey sand with silt	2.115	4.7	24.24	24.17	44.775	36	22	14	1.87	11.4	1.67	17.00	8.5	10	SC
14/0	Silty sand with clay	0.6	2.11	15.34	45.935	36.615	29	22	7	-	-	1.69	12.50	-	-	SM-SC

**Table 2.2: Soil Investigation Data of Existing Subgrade (Contd ...)**

Location (Km.)	Description of soil	Gradation: Percent by weight retained the Sieve (IS:2720-IV)				Clay and silt content %	Atterberg Limits [ IS :2720-Pt-V]			Modified Proctor Test (IS:2720-VIII)		Field dry density at subgrade level gm/cc	In-situ Moisture content %	CBR Soaked %	DFS	Group of soil (IS:1498)
		4.75 mm	2.0 mm	425 micron	75 micron		Liquid Limit (LL) %	Plastic Limit (PL) %	Plasticity Index (PI)	Max. dry density gm/cc.	OMC %					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
15/0	Silty sand with clay	0.845	1.66	17.71	40.525	39.26	29	23	6	1.82	11.86	1.61	14.00	8.9	27	SM-SC
16/0	Silty clay with sand	1.34	7.02	7.985	11.415	72.24	50	23	27	1.82	19.6	1.78	18.50	2.9	35	CH
17/0	Silty clay with sand & gravel	12.575	10.965	7.575	13.565	55.32	39	20	19	-	-	1.65	17.75	-	53	CI
18/0	Silty clay with sand	1.005	4.15	10.775	16.95	67.12	39	19	20	1.87	16.7	1.69	17.25	4.8	35	CI
19/0	Silty clay with sand	0	2.95	9.475	20.11	67.465	42	21	21	-	-	1.70	16.50	-	56	CI
20/0	Silty clay with sand	0.255	0.56	10.17	33.55	55.465	34	21	13	1.83	14.8	1.66	16.25	6.8	35	CL
21/0	Silty clay with sand	0.625	0.555	10.65	33.11	55.07	39	25	14	-	-	1.66	13.25	-	57	CI
22/0	Clayey sand with silt	3.105	12.315	19.855	24.885	39.84	30	20	10	1.85	12.25	1.74	15.25	6.8	21	SC
23/0	Clayey sand with gravel & silt	21.19	9.65	14.825	18.81	35.525	33	21	12	2.08	10.7	1.74	13.25	12.5	20	SC
24/0	Silty sand	2.925	13.585	26.24	26.25	31	20	NP	NIL	-	-	1.75	11.00	-	-	SM
25/0	Silty sand	5.025	12.52	27.585	25.55	29.32	21	NP	NIL	1.85	11.68	1.76	10.25	13.5	18	SM
26/0	Clayey sand with silt	0	0.41	31.98	28.1	39.51	29	19	10	-	-	1.78	8.25	-	-	SC
27/0	Silty sand	4.18	14.02	25.665	26.01	30.125	23	NP	NIL	-	-	1.82	7.50	-	-	SM
28/0	Silty clay with sand	0.6	1.8	11.077	30.16	56.364	34	23	11	1.88	15.3	1.72	13.25	8.5	10	CL

**Table 2.2: Soil Investigation Data of Existing Subgrade (Contd ...)**

Location (Km.)	Description of soil	Gradation: Percent by weight retained the Sieve (IS:2720-IV)				Clay and silt content %	Atterberg Limits [ IS :2720-Pt-V]			Modified Proctor Test (IS:2720-VIII)		Field dry density at subgrade level gm/cc	In-situ Moisture content %	CBR Soaked %	DFS	Group of soil (IS:1498)
		4.75 mm	2.0 mm	425 micron	75 micron		Liquid Limit (LL) %	Plastic Limit (PL) %	Plasticity Index (PI)	Max. dry density gm/cc.	OMC %					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
29/0	Silty clay with sand	0	0.96	10.17	30.86	58.01	33	21	12	1.85	15	1.77	13.50	7.6	-	CL
30/0	Silty clay with sand	0.12	0.79	12.84	30.235	56.025	34	22	12	-	-	1.74	15.50	-	-	CL
31/0	Silty sand	0	0.83	24.38	42.145	32.645	22	NP	NIL	-	-	1.77	8.50	-	-	SM
32/0	Silty sand	0.1	0.725	21.54	38.72	37.915	24	NP	NIL	1.88	10.88	1.68	9.7	14.8	-	SM
33/0	Clayey sand with silt	0	0.79	25.385	30.35	43.475	32	20	12	1.97	10.2	1.82	7.25	8.7	10	SC
34/0	Silty sand	0	0.645	21.01	44.53	33.815	21	NP	NIL	-	-	1.66	8.35	-	-	SM
35/0	Silty sand	0.12	0.82	21.885	44.62	32.555	18	NP	NIL	-	-	1.69	10.95	-	-	SM
36/0	Silty sand	0.08	1.065	22.06	43.615	33.18	20	NP	NIL	2.03	9.8	1.79	9.50	9.5	10	SM
37/0	Silty clay with sand & gravel	17.25	5.59	11.115	16.175	49.87	36	19	17	-	-	1.68	16.25	-	58	CI
38/0	Silty clay with sand & gravel	7.95	8.88	13.725	13.925	55.52	39	18	21	1.89	16.7	1.66	15.50	6.2	69	CI
39/0	Silty clay with sand & gravel	15.435	6.35	11.61	15.67	50.935	34	19	15	1.78	14.0	1.72	12.50	6	49	CL
40/0	Clay sand with sand & gravel	12.48	12.31	19.045	15.965	40.2	31	19	12	-	-	1.69	7.50	-	-	SC
41/0	Clay sand with sand & gravel	7.48	9.705	30.92	12.85	39.045	34	19	15	1.83	11.5	1.81	6.50	9.3	21.5	SC



## Discussion of Results

The soils in this stretch mainly classify in the group of SC / SM / CI /CL/SM-SC/CH and it is described as Silty Sand with Clay /Silty Sand / Silty clay with Sand/ Silty Clay. CL/CI/CH soil is low to high plastic and cohesive having CBR values (Soaked) ranging from 2.9% to 15 %. The maximum dry density at O.M.C. of the existing subgrade soil of CL/CI/CH group varies between 1.78 gm/cm<sup>3</sup> to 1.89 gm/cm<sup>3</sup>. In these sections PI value ranges from 17 to 25.0. The P.I. value is Nil in the case of Silty Sand soil of SM group. While the Clayey Sand with Silt (SC) soil is little plastic. In some kilometers, there are Expansive soils found with low to high degree of expansion. The treatments for such soils are discussed in the following Paragraph

### Expansive Soils and their Treatment

Low to high expansive soils of CL-CH group are found in various Sections of SH-17 i.e. km 3/0, 6/0, 9/0, 16/0 - 21/0, 28/0 – 30/0, and 37/0 – 39/0. Though, there are very few kilometers in such a long stretch of road section, it is always preferable either to replace the soil of high expansive properties or to treat the soil of low to medium expansive soils as below.

Thus to reduce the expansive properties of soil, firstly the expansive soil should be compacted slightly 1-2 % wet of the O.M.C and provide a buffer layer of non-expansive cohesive soil cushion of 0.6 – 1.0m thickness. It prevents the ingress of water in the underlying expansive soil layer, counteracts swelling and secondly even if the underlying expansive soil heaves, the movement will be more uniform and consequently more tolerable or it is recommended to either replace the soil by importing good soil from borrow area in the case of highly expansive soils. However where provision of non-expansive buffer layer is not economically feasible, a blanket course of suitable material and thickness as discussed below must be provided.

A blanket course of at least 225 mm thickness and composed of coarse/ medium sand or non-plastic Moorum having PI less than 5 should be provided on expansive soil subgrade as a sub-base to serve as an effective intrusion barrier. The blanket course should extend over the entire formation width together with measures for efficient drainage of the pavement section. Improvement of drainage can significantly reduce the magnitude of seasonal heaves.

### 2.3.3 Investigation for Construction Material

Samples of borrow area soils, sand, gravel and crushed rocks for use in embankment, pavement structure and concrete mix were obtained from the existing and proposed borrow sources / quarries within reasonably short haulage distances of the project road. Test pits were also excavated wherever necessary to obtain samples for testing.

Appropriate laboratory tests were carried out on the representative samples of soil and materials obtained during field investigations to determine relevant engineering properties. Following table gives the details of different material sources identified.

**Table 2.3: Sources of Construction Material**

S.No.	Material	No. of Sources Identified
1	Granular Sub base	4
2	Coarse Aggregate/ Stone	6
3	Sand / Fine Aggregate	3
4	Morrum	4
5	Cement	2
6	Water	3
7	Stone	6

**2.3.3.1 Sub-grade**

In this stretch, there was no soil available in borrow areas. The materials which can be used in sub-grade from borrow areas are sand and Moorum only. The representative samples were collected from each of the quarries and the laboratory tests were conducted to determine the suitability for construction.

**Identified Location of Sand Quarries:**

- i. Ballipada @ km 9/400
- ii. Nuagada @ km 32/0

**Identified Location of Moorum Quarries:**

- i. Fadiripalli @ km 7/0
- ii. Antei km @ 7/0
- iii. Ramchandrapur @ km 25/0
- iv. Podamiri Nanda Quarry @ km 38/0

The Tests results are tabulated in Table. 2.3 and 6.2 of Material Report Part-I and their suitability for subgrade was found out on the basis of these results.

**Discussion of Test results**

Sand in this stretch mainly found in km 9/400 (Ballipada River), and 32/0 (Nuagada River) which classified in the group of SM described as Silty Sand. The Silty Sand (SM) soil is non plastic and cohesion less. The Maximum Dry Density at O.M.C. of the existing subgrade soil of SM group varies between 1.82 gm/cm<sup>3</sup> to 2.03 gm/cm<sup>3</sup>. The sand from river borrow area is available in much quantity, also another alternative is either to use Moorrum mixed with sand, as subgrade material, which is abundantly available in this stretch. The various test results of samples collected from the Borrow areas are given in Table 2.3 & 6.2 (Refer Material Report – Part I).

**2.3.3.2 Granular Sub-base**

Along the Project corridor, six quarries were identified. The representative samples were collected from each of the quarries and the laboratory tests were conducted to determine the suitability for construction.

**Identified Location of Quarries:**

- i. Antei @ km 7/0
- ii. Ballipada @ km 9/400
- iii. Ramchandrapur @ km 25/0
- iv. Padaniri @ km 38/0

**Laboratory Tests Conducted:**

- i. Gradation (MoSRT&H)
- ii. Atterberg's Limits (IS: 2720 (Part 5) – 2001)
- iii. Modified Proctor Test (IS: 2720 (Part 8) – 2001)
- iv. California Bearing Ratio (CBR, Soaked) (IS : 2720 (Part 16) – 2002)

The Tests results are tabulated in Table. 4.1 and 4.2 of Material Report Part-I and their suitability for different type of works was found out on the basis of these results.

**Discussion of Test results**

The sub base material should have minimum CBR of 30% for traffic exceeding 2 MSA and 20% for traffic upto 2 MSA. The samples of Granular Sub Base materials were collected from various quarries along the Berhampur to Taptapani road. From the tests results it is clearly evident that in Berhampur to Taptapani road section, only two number of quarries named Antei (km 7/0), Ballipada ( km 9/400 ) have suitable GSB material having Liquid Limit and Plasticity Index value within the prescribe limit of MoSRT&H . For rest of quarries in which Liquid Limit and Plasticity Index is more than 25 and 6.0 respectively, blending of coarse grained sandy soil is suggested to lower down their Liquid limit and Plasticity Index within the prescribed limit. Quarries having CBR values less than 30% also need blending, and for rest of quarries blending of sand in required proportion is done and their revised tests results have been tabulated in Table 4.2 (Refer Material Report-Part I)

Therefore it shall be ensured prior to actual execution that the material to be used in the sub-base satisfies the requirements of CBR and other physical requirements.  
Coarse Aggregate:

**2.3.3.3 Coarse Aggregate/Stone**

Along the road section of SH-17, Berhampur to Taptapani, six quarries were found. The representative samples were collected from each of the quarries and the laboratory tests were conducted to determine the suitability for construction.

**Identified Location of Quarries:**

- i. Fadiripalli @ km 7 / 0
- ii. Antei @ km 7 / 0
- iii. RamchandraPur @ km 25/0
- iv. Chudanga Pur @ km 25/0
- v. Rajpur-Narendrapur @ km 40/0
- vi. Dasipur @ km 42/0

**Laboratory Tests Conducted:**

- i. Gradation (IS: 2386 (Part 1) – 2002 and MoSRT&H)
- ii. Aggregate Impact Value (IS: 2386 (Part 4) – 2002)
- iii. Specific Gravity & Water Absorption (IS: 2386 (Part 3) – 2002)
- iv. Combined Flakiness & Elongation Index (IS: 2386 (Part 1) – 2002)
- v. Stripping Value (IS : 6241 – 1971 Reaffirmed – 1998)

The Tests results are tabulated in Table 5.1 of Material Report Part-I and their suitability for different type of works is found out on the basis of these results.

**Discussion of Test Results**

The samples collected from various queries were tested in the laboratory. All the samples comply with the physical requirement of MoSRT&H specifications.

Their water absorption value ranges from 0.32 % to 1.02% and the combined Flakiness and Elongation Indices also comply with the physical requirements as per MoSRT&H specifications. The Impact values are in the range from 9% to 27% which is also well within the prescribed limits as per MoSRT&H. The aggregates from quarries do not conform exactly to the grading specified in the specification of MoSRT&H. Therefore; the blending as per the requirement should be done prior to mixing at plant. The stripping values of most of aggregate do not fulfill the requirements. For the aggregates whose stripping values do not fulfill the requirement then anti stripping agent should be used during execution as per the requirement. The tests results are given in Table 5.1. Refer Material Report – Part I)

Materials from quarries / crusher (aggregate) given in test results Table 5.1 (Refer Material Report – Part I) are suitable for WMM., Bituminous work and other construction works in accordance to MoSRT&H specifications.

**2.3.3.4 Sand / Fine Aggregate**

Sand/Fine Aggregate will be required for concrete work. Along the road section of SH-17, Berhampur to Taptapani, three quarries were found. The representative samples were collected from each of the quarries and the laboratory tests were conducted to determine the suitability for construction.

**Identified Location of Quarries:**

- i. Ballipada River Sand @ km 9/0
- ii. Gadagada River sand @ km 29/0
- iii. Nuagada, River sand @ km 32/0

**Laboratory Tests Conducted:**

- i. Gradation (IS: 383 – 2002)
- ii. Silt content and Fineness Modulus (IS: 383 – 2002)
- iii. Specific Gravity (IS: 2720 (Part 3) – 2002)
- iv. Deleterious content (IS: 2386 (Part 1) and IS: 383 – 2002)

The Tests results are tabulated in Table 6.1 (Refer Material Report Part-I) and their suitability for different type of works is found out on the basis of these results.

### **Discussion of Test results**

Sand sources are generally suitable for fine aggregate materials in Bituminous works and Concrete works but would require the removal of deleterious materials and Clay / Silt contents. From the Table 6.1 and 6.2 (Refer Material Report Part-I), it is evident that the Sand of Ballipada River is lies in zone I, and for rest of the sources the sand lies in Zone II, though test results shows that sand samples from other sources are also suitable for subgrade material as well as RCC / Masonry work

#### **2.3.3.5 Cement / Concrete**

##### **Cement**

Cement is made by branded manufacturers in the regions. In this region, Konark Slag Cement and Lafarge Cement are mainly in use for construction purpose. As cement is manufactured by branded companies and its testing is done on lot to lot basis regularly. Therefore, samples of these two types of cement were tested for the physical properties. The test results are tabulated in Table 7.1 and 7.2 (Refer Material Report-Part I).

##### **Concrete**

The concrete work shall consist of furnishing and placing structural concrete and incidental construction with these specifications and in conformity with the lines, grades and dimensions, as shown on the drawings or as directed by the Engineer. It is recommended that as the gradation and other physical properties of materials used in mix design vary site to site. Therefore fresh mix designs of the required grade should always be conducted before the construction starts and it should be checked at regular intervals during the phase of construction itself.

#### **2.3.3.6 Water**

Water used for mixing and curing shall be clean and free from injurious amounts of oils, acids, alkalis, organic materials or other substances that may be deleterious to concrete or steel. Potable water is generally considered satisfactory for mixing concrete. Mixing and curing with seawater shall not permit.

One sample of water from each road section of Berhampur to Taptapani (SH-17) was collected and tested for the suitability for use in construction as per IS: 456-( ). For test results refer Table 8.1 & 8.2 of Material Report-Part I.

From the given test results it is evident that these water samples are suitable for the construction purpose.

### **2.3.4 Investigation for Structures**

The main function of a foundation is to distribute or transmit all the loads coming over it to the soil or ground upon which it rests. The knowledge of the characteristics of underlying soil is therefore very essential for safe & economical design of foundations. The performance of supporting stratum depends upon the physical properties of soil, type & shape of footing & structure, water table depth etc.

It is therefore necessary to have sufficient information about the arrangement and behavior of the underlying materials and their physical properties, for adopting and designing the structural foundation. Soil exploration through field investigation and

relevant laboratory testing of the samples are essential to arrive at required parameter for designing of foundations.

#### 2.3.4.1 Sub soil exploration Test Locations

The Sub Soil explorations were carried out at locations as indicated in following table.

**Table 2.4: Sub Soil exploration Test Locations**

Location	Chainage	Nallah
1	1/915	Ambagada Nallah
2	11/270	Kanchi Nallah
3	29/500	Khajuri Nallah

Detailed information about the sub soil exploration investigations, characteristics of site, field investigation, laboratory tests, analysis, test results, bore hole details and conclusions refer Geo-Technical report of Bherampur to Bangi Jn (SH-17).

#### 2.3.4.2 Recommendations from Investigations:

**Table 2.5: Recommendations from Subsoil Investigations**

Location	Chainage	Type of foundation	Minimum Depth of Foundation
1	1/915	-	Recommended for Widening of Existing Bridge
2	11/270	Open	3.0m from bed level
3	29/500	Pile	13.5m from Ground level

## 2.4 HYDRAULIC AND HYDROLOGICAL INVESTIGATIONS

The Highway network in a project area crosses a number of rivers/ tributaries / streams / nallahs with small, medium or large catchment and therefore for design of bridges and other structures, hydrological parameters of these structures are essentially required. The design discharge has been calculated for a maximum 50-year return period as per IRC 5-1985, clause 103.

### 2.4.1 Design Discharge

For the calculation of discharge, following different methods have been used.

#### 2.4.1.1 Dicken's Formula

This is an empirical formula and is used for small catchments upto 25 to 30 sqkm.

$$Q = C * (M)^{3/4}$$

Where, Q = Peak runoff in cumecs

M = Catchment area in Sq.km.

C= Dicken's constant

= 11-14 where the annual rainfall is 600 mm to 1200 mm

= 14- 19 where the annual rainfall is more than 1200 mm

=22 in Western Ghats

### 2.4.1.2 Rational Formula

The rational formula for assessment of peak discharge from project catchment takes into account rainfall, runoff under various circumstances, time of concentration and critical intensity of rainfall. The formulas used are as under.

$$\text{One hour rainfall (I}_o\text{), } I_o = \frac{F}{T} \left( \frac{T+1}{1+1} \right)$$

$$\text{Time of concentration (SP-13, page 12), } t_c = \left( 0.87 \frac{L^3}{H} \right)^{0.385}$$

$$\text{Critical rainfall intensity } I_c = I_o \left( \frac{2}{t_c + 1} \right)$$

$$\text{Discharge } Q = 0.028 P A I_c$$

Where,

$t_c$  = Time of concentration i.e. time taken by runoff from farthest point on the periphery of catchment (hrs)

$I_o$  = One hour rainfall in cm.

$I_c$  = Critical intensity of rainfall in cm per hour

$P$  = Coefficient of runoff for the catchment characteristics (Ref. Table-4.1, P-13, I.R.C. SP: 13-2004)

$A$  = Catchment area in hectare

$Q$  = Maximum discharge in cumecs

$L$  = Distance from the critical point to the structure (Length of path) in Km

$H$  = The difference in level from the critical point to the structure in metre

$F$  = Maximum rain fall in mm

$T$  = Duration of storm in hours

$f$  = A fraction of maximum point intensity at the centre of the storm and related with the catchment area (Determined from Figure 4.2, Page-14, I.R.C.: SP: 13-2004.)

In the present study, storm rainfall and storm duration data of 50 –Year return period have been utilized from design flood hydrograph of near by project sites, developed on the basis of Hydro-meteorological studies as per Flood estimation reports of Mahanadi and Upper eastern coast sub-zones.

### 2.4.1.3 *Manning's Formula*

In this method cross sectional area and longitudinal slope of the stream is used to determine the velocity of flow and design discharge. Discharge has been calculated at three locations i.e. one near the proposed bridge site, one at u/s and one at d/s of the proposed bridge site.

$$V = \frac{1}{n} R^{\frac{2}{3}} S^{\frac{1}{2}}$$

$$Q = AV$$

Where

V = Velocity of flow

n = Manning's constant

R = A/P = Hydraulic mean radius

A = Cross sectional area of flow

P = Wetted perimeter

S = Longitudinal slope of stream

Q = Discharge

### 2.4.1.4 *Unit Hydrograph Method*

This method is used for estimating design flood peak and design flood hydrograph of desired frequency, knowing the physical/ physiographic characteristics of the catchment and reasonable design storm rainfall.

The regional flood estimation reports under long-term plan of 26 Sub-Zones in India are available. These reports have been formulated as a joint venture by the Ministry of Water resources through Central Water Commission, Research, and Designs & Standards Organization (RDSO) of Ministry of Railways, Ministry of Shipping & Transport (MoSRT&H) and India Meteorological Department (IMD) of Government of India. The reports pertaining to Orissa State are Sub-zone-III-d-Mahanadi basin and Sub-zone- IV-a- Upper Eastern coast.

In the absence of site-specific discharge data, which is generally the situation in case of small and medium catchments, the approach open is to evolve a regional frequency storm rainfall-loss-synthetic unit hydrograph model for a hydro-meteorological homogeneous region. The approach consists of working out regional Synthetic Unit hydrograph (SUG) parameters with pertinent physiographic characteristics from the recommended formulae in the particular Sub Zone flood estimation report, drawing and adjusting SUG, computation of design storm duration and point rainfall & areal rainfall, distribution of areal rainfall during design storm duration to obtain rainfall increments for unit duration intervals, assessment of effective rainfall units after subtraction of prescribed loss rate from rainfall increments, estimation of hourly rainfall excess, estimation of base flow and computation of 50-year peak flood and 50-year design flood hydrograph.

The step-by-step method has been described separately in Hydrology Report.



### 2.4.1.5 Fixing Design Discharge

Design discharge has been decided after comparing the discharge calculated from different methods as discussed above. Highest of these values has been adopted as design discharge, provided it does not the next highest discharge by more than 50%. If it exceeds, design discharge has been restricted to that limit.

### 2.4.2 Linear Waterway

Linear Waterway for a bridge structure is fixed from hydraulic and economic considerations with particular reference to:

- i. Design flood
- ii. Topography of the site
- iii. Existing and proposed section
- iv. Scour depth
- v. Permissible afflux, and
- vi. Construction and maintenance aspects

The linear water way/regime width (W) of a bridge across a purely alluvial stream in regime state as per IRC-SP-13.

$$W = 4.8Q^{1/2}$$

Where,

W= Liner waterway in metres

Q = Design flood discharge in cumecs.

### 2.4.3 Scour Depth

For the purpose of design of foundations, the design discharge as calculated above has been further increased as recommended in IRC:78-2000.

As per I.R.C:78-2000, Clause: 703.1.1, normal scour depth is given by

$$d_{sf} = d_{sm} = 1.34 \left( \frac{D_b^2}{K_{sf}} \right)^{1/3}$$

$D_b$ = Design discharge in cumecs/ metre

$$K_{sf} = K_{sf} = 1.76(d_m)^{1/2} = \text{silt factor}$$

$d_m$  = Weighted mean diameter of the particles in mm

Maximum scour depth for individual foundations without any floor protection works is given as

$$\text{For pier} = 2 * d_{sf}$$

$$\text{For abutments} = 1.27 * d_{sf}$$

## 2.4.4 Vertical clearance

As per IRC-SP:13, following vertical clearances have been kept.

**Table 2.6: Vertical Clearance**

Discharge in cumecs	Vertical clearance in m
Below 0.30	0.15
0.30 - 3.00	0.30
3.00 - 30.0	0.60
30.0 - 300.0	0.90
300.0 - 3,000.0	1.20
Above 3,000.0	1.50

## 2.4.5 Summary of Hydraulic Parameters

Detailed hydrology has been carried out at each of the bridge locations and presented in separate report. The abstract of hydraulic parameters are as under.

**Table 2.7: Hydraulic Parameters**

S. N.	Location/ Chainage	Existing Span Arrangement (no.x span)	Design Discharge (Cumec)	Existing Waterway (m)	Proposed Waterway (m)	Remarks
1	1/915	2 x 6.6	10.16	11.0	-	Widening required due to change of alignment
2	4/400	3 x 6.75	-	16.95	-	Good, Rehabilitation required
3	11/270	1 x 6.35	5.99	5.35	10.0	Reconstruction due to poor condition
4	11/660	3 x 6.8	20.15	17.4	-	Good, Rehabilitation required
5	15/185	2 x 6.8	25.60	11.6	-	Good, Rehabilitation required
6	15/680	4 x 6.8	64.53	23.2	-	Good, Rehabilitation required
7	17/900	4 x 6.8	149.34	23.2	-	Good, Rehabilitation required
8	21/850	3 x 10.8	94.58	29.25	-	Good, Rehabilitation required
9	29/230	3 x 42.2	2442.01	123.6	-	Good, Nothing to do
10	29/500	2 x 7.0	28.21	11.6	20.0	Reconstruction due to realignment

## 2.5 INVESTIGATION FOR BRIDGES AND STRUCTURES

### 2.5.1 General

The total stretch of Berhampur to Taptapani is 41 km on SH-17. The detailed study has been undertaken for the culverts & bridges. The detailed study consists of:

- Inventory of culverts & bridges.
- Condition assessment of existing culverts & bridges.
- Additional cross drainage structures as per detailed site investigation.
- Construction of new bridge on same alignment because,

- a. Existing bridge is narrow and dilapidated.
- b. Hydrological study and local data indicates bridge getting overtopped frequently.
- v. Possibility of widening the bridges to the required width if structural, hydrological considerations would so permit.
- vi. Retaining the existing bridges with
  - a. Touchup repairs if the prevailing structural and hydrological considerations are adequate.
  - b. Touchup repair and scour protection measures, structural conditions are all right but hydraulic conditions are not met.

### 2.5.2 Inventory of Bridges and Culverts

The culvert and bridge inventory was undertaken by actual study, site visit, measurements and visual inspections. It was supplemented by survey and detailed investigations by the experienced team. After preparing draft inventory and condition survey report, joint verification was carried along with PIU Engineers. Necessary corrections as observed during site visit were incorporated. The final report after incorporating decisions taken during joint site visit was submitted to PIU. The detailed inventory and condition survey report along with recommendations has also been submitted in Feasibility Report.

Bridge Inventory broadly covers the following features.

- i. Location of bridge
- ii. Name of bridge or nallah
- iii. Span arrangement
- iv. Width of carriageway
- v. Type of bridge
- vi. Type of foundation
- vii. Skew angle
- viii. Type of superstructure & substructure
- ix. Condition of superstructure & substructure
- x. Condition of bearings, expansion joint, approach slab, drainage spout etc.

The format prescribed in SP-19 has been enhanced to accommodate additional features such as wearing coat, expansion joint and railing condition, floor protection and approach slab.

There are total 10 bridges, 1 of them is major and remaining 9 are minor bridges. The abstract of bridge inventory is presented in Table 2.8.

Culvert Inventory covers the following features.

- i. Location of culvert
- ii. Span arrangement

- iii. Type of structure
- iv. Width of carriageway
- v. Material of abutment & headwall
- vi. Condition of slab & pipe
- vii. Condition of abutment & headwall
- viii. Protection of bed
- ix. Presence of scour
- x. Hydrological adequacy

There are total 142 culverts, 41 of them are Pipe culverts, 51 are RCC slab culverts, 24 are stone slab culverts, 11 are arch culverts and 15 are in choked condition. The abstract of culvert inventory is presented in Table 2.10.

### **2.5.3 Condition surveys for bridges and culverts**

#### **2.5.3.1 Bridges**

Detailed visual inspections were carried out in addition to Non-Destructive Tests (NDT). Special attention was paid to the Condition Survey of various features of bridges and hydraulic adequacy. The NDT (Rebound hammer and Ultrasonic pulse velocity and corrosion test by half cell potential meter) tests were conducted for bridges at Chainage 11/660 and 17/900 to study the structural soundness of the structures. Some of photographs showing NDT tests are presented in Plate 1.

There are total 10 bridges. Analytical study of the Condition Survey data has been carried out and following important conclusions are arrived:

- i. Approach slab of 150 mm thick has been provided in most of the bridges as per the Existing bridge drawing received.
- ii. Mastic asphalt in case of bituminous concrete wearing coat has not been provided in any bridge.
- iii. The condition of the expansion joints in most of the bridges is poor.
- iv. Bridge at Ch 11/270 is narrow having 5.0m carriageway width, not in good condition, has been recommended for reconstruction.
- v. Bridge at Ch 29/500 is narrow in width and in poor condition has been recommended for reconstruction.
- vi. Bridge at Ch. 4/400 is meant for canal crossing.
- vii. Bridge at Ch. 11/660 is RR stone masonry bridge with reinforcement exposed in slab.

The abstract of inventory and condition of the existing bridge studies along with the recommendations is presented in Table 2.8 and summary at a glance has been presented in Table 2.9.

The photographs showing NDT tests are shown in Plate 1. The Photographs of some of bridges to be dismantled is presented in Plate 2 and for rehabilitation in Plate 3.

**Table 2.8: Inventory and Condition of Existing Bridges**

Sl. No.	Location/Chainage	Existing Span Arrangement	Type of Superstructure	Type of foundation	Overall condition/ Recommendation
1	1/915	2 x 6.6	Solid Slab	Open foundation	Good, Rehabilitation required
2	4/400	3 x 6.75	Solid Slab	Open foundation	Good, Rehabilitation required
3	11/270	1 x 6.35	Iron Joist with Solid Slab	Open foundation	Reconstruction due to poor condition
4	11/660	3 x 6.8	Solid Slab	Open foundation	Rehabilitation required
5	15/185	2 x 6.8	Solid Slab	Open foundation	Good, Rehabilitation required
6	15/680	4 x 6.8	Solid Slab	Open foundation	Good, Rehabilitation required
7	17/900	4 x 6.8	Solid Slab	Open foundation	Good, Rehabilitation required
8	21/850	3 x 10.8	Solid Slab	Open foundation	Good, Rehabilitation required
9	29/230	3 x 42.2	PSC girder with Deck slab	Well foundation	Good, Nothing to do
10	29/500	2 x 7.0	RCC girder with Deck slab	Open foundation	Reconstruction due to narrow in width and poor condition

**Table: 2.9 Summary of Existing Bridges**

Type of Action Required	No.
Nothing to do cases	1
Rehabilitation cases	7
Replaced due to Poor condition	2
Replaced due to Submersible condition	Nil

**Plate 1****Photographs of some of bridges showing NDT****Pulse velocity Test in deck slab for bridge at Ch. 11/270****Pulse velocity Test for bridge at CH. 17/900****Rebound Hammer testing for bridge at Ch. 17/900**

**Plate 2**

**Photographs of bridges to be dismantled**



**Bridge at Ch:11/270**



**Bridge at Ch:11/270**



**Bridge at Ch:29/500**



**Plate 3**

**Photographs of some of bridges to be rehabilitated**



**Bridge at Ch:4/400**



**Bridge at Ch:15/185**



**Bridge at Ch:21/850**



### 2.5.3.2 Culverts

Detailed visual inspection was made for each Culvert and their condition was assessed. The inventory and condition survey of the culverts along the project road were conducted.

Analytical study of the Condition Survey data has been carried out and following important conclusions are arrived:

- i. The total numbers of culverts are 142 in a road length of from km 0/0 to 41/0 i.e. in a stretch of 41.00 km.
- ii. Most of the culverts do not meet the considerations of maintenance of culverts (minimum vent size) as specified in IRC: SP-13- 2004, para 13.3.2.
- iii. Most of the CD culverts are having overall width less than 12 m. These culverts have been widened if horizontal and vertical profile permits.
- iv. Return walls, Head walls or parapet walls of most of the culverts are damaged and proposed to be reconstructed in case the culvert condition is good and alignment permits.
- v. 65 Nos of culverts are RR stone masonry with RCC deck slab out of 76 slab culverts in poor condition and most of them have been proposed to be reconstructed.
- vi. Most of the culverts have been provided without any protection works.
- vii. 24 culverts with stone slab deck have been recommended for reconstruction.
- viii. Culverts at Ch.10/470,10/510,13/250,18/350 & 24/560 are suggested to be abandoned as they are not required as per the site condition.

The following table presents abstract of inventory and condition of existing culverts along with the recommendation.

**Table 2.10: Inventory and Condition of Existing Culverts**

Sl. No.	Location/ Chainage	Existing Span Arrangement	Type of Culvert	Recommendation
1	0/190	-	Choked	Replaced due to insufficient vent
2	0/350	1 x 1.75	Slab	To be widened
3	0/830	1 x 2.0	Slab	To be widened
4	0/950	-	Choked	Replaced due to insufficient vent
5	1/150	1 x 1.5	Slab	Replaced due to poor condition
6	1/310	1 x 1.5	Slab	To be widened
7	1/785	1 x 1.5	Slab	Replaced due to poor condition
8	2/140	1 x 1.5	Slab	Replaced due to poor condition
9	2/285	1 x 1.5	Slab	Replaced due to insufficient vent
10	2/515	3 x 0.9	Slab	Replaced due to poor condition
11	2/630	1 x 1.5	Slab	To be widened
12	2/745	1 x 2.5	Slab	To be widened
13	3/105	1 x 0.5	Stone Slab	Replaced due to poor condition
14	3/265	1 x 0.8	Pipe	To be widened
15	3/390	1 x 1.4	Slab	Replaced due to poor condition
16	3/505	1 x 2.5	Slab	Nothing to do
17	3/775	1 x 0.7	Stone Slab	Replaced due to poor condition
18	3/895	1 x 0.7	Stone Slab	Replaced due to insufficient vent
19	4/115	1 x 1.5	Slab	To be widened
20	5/145	1 x 1.5	Slab	To be widened
21	5/230	1 x 0.5	Stone Slab	Replaced due to poor condition
22	5/535	2 x 1.5	Arch	Replaced due to poor condition
23	5/775	1 x 2.5	Slab	Replaced due to poor condition
24	6/090	1 x 0.8	Pipe	Replaced due to poor condition
25	6/555	-	Choked	Replaced due to insufficient vent
26	6/590	1 x 0.5	Stone Slab	Replaced due to poor condition
27	7/020	1 x 0.5	Stone Slab	Replaced due to poor condition
28	7/240	1 x 0.8	Pipe	Replaced due to poor condition
29	7/540	1 x 0.5	Stone Slab	Replaced due to poor condition
30	7/630	1 x 1.5	Slab	Nothing to do
31	7/795	1 x 1.5	Slab	Nothing to do
32	8/030	1 x 2.0	Slab	Nothing to do
33	8/210	2 x 1.0	Pipe	Replaced due to poor condition
34	8/385	1 x 0.5	Stone Slab	Replaced due to poor condition
35	8/550	1 x 3.0	Slab	Replaced due to poor condition
36	8/700	-	Choked	Replaced due to insufficient vent
37	9/175	1 x 1.5	Slab	Nothing to do
38	9/600	1 x 0.5	Stone Slab	Replaced due to poor condition
39	9/810	1 x 1.5	Slab	Nothing to do
40	10/370	-	Choked	Replaced due to insufficient vent
41	10/470	-	Choked	To be abandoned
42	10/510	-	Choked	To be abandoned
43	10/965	2 x 1.5	Slab	To be widened
44	11/120	1 x 0.9	Arch	Replaced due to poor condition
45	11/500	1 x 1.5	Slab	Replaced due to poor condition
46	12/040	2 x 0.8	Pipe	To be widened
47	12/380	1 x 1.0	Pipe	Replaced due to poor condition
48	12/585	1 x 0.8	Pipe	Replaced due to poor condition
49	12/810	3 x 1.2	Pipe	Replaced due to poor condition
50	12/880	1 x 0.9	Pipe	Nothing to do
51	13/110	1 x 0.5	Stone Slab	Replaced due to poor condition
52	13/250	-	Choked	To be abandoned
53	13/265	1 x 1.5	Slab	Replaced due to poor condition

Sl. No.	Location/ Chainage	Existing Span Arrangement	Type of Culvert	Recommendation
54	13/450	1 x 3.0	Slab	Nothing to do
55	13/600	1 x 0.8	Pipe	Replaced due to poor condition
56	13/790	1 x 1.2	Pipe	Replaced due to poor condition
57	13/895	1 x 1.0	Pipe	To be widened
58	14/135	1 x 3.0	Slab	To be widened
59	14/510	1 x 0.6	Pipe	Replaced due to insufficient vent
60	14/855	1 x 1.5	Slab	Replaced due to poor condition
61	15/430	1 x 0.6	Pipe	Replaced due to insufficient vent
62	15/880	NV	Pipe	Replaced due to insufficient vent
63	16/050	1 x 0.8	Pipe	Replaced due to insufficient vent
64	16/400	1 x 2.3	Slab	Replaced due to poor condition
65	16/505	1 x 0.8	Pipe	Replaced due to poor condition
66	16/750	NV	Pipe	Replaced due to insufficient vent
67	16/950	1 x 0.6	Pipe	Replaced due to submergence
68	17/650	1 x 0.9	Pipe	Replaced due to poor condition
69	18/020	2 x 1.7	Slab	To be widened
70	18/105	1 x 1.0	Slab	Replaced due to poor condition
71	18/350	-	Choked	To be abandoned
72	18/470	1 x 0.6	Stone Slab	Replaced due to poor condition
73	19/240	1 x 0.9	Slab	Replaced due to poor condition
74	19/430	1 x 0.6	Slab	Replaced due to poor condition
75	19/570	1 x 1.5	Slab	To be widened
76	19/845	1 x 1.0	Pipe	To be extended
77	20/355	1 x 0.8	Pipe	Replaced due to poor condition
78	20/610	1 x 0.5	Slab	Replaced due to insufficient vent
79	20/930	1 x 0.8	Pipe	Replaced due to poor condition
80	21/015	1 x 0.5	Stone Slab	Replaced due to insufficient vent
81	21/230	1 x 0.45	Pipe	Replaced due to insufficient vent
82	21/420	1 x 1.0	Pipe	Replaced due to poor condition
83	21/875	1 x 1.2	Pipe	To be extended
84	22/210	1 x 0.6	Pipe	Replaced due to insufficient vent
85	22/605	1 x 1.6	Slab	To be widened
86	22/790	1 x 1.0	Pipe	To be extended
87	22/985	1 x 0.9	Stone Slab	Replaced due to poor condition
88	23/180	1 x 0.7	Stone Slab	Replaced due to insufficient vent
89	23/300	-	Choked	Replaced due to insufficient vent
90	23/515	1 x 0.3	Pipe	Replaced due to insufficient vent
91	23/750	-	Choked	Replaced due to insufficient vent
92	23/850	1 x 1.5	Slab	To be widened
93	24/365	1 x 0.6	Pipe	Replaced due to insufficient vent
94	24/560	-	Choked	To be abandoned
95	24/650	1 x 1.5	Slab	Replaced due to poor condition
96	24/1020	1 x 1.8	Arch	Replaced due to poor condition
97	25/050	1 x 4.7	Slab	To be widened
98	25/695	1 x 1.85	Slab	Replaced due to poor condition
99	25/905	1 x 0.95	Arch	Replaced due to poor condition
100	26/150	1 x 0.5	Stone Slab	Replaced due to insufficient vent
101	26/430	1 x 3.1	Slab	Replaced due to poor condition
102	26/850	1 x 1.0	Arch	Replaced due to poor condition
103	27/600	1 x 0.8	Pipe	Replaced due to poor condition
104	27/850	1 x 0.65	Stone Slab	Replaced due to insufficient vent
105	28/375	-	Choked	Replaced due to insufficient vent
106	28/800	3 x 1.2	Pipe	Replaced due to insufficient vent
107	30/060	1 x 3.0	Slab	To be widened
108	30/460	1 x 0.8	Pipe	Replaced due to poor condition
109	30/720	1 x 1.8	Slab	To be widened

Sl. No.	Location/ Chainage	Existing Span Arrangement	Type of Culvert	Recommendation
110	31/960	1 x 0.8	Stone Slab	Replaced due to poor condition
111	32/300	NV	Pipe	Replaced due to insufficient vent
112	33/220	1 x 1.5	Slab	Replaced due to poor condition
113	33/310	1 x 1.6	Slab	Replaced due to poor condition
114	33/806	NV	Pipe	Replaced due to insufficient vent
115	33/900	1 x 0.8	Pipe	Replaced due to insufficient vent
116	34/250	1 x 0.8	Pipe	Replaced due to insufficient vent
117	34/525	1 x 2.9	Slab	Replaced due to poor condition
118	34/640	2 x 0.9	Pipe	Replaced due to insufficient vent
119	34/675	1 x 2.1	Arch	Replaced due to poor condition
120	35/204	1 x 0.5	Stone Slab	Replaced due to insufficient vent
121	35/350	1 x 0.5	Stone Slab	Replaced due to insufficient vent
122	35/825	1 x 0.5	Stone Slab	Replaced due to insufficient vent
123	36/060	1 x 0.5	Stone Slab	Replaced due to insufficient vent
124	36/220	-	Choked	Replaced due to insufficient vent
125	36/500	1 x 0.6	Pipe	Replaced due to poor condition
126	36/575	1 x 0.8	Pipe	Replaced due to poor condition
127	36/800	NV	Pipe	Replaced due to insufficient vent
128	36/990	1 x 0.5	Stone Slab	Replaced due to insufficient vent
129	37/440	1 x 0.8	Arch	Replaced due to poor condition
130	37/985	1 x 0.5	Stone Slab	Replaced due to insufficient vent
131	38/450	1 x 1.5	Slab	To be widened
132	38/600	1 x 1.5	Slab	Replaced due to poor condition
133	38/810	NV	Choked	Replaced due to insufficient vent
134	38/960	1 x 0.8	Arch	Replaced due to poor condition
135	39/195	1 x 1.8	Arch	Replaced due to poor condition
136	39/340	1 x 3.2	Slab	To be widened
137	39/455	1 x 0.8	Arch	Replaced due to poor condition
138	39/900	1 x 0.85	Arch	Replaced due to poor condition
139	40/100	1 x 1.35	Slab	Replaced due to poor condition
140	40/240	2 x 0.45	Stone Slab	Replaced due to insufficient vent
141	40/420	1 x 1.5	Slab	Replaced due to poor condition
142	40/815	1 x 1.5	Slab	Replaced due to poor condition

Table 2.11: Summary of Existing Culverts

Type of Culvert	Nos.
Pipe	41
Slab	51
Stone slab	24
Choked	15
Arch	11
<b>Total</b>	<b>142</b>

## 2.6 PAVEMENT INVESTIGATIONS

This section describes the studies and investigations carried out on existing pavement condition to determine the most technically sound and economically feasible pavements design. The investigations include:

- i. Visual Inspection Survey
- ii. Pavement Composition.
- iii. Roughness Survey

iv. Benkelman Beam Deflection Survey

### **2.6.1 Visual Inspection Survey**

The Visual Inspection Survey was carried out for the entire stretch under consideration. The parameters observed in this Survey were:

- i. Type of surface
- ii. Types of cracks (alligator/block/transverse/longitudinal) and its area.
- iii. Pot holes, raveling and patching areas
- iv. Shoulder condition
- v. Rutting (measured with a 3 meter long straight edge).


The detailed field studies were carried out in respect of pavement condition. The data collected through pavement investigations are presented in Table 2.12, graphical representation of the same is presented in Figures 2.1 to 2.5 shall be sufficient to meet the input requirements of HDM- IV.

Table 2.12: Pavement condition


CHAINAGE		Riding Quality		Pavement Condition											Remarks
From (KM)	To (KM)	Speed (km/hr)	Quality G/F/P/VP	Cracking (%)	Ravelling (%)	Pothole (Nos)	Potholing (%)	Rut**** (None / Moderate / Severe)	Patching (Nos) **	Patching (%)	Pavement Edge drop (mm)	Embankment Condition (G/F/P)	Embankment Height	Road side Drain (NE/PF/F)***	
0/0	1/0	30	G	-	0.1	-	-	None	-	-	15	F	1.3	F	Under New Construction upto Km-25/000
1/0	2/0	30	P	2	-	30	2.0	None	27	2.0	10	F	1.6	F	
2/0	3/0	30	VP	2	1.5	35	2.0	None	27	2.0	-	F	1.8	F	
3/0	4/0	30	VP	-	2.0	15	0.3	None	4	0.2	5	F	1.8	PF	Edge Damage
4/0	5/0	30	G	-	0.1	-	-	None	-	-	5	F	0.2	NE	
5/0	6/0	30	VP	4	2.5	31	2.0	None	18	3.0	7	F	1.0	NE	Edge Damage
6/0	7/0	30	P	-	1.5	35	2.0	None	17	3.0	10	F	0.3	NE	Edge Damage
7/0	8/0	30	P	-	1.5	69	3.0	None	22	3.0	10	F	1.5	NE	Edge Damage
8/0	9/0	30	P	-	2.0	24	1.0	None	18	3.0	10	F	2	NE	Edge Damage
9/0	10/0	30	F	-	0.5	13	0.5	None	9	1.0	10	F	0.8	NE	
10/0	11/0	30	F	-	0.3	6	0.2	None	5	0.5	10	F	1.0	NE	
11/0	12/0	30	P	-	2.0	-	-	None	68	7.0	10	F	1.2	NE	
12/0	13/0	30	G/F	-	-	-	-	None	-	-	12	F	1.2	NE	
13/0	14/0	30	G	-	-	-	-	None	-	-	15	F	1.3	F	
14/0	15/0	30	G	-	-	-	-	None	-	-	12	F	1.3	PF	
15/0	16/0	30	G	-	-	-	-	None	-	-	25	F	1.5	PF	
16/0	17/0	30	VP	-	1.5	22	1.0	None	92	10.0	10	F	1.2	F	Edge Damage
17/0	18/0	30	VP	-	2.0	28	1.0	None	42	4.0	10	F	1.5	PF	Edge Damage
18/0	19/0	30	VP	-	2.0	78	3.0	None	45	5.0	5	-	1.0	F	Edge Damage
19/0	20/0	30	VP	-	2.0	92	4.0	None	37	3.0	5	P	1.5	F	Edge Damage
20/0	21/0	30	VP	-	2.0	83	3.5	None	10	1.0	5	P	1.5	PF	Edge Damage
21/0	22/0	30	F	-	0.3	6	0.1	None	-	-	10	F	2.0	NE	Edge Damage
22/0	23/0	30	VP	-	1.5	8	0.2	None	14	1.5	10	F	1.5	F	Edge Damage
23/0	24/0	30	VP	-	2.0	7	0.2	None	15	1.5	20	P	1.2	PF	Edge Damage
24/0	25/0	30	P	-	1.0	78	3.0	None	12	1.0	5	P	1.2	PF	Edge Damage

Table 2.12: Pavement condition (Contd ...)

CHAINAGE		Riding Quality		Pavement Condition											Remarks
From (KM)	To (KM)	Speed (km/hr)	Quality G/F/P/VP	Cracking (%)	Ravelling (%)	Pothole (Nos)	Potholing (%)	Rut**** (None / Moderate / Severe)	Patching (Nos)**	Patching (%)	Pavement Edge drop (mm)	Embankment Condition (G/F/P)	Embankment Height	Road side Drain (NE/PF/F)***	
25/0	26/0	30	P	-	2.0	52	3.0	None	17	1.5	20	F	1.0	NE	Edge Damage
26/0	27/0	30	P	-	0.8	31	2.0	Moderate	25	2.0	25	F	0.9	F	Edge Damage
27/0	28/0	30	P	-	0.2	27	1.5	None	24	2.0	25	F	1.2	F	Edge Damage
28/0	29/0	30	P	-	0.1	32	2.0	None	20	2.0	20	P	1.5	F	Edge Damage
29/0	30/0	30	P	-	0.5	13	0.5	None	38	3.0	35	F	1.2	PF	
30/0	31/0	30	P	-	2.0	33	2.0	None	48	5.0	30	F	1.1	F	Edge Damage
31/0	32/0	30	VP	-	3.0	44	3.0	None	37	3.0	20	F	0.5	F	Edge Damage
32/0	33/0	30	P	7	3.0	73	4.0	None	58	6.0	10	F	0.4	PF	Edge Damage
33/0	34/0	30	VP	2	3.0	88	5.0	None	85	8.0	25	P	0.8	PF	Edge Damage
34/0	35/0	30	VP	2	0.5	97	5.0	None	46	5.0	20	P	0.5	PF	Edge Damage
35/0	36/0	30	VP	5	1.0	83	4.5	None	38	3.0	25	F	0.7	F	Edge Damage
36/0	37/0	30	F	-	0.2	17	0.8	None	24	2.0	7	F	1.5	PF	
37/0	38/0	30	P	4	3.0	31	2.0	None	35	3.5	35	F	1.2	PF	Edge Damage
38/0	39/0	30	VP	2	4.0	22	1.0	None	12	1.0	20	F	1	PF	Edge Damage
39/0	40/0	30	P	1	1.5	78	4.0	None	27	3.0	40	F	1.7	PF	Edge Damage
40/0	41/0	30	G	-	-	-	-	None	-	-	5	F	1.8	PF	




**Figure 2.1: Cracking (%) Variation along the stretch**




**Figure 2.2: Raveling (%) Variation along the stretch**





**Figure 2.3: Potholing (%) Variation along the stretch**



**Figure 2.4:Patching (%) Variation along the stretch**

## 2.6.2 Pavement Composition

The test pits were made to ascertain the pavement composition. The Test Pits measuring 1m x 1m in plan were made at every 1 km interval (Staggered Left/Right) or at each major change in the pavement condition, whichever is less. The specification for making good the excavated pavement would be, by sand filling up to top level of sub grade followed by PCC in M-15 grade equal to road crust thickness.

For each test pit, the following information has been recorded:

- i. Test pit reference (Identification number, location);
- ii. Pavement composition (material type and thickness);
- iii. Sub-grade type (textural classification) and condition (dry, wet)

The pavement composition has been shown in Table 2.13. Pavement sub-grade characteristics have already been discussed in section 2.3.2

**Table 2.13: Pavement composition**

Chainage		Wear- ing Course (mm)	Base Course (mm)	Sub- base course (mm)	Total Thickness (mm)	Chainage		Wear- ing Course (mm)	Base Course (mm)	Sub- base course (mm)	Total Thickness (mm)
From	To					From	To				
0	1	75	150	150	375	21	22	30	150	160	340
1	2	75	160	140	375	22	23	30	200	150	380
2	3	75	160	150	385	23	24	40	190	140	370
3	4	30	100	200	330	24	25	40	160	140	340
4	5	40	150	150	340	25	26	30	170	150	350
5	6	40	160	150	350	26	27	30	180	110	320
6	7	40	180	150	370	27	28	30	150	150	330
7	8	60	250	100	410	28	29	30	170	150	350
8	9	30	200	140	370	29	30	30	190	150	370
9	10	30	170	160	360	30	31	30	170	180	380
10	11	20	180	130	330	31	32	30	160	170	360
11	12	20	200	140	360	32	33	30	200	120	350
12	13	30	170	150	350	33	34	35	170	150	355
13	14	20	180	160	360	34	35	30	200	140	370
14	15	30	160	160	350	35	36	30	150	150	330
15	16	30	200	110	340	36	37	30	180	150	360
16	17	30	200	100	330	37	38	30	160	140	330
17	18	20	150	150	320	38	39	35	160	150	345
18	19	70	160	150	380	39	40	30	160	150	340
19	20	40	170	140	350	40	41	30	190	120	340
20	21	30	180	140	350						

## 2.6.3 Roughness Survey

For assessment of roughness, reported in terms of unevenness index (UI), the locations identified on the carriageway were left and right wheel paths. Average of the values along left and right wheel paths were taken as the measure of unevenness index for the carriageway. Based on the IRC recommendations of roughness, the riding quality of the pavement has been determined in terms of Pavement Serviceability Rating (PSR) also.

The roughness surveys have been carried out using Bump Integrator. The calibration of the instrument has been done as per the procedure given in the World Bank's Technical Publications and duly got authenticated by CRRI. The surveys have been carried out along the left and right wheel paths. The surveys have covered a minimum of two runs along the wheel paths for each direction.

The results of the survey have been expressed in terms of UI and IRI are presented in Table 2.14.

**Table 2.14: Roughness Value in IRI**

Chainage		Avg.UI (mm/Km)	IRI Value (m/Km)	Chainage		Avg.UI (mm/Km)	IRI Value (m/Km)
From	To			From	To		
0	1	3010	2.822	21	22	3090	2.887
1	2	2420	2.337	22	23	8760	7.546
2	3	8840	7.612	23	24	6740	5.886
3	4	9390	8.064	24	25	5760	5.081
4	5	3680	3.372	25	26	6760	5.903
5	6	7890	6.831	26	27	6040	5.311
6	7	7750	6.716	27	28	6020	5.295
7	8	8730	7.522	28	29	5680	5.015
8	9	8580	7.398	29	30	5320	4.720
9	10	7930	6.864	30	31	7960	6.889
10	11	3830	3.495	31	32	8140	7.037
11	12	7770	6.733	32	33	5490	4.859
12	13	3720	3.405	33	34	8560	7.382
13	14	3830	3.495	34	35	7290	6.338
14	15	2990	2.805	35	36	5910	5.204
15	16	3710	3.397	36	37	3770	3.446
16	17	8760	7.546	37	38	8180	7.070
17	18	8710	7.505	38	39	8370	7.226
18	19	10840	9.255	39	40	7630	6.618
19	20	9140	7.859	40	41	3515	3.236
20	21	8130	7.029				

## 2.6.4 Benkelman Beam Deflection Survey

The structural strength survey was carried out for existing pavements using Benkelman Beam Deflection technique in accordance with the CGRA procedure given in IRC:81-1997 ("Guidelines for Strengthening of Flexible Road Pavements Using Benkelman Beam Deflection Technique"). During the course of the testing, checks of axle load and tyre pressure were made at frequent intervals. Deflection measurements were performed at 100 m interval for the total stretch covered under the study.

Details of BBD survey were presented in volume IV, Annexure to chapter 6 (6.5) of Appendices to Feasibility Report. The summary of BBD survey is presented in Table 2.15.

**Table 2.15: Characteristic Deflections**

Chainage		Characteristic Deflection	Chainage		Characteristic Deflection
From	To		From	To	
0	1	6.00	21	22	3.56
1	2	6.01	22	23	4.51
2	3	5.97	23	24	6.56
3	4	4.44	24	25	1.62
4	5	5.17	25	26	5.63
5	6	4.18	26	27	5.93
6	7	4.31	27	28	2.51
7	8	3.74	28	29	3.39
8	9	3.32	29	30	2.52
9	10	12.08	30	31	2.08
10	11	1.90	31	32	1.41
11	12	2.85	32	33	5.47
12	13	2.85	33	34	4.52
13	14	3.21	34	35	4.50
14	15	2.43	35	36	2.98
15	16	4.28	36	37	1.99
16	17	3.79	37	38	4.62
17	18	3.48	38	39	3.09
18	19	3.06	39	40	2.58
19	20	2.54	40	41	4.30
20	21	3.93			

## 2.7 ROAD SAFETY REVIEW

### 2.7.1 General

Traffic Safety is an important aspect of a road project. It is a matter of deep concern that in India, deaths in road accidents every year are more than all other types of accidental deaths taken together like drowning, industrial accidents, poisoning, fire, railway accidents and even natural calamities etc. India is a developing country and safety of roads is still in a premature stage. Not much importance is given to road safety in most of our roads.

The existing single lane to intermediate lanes has been proposed to be widened to two lanes to decongest and to provide a high-speed corridor for the movement of passenger and goods traffic. Considerations have been given to a safe design of the road components to reduce accident involving both human and vehicles. Some of the important design considerations are listed below,

- i. Higher operating speed of the vehicles
- ii. Road geometric components
- iii. Partial access control
- iv. High standards of traffic safety
- v. Efficient and effective road signage schemes
- vi. Appropriate road safety structures

Improved roads minimize the occurrence of accidents and reduce the accident cost. Thereby making the proposed facility more safe and user friendly to traffic.

Traffic on the Project Roads is mixed traffic comprising fast moving cars/ buses/ coaches to slow moving agricultural tractors, 3-wheelers and bi-cycles plus pedestrians and farm animals all moving along. The Project Roads have not pedestrian lane or cycle tracks to accommodate this traffic in the built up-sections.

The road geometric has been designed to provide and maintain harmony between the local community and better, faster and safer high speed State Highway.

The poor geometry of the road affects the risk and severity of the accidents. Hence appropriate design has been adopted so as to minimize the presence of sudden elements of surprise and to increase effective decision making of the road user traffic. This has been achieved by providing and improving the road safety features, road signage, partial access control, crash barriers etc.

The main causes observed for traffic accidents on the Project Road are:

- i. Traffic on the road is far in excess of the capacity of a single lane road, and hence there is frustration among motor vehicle drivers about the low speeds achievable and the lack of over taking opportunities;
- ii. Presence of slower vehicles that too without reflectors on the rear side, incites overtaking by the faster moving vehicles and causes accidents and also parked vehicles along the road without reflectors/back light;
- iii. Undisciplined driving by the drivers in general, and the bus/coach, truck drivers in particular;
- iv. Inadequate sight/stopping distances which results in accident during overtaking;
- v. Present of large diameter trees next to the paved carriageway (within 1000-1500 mm) causes vehicles to hit the trees either to avoid an overtaking incoming vehicle or skidding while overtaking on curves or slippery carriageway / wet unpaved shoulder;
- vi. The geometry of the existing road which has very poor sight distance;
- vii. Frequent parking of breakdown vehicles within the carriageway thereby requiring overtaking and consequently accidents;
- viii. Combination of horizontal and vertical curves for the two-way traffic carriageway;
- ix. Lack of access control in the built up sections, resulting in traffic from connecting minor roads entering the main carriageway;
- x. Unpainted/damaged parapet walls, absence of reflectors;
- xi. Frequent occurrence of bridges and culverts having in adequate width
- xii. Absence of guard beams at bridge approaches results in vehicles colliding with railings, and in some cases falling off bridges;

- xiii. Absence of guard beams at high embankments and sharper horizontal curves; and
- xiv. Absence of proper road markings, and warning, cautionary and hazard signs.

The accident statistics of the state of Orissa, compiled by the consultant was presented in the Feasibility Report. The statistics and the results presented a gloomy picture in general and horrendous at several black spots identified by the Consultant along the project road.

### 2.7.2 Geometric Deficiencies

The overall geometry of the project road was found to be fair. The existing Project Roads has sharp horizontal curves and insufficient vertical design standard, which do not provide adequate overtaking sight and stopping distance even for 50 kmph. Inadequate sight distance reduces the driver's perception to prepare himself for necessary maneuvers. It is therefore; very plausible that increase sight distance would reduce accidents, unless it results in increase speed. At some of the section it has an average speed of just over 40 kmph.

The existing geometric design did not have sufficient transition curves thereby making the accidents more frequent on the Project Road. The horizontal design speed did not match with vertical design speed that surprised the drivers and affected the decision making while choosing the right speed.

Existing bridges have insufficient carriageway width at Chainages km1/970, km11/270 and km29/500. All the existing culvers have insufficient carriageway width.

### 2.7.3 Road Intersections

During the road safety review, the existing poor condition of junctions was considered as one of the major contributing factor to the large prevailing numbers of accidents. Accordingly pilot surveys were conducted to assess the condition of the existing junctions.

As intersection areas normally carry heavier traffic than other highway sections as traffic approaches from both crossing roads, they become the potential black spot if not designed effectively. The conflict points at cross-junctions and T-junctions are shown in Fig 2.5. and Fig 2.6.




Figure 2.5 Cross Junction




Figure 2.6 T-Junction

Though the present project road does not have any Major junctions, many minor junctions are present. The following points were observed with respect to the junctions,

- i. None of the junctions along the project road had been designed as per the standards,
- ii. Most of the junctions had no appropriate road markings to guide the merging as well as the main road traffic,
- iii. Most of the intersections had no pedestrian crossing facility,
- iv. The junction signage were absent,
- v. Most of the junctions had insufficient sight distance, turning radius etc.
- vi. All the junctions are at grade junction,

The list of the major and minor junctions are presented below with the types of the junction,

**Table 2.16: List of Junctions**

S. No.	Chainage	Type	LHS/RHS
1	0.00	Y-Type	Major Junction
1	1.95	T-Type	LHS
2	2.54	T-Type	RHS
3	3.01	Y-Type	LHS
4	5.55	Y-Type	LHS
5	7.21	T-Type	LHS
6	8.34	Y-Type	RHS
7	11.71	T-Type	LHS
8	12.80	T-Type	LHS
9	12.79	T-Type	RHS
10	15.09	Y-Type	RHS
11	15.85	T-Type	RHS
12	16.42	Y-Type	LHS
13	18.70	T-Type	RHS
14	22.64	Y-Type	LHS
15	24.59	4-Legged	Major Junction
16	25.18	T-Type	LHS
17	27.13	T-Type	RHS
18	28.57	T-Type	RHS
19	29.51	T-Type	RHS
20	32.52	T-Type	RHS
21	32.60	T-Type	LHS
22	36.38	Y-Type	RHS
23	36.75	4-Legged	
24	37.00	Y-Type	RHS
25	37.52	Y-Type	LHS

## 2.7.4 Safety of Pedestrian

Due to the scattered / irregular settlements all along the proposed project road, due considerations have been given to safety of the local traffic and pedestrians in particular. The pedestrian movement in the built-up/settlements along the project road poses a major reason for the occurrence of the accidents. Access control is

totally absent in the present project corridor. Some of the observations of the consultant are given below,

- i. No Provision of footpath at the built up section on both sides of the Road.
- ii. No road markings for the pedestrian crossing at congested intersections and market places.
- iii. No signboard for speed reduction at built up sections.
- iv. No access control facility.

### **2.7.5 Road Signs and Furniture**

The road signs and furniture along the present project road is very poor not meeting the standards as outlined in the IRC guidelines. The Road Signs and Furniture are an important part to control and guide the flow of traffic on a road. These also reduce the occurrence of accidents as it increases the traffic safety by helping the drivers with more information for decision making.

#### **Road Markings**

The road markings are almost absent along the present section of the Project Road. This results in ineffective guiding of the traffic flow, hence tending to increase the road accidents. The junctions do not have any pavement markings and no traffic islands, which makes the junction a potential black spot along the corridor.

#### **Road Signs**

The road signs along the project road are grossly insufficient either to provide the drivers with information or to guide the drivers of the road features while driving. The drivers are often taken by surprise with sharp curves, congested built up, sudden change of speed, road humps, intersections etc.

#### **Road Delineators**

The presence of the road delineators is nil.

#### **Bus-Bays and Shelters**

The bus lay-bys along the existing project road are of very low standards. There are no proper and safe bus shelter structures provided for the passengers waiting for the bus. The bus shelter structure is not aesthetically pleasing and functional so as to protect the waiting passengers from sun, rain and wind. The current bus bays do not have any extra widening or extra lane dedicated for the buses. Thus the buses stop to drop and pick passengers on the main carriageway causing traffic disruptions and road mishaps.

#### **Truck Lay-Bys**

The project road does not have any truck lay byes at present. As a result the truck use the shoulder as well as the main carriageway to park their vehicles for refreshments or for washing the vehicle. In any case the carriageway capacity is reduced and affects the movement of the traffic on the road.



### **Crash Barriers**

Crash barriers/high embankment protective works are almost absent along the whole of the project road. Thus making the accidents more severe and increasing the loss of life and property.

### **Guard Post**

Guard Post or protective works of similar nature are mostly not provided to the bridge approaches. In such cases the accidents at such locations can be of serious nature.

## **2.7.6 Design Approach to Improve Traffic Safety Measures**

The design approach followed as per the Indian Standards and with agreement with the OPWD for the two lane Project State Highways will eliminate the physical deficiencies stated here above and will significantly improve the safety of the users, vehicles and pedestrians/ farm animals. Traffic safety measures have also been taken up extensively to improved safe passage of traffic and reduce the accident rates.

The salient features of the design approach to safety measures shall include:

- i. Provision of two lane carriageway to increase the capacity of the road so as to allow more freedom to the drivers
- ii. Improvement of major and minor junction with the provision of extra lanes.
- iii. Facilities to assure safe circulation of slow moving vehicles, pedestrians and farm animals
- iv. Provision of appropriate guard rails/crash barriers for high embankment
- v. To provide marker post and other safety signage at Bridge approaches Proper road markings and traffic signage to warn the drivers as per the IRC norms
- vi. Adequate road side protective works like retaining walls, berms etc
- vii. Delineators: will be provided at all bridges, high embankments, metal guard beams/ crash barriers on curves intersections and traffic islands as warranted.
- viii. Bus and truck laybys are provided along the Project Road sections

The road safety measure has been fully inculcated in the detailed design and the various safety measures are discussed in detail in Chapter-7 “Detailed Design-Road Safety Measures, Traffic Control and Other Facilities”.

## **2.8 SURVEYING UTILITY SERVICES**

Except for the vicinity of built-up and roadside establishments, the project road alignment runs through open country with predominantly agricultural land use. Hence, the project road is relatively free from the problems associated with utilities and services.

All the utility services such as electric power lines, electric poles, telephone posts and telephone lines etc. were recorded during survey.

Strip plan indicating the scheme for carriageway widening, location of all existing utility services (both over and underground) and the scheme for their relocation has been prepared separately.

## 2.9 TRAFFIC SURVEY

The traffic surveys were conducted to determine classified traffic volumes in terms of Annual Average Daily Traffic (AADT), directional split, hourly variation, trip length pattern, travel pattern of goods and passenger traffic, commodity flow and axle loads. The details of these have already been presented in Feasibility Report Chapter -7. Abstract of findings have been presented in following paragraphs.

### 2.9.1 Volume Count

Traffic Volume Count Survey was conducted at two locations; one VC-7 at km 0/600 (near Berhampur) and other VC-8 at 22/500 (near Digapahandi). Results are shown in Table 2.17. The table shows that Annual Average Daily Traffic (AADT) are 8152 and 6647, whereas the PCU are 1190 and 687 respectively.

**Table 2.17: AADT and PCU**

Count Stn.	Description	FAST MOVING VEHICLES											SLOW MOVING VEHICLES			
		2 W	3 W	Car/ Jeep/ Taxi	Bus		LCV	TRUCK			Agri. Tractor		Cycle	Rickshaw	Animal DRAWN	
					Mini	Full		2-Axle	Multi-Axle	Articulated	With Trailer	No Trailer			Bullock Cart	Horse Drawn
VC-7	AADT	2685	223	416	132	222	107	179	30	25	113	17	3802	192	9	0
	PCU	1343	223	416	199	665	160	538	91	115	509	26	1902	385	75	0
	%	64.7%	5.4%	10.0%	3.2%	5.4%	2.6%	4.3%	0.7%	0.6%	2.7%	0.4%	95.0%	4.8%	0.2%	0.0%
VC-8	AADT	1433	174	289	70	201	54	121	13	2	32	9	1172	8	10	0
	PCU	717	174	289	105	603	81	362	40	9	145	15	587	17	83	0
	%	59.8%	7.3%	12.1%	2.9%	8.4%	2.3%	5.0%	0.5%	0.1%	1.3%	0.4%	98.5%	0.7%	0.8%	0.0%

**Table 2.17: Summary of AADT and PCU**

Count Stn.	Description	Total Motorised Vehicle	Total Comm. Vehicle	Total Non Motorised Vehicle	Total Vehicle
VC-7	AADT	4149	808	4003	8152
	PCU	4285	2277	2362	6647
VC-8	AADT	1432	2398	493	1190
	PCU	1987	2540	1345	687

### 2.9.2 Axle Load Survey

Axle load survey was carried out near Berhampur, designated as AL-05. The axle load surveys were conducted using Portable Load Pads, developed in Indian Institute Technology, Kharagpur, having platform size 550mm X 700mm X 30mm (weight 30 kg) with digital load indicator.

The Vehicle Damage Factor (VDF) has been calculated direction wise and a higher value has been adopted for design. In light of the order passed by the Hon'ble Supreme Court of India on dated 9th November 2005 in Writ Petition (Civil) No. 136 of 2003 (Paramjit Bhasin and Others v/s Union of India), the over loading of the trucks beyond legal axle loads will be ceased in coming years. Therefore, the observed calculated values have been adopted for first five years only i.e. from 2008 to 2013. Beyond this period, the VDF values higher than 3.5 have been moderated to 3.5. Abstract of VDF is as presented in Table 2.18 and design year MSA in Table 2.19.

**Table 2.18: Design VDF**

Station	Road Section	Recommended values of VDF for				
		LCV	2-Axle Truck		3-Axle Truck	
			2008-13	2013-28	2008-13	2013-28
AL-05	Berhampur - Taptapani	0.18	3.71	3.5	3.71	3.5

**Table 2.19: Design MSA**

Location	Design Year	Design MSA
VC-7	2028	14.40
VC-8	2028	8.65

### 2.9.3 Projected Traffic

The traffic forecast has been made on the basis of elasticity of transport demand keeping in view present growth in registration of vehicles, economic indicators like Net State Domestic Product, Per Capita Income, Net National Domestic Product and growth in population. The projected traffic in different years is shown in Table 2.20.

**Table 2.20: Projected Traffic**

Year	AADT		PCU	
	VC-7	VC-8	VC-7	VC-8
2006	8152	3588	6647	3227
2007	8388	3722	6907	3374
2008	9309	4165	7743	3805
2009	9646	4357	8119	4016
2010	10006	4562	8524	4244
2011	10391	4781	8961	4488
2012	10804	5015	9433	4751
2013	11245	5266	9941	5034
2014	11715	5532	10484	5336
2015	12218	5817	11070	5661
2016	12756	6122	11702	6010
2017	13333	6448	12383	6386
2018	13950	6797	13119	6791
2019	14578	7152	13876	7207
2020	15249	7531	14691	7653
2021	15965	7935	15568	8133
2022	16731	8367	16512	8648

Year	AADT		PCU	
	VC-7	VC-8	VC-7	VC-8
2023	17548	8828	17529	9203
2024	18344	9276	18526	9745
2025	19190	9752	19594	10324
2026	20088	10257	20737	10944
2027	21043	10794	21962	11607
2028	22058	11364	23275	12316

## **CHAPTER - 3**

# **DETAIL DESIGN – ROAD ALIGNMENT**

---

## **CHAPTER – 3**

### **DETAIL DESIGN – ROAD ALIGNMENT**

#### **3.1 GENERAL**

The existing road is a single lane carriageway road with horizontal and vertical geometric average to poor. As detailed out in Final Feasibility, the road shall be upgraded to two lane carriageway facilities with hard shoulders on either side of the carriageway. The design philosophy that will be followed embodies the following.

- i. Facility should be of State Highway standards.
- ii. Facility must meet the needs for development activities in the region.
- iii. Travel should be safe, with in-built engineering features.
- iv. Facility should be aesthetically pleasing and should not be visually intrusive.
- v. Facility should meet the environmental conditions.

While designing, improvement shall be done for widening to two lanes, horizontal and vertical geometry, road intersections, road signs, road markings, drainage system, bus bays and other road features as per requirements. Computer software have been used for plan and profile design.

#### **3.2 DESIGN STANDARDS**

Design Standards for the State Highway requirements have been framed for following items for providing the desirable level of service, safety and comfort to the vehicle using the facility. Design Standards given in IRC Codes, Guidelines and Special Publications besides MoSRTTH circulars and specifications as applicable to State Highways have been followed and also taking into consideration the inputs given by the OWD Officials on the local conditions. List of IRC publications referred for design is given in following table.

**Table 3.1: List of IRC Publications**

Ref. No.	Title of Standards
IRC:8-1980	Type Designs for Highway Kilometre Stones (Second Revision)
IRC:25-1967	Type Design for Boundary Stones
IRC:31-1969	Route Marker Signs for State Routes
IRC:35-1997	Code Of Practice for Road Markings (First Revision)
IRC:38-1988	Guidelines for Design of Horizontal Curves for Highways and Design Tables (First Revision)
IRC:52-2001	Recommendations About the Alignment Survey and Geometric Design of Hill Roads (First Revision)
IRC:54-1974	Lateral and Vertical Clearance at Underpasses for Vehicular Traffic
IRC:64-1990	Guidelines for Capacity of Roads in Rural Areas
IRC:66-1976	Recommended Practice for Sight Distance on Rural Highways
IRC:67-1977	Code Of Practice for Road Signs
IRC:73-1980	Geometric Design Standard for Rural (Non-Urban) Highways
IRC:79-1981	Recommended Practice for Road Delineators
IRC:80-1981	Type Designs for Pick-Up Bus Stops on Rural (I.E., Non-Urban) Highways
IRC:99-1988	Tentative Guidelines on the Provision of Speed Breakers for Control of Vehicles Speeds on Minor Roads
IRC SP:23-1983	Vertical Curves for Highways
IRC SP:41-1994	Guidelines on Design of At-Ggrade Intersections in Rural and Urban Areas
	Most Specifications for Roads & Bridge Works (2001) (Fourth Revision)
	Most Typel Designs for Intersections on National Highways
	Manual for Safety in Road Design

### 3.3 GEOMETRIC DESIGN STANDARDS

For this Project Road, Geometric Design Standards as per IRC: 73-1980 “Geometric Design Standards for Rural (Non-urban) Highway” and IRC: SP-48 -1998 has been generally followed. Based on these documents, the requirements of Geometric Design Standards are given below.

The main design components are:

- i. Geometric design: Alignment and Profile
- ii. Cross-sectional elements
- iii. Intersections
- iv. Wayside amenities
- v. Service Roads

To enable the design of above components, design standards adopted are given in the following paragraphs.

#### 3.3.1 Terrain Classification

The classes of various terrains as per IRC: 73-1980 is given below in Table 3.2. The Project Road has sections varying from Plain to rolling.

**Table 3.2: Terrain Classifications as per IRC**

Sl no.	Terrain Classification	% Cross Slope of the Country
1	Plain	0 to 10
2	Rolling	10 to 25
3	Mountainous	25 to 60
4	Steep	60 and above

### 3.3.2 Design Speed

The Design Speed selected is the governing factor for all the geometric and road components. Based on, table no 2 of IRC: 73-1980, Design Speed, Different sections of the Project Road have been designed with different design speed corresponding to the terrain classification.

The design speed as per table 2 of IRC: 73-1980 for different terrain classes is given below in Table 3.3.

**Table 3.3: Design Speed for different Terrain Classes**

Road Classification	Design Speed in kmph							
	Plain Terrain		Rolling Terrain		Mountainous Terrain		Steep Terrain	
	Ruling Design Speed	Minimum Design Speed	Ruling Design Speed	Minimum Design Speed	Ruling Design Speed	Minimum Design Speed	Ruling Design Speed	Minimum Design Speed
State/ National Highways	100	80	80	65	50	40	40	30

The design speed of the project road has been adopted as per the design speeds given in Table 3.3 and the terrain classification of the project road section. But at certain sections, lower design speeds have been adopted as per record on instructions by the PIU officers. These changes have been agreed to and adopted to minimize the corridor impact of the proposed project on the social life and also to minimize the land acquisition. Attempts have been made to restrict the road design within the existing ROW in heavy built up sections.

### 3.3.3 Cross-Section Elements

The different components of cross-section adopted are as follows

#### Right of Way (ROW)

The recommended Road Land width (or Right of Way) for different terrain classifications and for land use is given in Table 3.4 as per IRC guidelines.

**Table 3.4: Recommended Road Land Width**

Road Classification	Plain and Rolling Terrain				Mountainous and steep terrain	
	Open areas		Built-up areas		Open areas	Built-up areas
	Normal	Range	Normal	Range	Normal	Normal
National & State Highways	45	30-60	30	30-60	24	20



The existing ROW along the project road is not uniform and lesser than the IRC Recommendations. However, for improvement of junctions, relocation, realignment etc, design has been as per functional requirement. Additional land acquisition has been kept to the minimum for these areas.

Due to lesser/ limited existing ROW at certain sections and to minimize the Corridor of Impact (COI) and the land acquisition, the Consultant, World Bank Mission and the OWD together agreed upon to vary the limits set out in the IRC guidelines. Accordingly different ROW limits were adopted. With reference to the "Preparation Mission Aide Memo ire (July 4-13, 2006), Technical Aspects Para 23 – Design and Engineering Issues, for Berhampur to Taptapani road the ROW (absolute minimum corridor of impact, COI), in built-up areas has COI of 15m. If land needed to be acquired then such acquisition will be done up to 16m. In non built-up sections the minimum COI (Assuming an embankment height of 2m) has been taken about 22m.

### **Cross-Slope**

For the project road each carriageway has a cross slope of 2.50 per cent. The paved/hard shoulder and earthen shoulder has a slope of 2.5 per cent and 3.5 per cent respectively.

### **Roadway Details**

#### **i. Carriageway**

The Project road has been designed as a two-lane carriageway with hard shoulders. The width of two lanes has been taken as 7.0m.

#### **ii. Shoulder**

Hard Shoulders are provided as proposed in Final Feasibility Report and have a width of 2.5m on either side of carriageway.

#### **iii. Total Roadway Width**

Total roadway width has been taken as 12.00 m.

### **3.3.4 Sight Distance**

Sufficient stopping distance is made available for drivers to stop their vehicles when faced with an unexpected obstruction in the carriageway. During the design of the project road, Intermediate Sight Distance that is twice the Stopping Sight Distance is taken into consideration to help the vehicles for taking over with reasonable caution. But Stopping Sight Distance has also been used at sections where the provision of the Intermediate Sight Distance does not fit in. At no section, standards lower than the safe minimum stopping sight distance has been adopted, which is given as per IRC:73-1980 as follows.

$$\text{Safe stopping minimum sight distance} = 0.278 V.t + \frac{V^2}{254 f}$$

Where,

V = Design speed in km/hr

t = Perception & break reaction time (taken as 2.5 sec.)

f = Co-efficient of longitudinal friction varying from 0.40 at 20 km/h  
0.35 At 100 km/h

The safe stopping sight distance, overtaking sight distance as recommended in the IRC:73-1980 is shown in Table 3.5

**Table 3.5: Minimum recommended Sight Distances**

Speed (Km/h)	Safe Stopping Sight Distance (m)	Overtaking Sight Distance (m)	Intermediate Sight Distance (m)
100	180	640	360
80	120	370	240
65	90	340	180
60	80	300	160
50	60	235	120
40	45	165	90
30	30	-	60
20	20	-	40

### 3.3.5 Horizontal Alignment

Different parameters for horizontal alignment are as follows.

#### Radius

The radius of the project road section has been adopted as per the radius specified in IRC:73-1980 Clause 9.4, for the design speed selected.

$$R = \frac{V^2}{127 (e+f)}$$

Where,

V= vehicle speed in km/hr

e= super elevation (maximum 0.07) ratio in meter per meter.

f = co-efficient of side friction (taken as 0.15)

R= Radius in meters

Radius for some selected design speeds are given in Table 3.6.

**Table 3.6: Absolute Minimum Radius**

Road Classification	Plain		Rolling Terrain		Mountainous and steep Terrain	
			Areas not affected by snow	Snow bound areas	Open areas	Built-up areas
	Ruling minimum	Absolute minimum	Ruling minimum	Absolute minimum	Ruling minimum	Absolute minimum
National & State Highways	45	30-60	30	30-60	24	20

### Super Elevation

As per Clause 9.3 of IRC: 73-1980, super elevation is given as follows.

$$e = \frac{V^2}{225 R}$$

Where,

e = Super elevation in meter per meter

V = speed in km/h

R = radius in meters

The maximum super elevation has been kept as 7 % at plain to rolling and 10% for the mountainous sections. No super elevation has been proposed when its value obtained is less than the road camber. Radii beyond which super elevation is not proposed are given in Table 3.7, as per IRC: 73 - 1980.

**Table 3.7: Radius Beyond Which Super Elevation not Required**

Design speed (km/h)	Radius (m)
100	1800
80	1100
65	750
50	450
40	280
35	220
30	160
25	110
20	70

### Transition Curve

Longer of the two values of minimum length of the transition curve derived from the following equations has been adopted. (Clause 9.5 of IRC:73–1980).

$$\text{i) } L_s = \frac{0.0215 V^3}{CR} \quad \text{and} \quad \text{ii) } L_s = \frac{2.7 V^2}{R}$$

Where,

Ls = Length of transition in meters

V = speed in km/hr

R = Radius of Circular Curve in meter

C = 80 / (75+V), Subject to a maximum of 0.8 and minimum of 0.5

Minimum transition length for some radii is given in Table 17 of IRC: 73-1980.

### Extra Widening on Curves

Extra widening on curves as per provision of IRC: 73 – 1980 section 9.8 are given in following table.

**Table 3.8: Extra Widening at Curve**

Carriageway	Radius of Curve (m)				
	Up to 20	21 to 40	41 to 60	61 to 100	101 to 300
Two Lane	1.5	1.5	1.2	0.9	0.6
Single Lane	0.9	0.6	0.6	-	-

Wherever the radius is less than that specified for minimum design speed, the transition curve, super elevation and pavement widening has been introduced. This will minimize the intrusion of vehicles on to adjacent lanes, tend to encourage uniformity of speed and increase vehicle speed at the curves.

### 3.3.6 Vertical Alignment

Different parameters for vertical alignment are as follows.

#### Gradients

Ruling gradient has been used as a matter of course in design. Limiting gradient has been used where the topography compels or where gentle grade would add enormously to the cost. Minimum gradient for drainage at embankment near level grades are not objectionable when the pavement has sufficient camber to drain the storm water laterally. However, in cut sections minimum gradient for drainage considerations is 0.5% if the side drains are lined and 1.0% if these are unlined.

The gradients to be maintained in the design are as per IRC: 73-1980, given in following table.

**Table 3.9: Gradients for Different Terrain**

S.No	Terrain	Ruling gradient	Limited gradient	Exceptional gradient
1	Plain or rolling	3.3 % (1 in 30)	5 % (1 in 02)	6.7 % (1 in 14.3)
2	Mountainous terrain, and steep terrain having elevation more than 3,000 m above the mean sea level	5 % (1 in 20)	6 % (1 in 16.7)	7 % (1 in 14.3)
3	Steep terrain up to 3,000 m height above mean sea level	6 % (1 in 16.7)	7 % (1 in 14.3)	8 % (1 in 12.5)

#### Vertical Curves

Minimum length of vertical curves adopted in design are as given in following table. The actual length for the vertical curve shall however be provided as per IRC: 73–1980.

**Table 3.10: Minimum length of Vertical Curve**

Design speed km/h	Maximum grade change not requiring a vertical curve (%)	Minimum Length of vertical curve (m)
35	1.5	15
40	1.2	20
50	1.0	30
65	0.8	40
80	0.6	50
100	0.5	60

**Vertical Clearance**

IRC: 54–1978: Chapter 8: Vertical clearance at underpasses shall be at least 5 meters. However, in urban areas, this should be increased to 5.50 meters so that double decker buses could be accommodated.

IRC: 73–1980: 12.2.1 Vertical clearance at underpasses should be minimum 5 meters after making due allowance for any future raising/ strengthening of the underpass roadway.

**3.3.7 Side Slopes**

The side slopes of highway embankments shall be as flat as possible so that drivers accidentally leaving the roadway have better chances of survival. This has been also recommended in IRC-36, which provides a side slope of 1:4 for low embankment upto 1.5m high.

For side slope of embankment, IRC: 36-1970 recommends the following slopes purely from the safety considerations.

**Table 3.11: Side Slope in Embankment**

Embankment height	Side Slope
Up to 1.5 m	1V : 4H
1.5 m to 3.0 m	1V : 3H
3.0 m to 4.5 m	1V: 2.5 H
4.5 m to 6.0 m	1V : 2 H

The consultant feels that this will be very expensive and hence recommend providing a side slope of 1:2 with provisions for barriers in high embankments. The side slopes of cuttings depend on the soil type

**3.4 DESIGN SOFTWARES**

Following software have been used for the designing and drafting of road features, alignment, vertical profile etc.

- MX Road
- AutoCAD
- Autodesk Land Development Desktop

### **3.5 UTILITY SERVICES**

Different types of existing utility services components e.g. optical fiber cables (OFC), electric poles, telephone poles are to be shifted out of the proposed road way. For widening the Project Road to two-lane carriageway, all the utility service components coming in the way of the widening will require to be shifted/ relocated. Separate drawings have been prepared for utility shifting plans.

### **3.6 WAY SIDE AMENITIES**

#### **3.6.1 Bus-bays and Shelters**

The lay out for bus bays and shelters will be in accordance with IRC: 80-1981. The bus shelter structure shall be structurally safe, aesthetically pleasing and functional so as to protect the waiting passengers from sun, rain and wind. These have been located suitably either start or end of small habitations and at both ends of large habitations. Following table gives the location of bus-bays and Shelters. The location of bus-bays is given in drawings.

#### **3.6.2 Truck Lay-bys**

The provision of truck lay-bys shall be governed by site requirements and parking demand and as per the guidelines of MoSRT&H Technical Circular No. RW/34032/5/88-DO-II dated 22.8.88. Parking shall be designed in the form of a rectangular or trapezoidal area parallel and separated from the carriageway by a physical barrier. The parking lots shall have necessary facilities like repairing, eating and resting and shall be suitably landscaped. The location of truck lay-bys has been given in drawings.

### **3.7 DETAIL DRAWINGS**

Plan and profile drawings has been prepared separately at scale of 1:2000 horizontal and 1:200 vertical. It shows all existing plan features, toe line of highway embankment, proposed right of way limits, drainage structure locations, existing ground profile, proposed finished profile, intersection layouts, typical cross sections of the main alignment, etc. Information has also been provided in the form of schedules for signposts, footpath barricade, signals, bus bays, truck lay bys, rumble strip location, road humps, etc. Typical layouts have been prepared for different type of road intersections.

# **CHAPTER 4**

## **PAVEMENT DESIGN**

---

## **CHAPTER 4**

### **PAVEMENT DESIGN**

#### **4.1 GENERAL**

Designs for new pavement and overlays are worked out in accordance with Indian and International Practices. The design of new Flexible Pavement is carried out as per IRC: 37-2001, AASHTO Design Guide (1993), TRL Road Note-31 and Flexible overlays as per IRC: 81-1997. Generally the shoulder is structurally designed to carry 10 to 20% of the traffic load, the design lane is expected to carry. However the structural drainage system of the paved shoulder is required to be integrated with that of the carriageway pavement. The latter condition thus requires the thickness of pavement structure to be the same as that for the traffic lanes since the lower layer of the sub-base for the carriageway is extended to the full width of formation for the lateral drainage of any water percolating into the pavement. Therefore the drainage requirements demand that each carriageway pavement layer be extended to shoulder as this ensures constructional ease, quality and speed. Pavement design has been done by using all the three methods during Feasibility stage and compared all the three methods and concluded that IRC method of design is the best method of design and economical design for Indian conditions. In fact all the three methods cannot be compared as they are developed for different climatic conditions. So, it is recommended to use IRC method for Indian conditions.

#### **4.2 IRC METHOD**

The Flexible Pavement has been modeled as a three-layer structure. Pavement design has been based on CBR values of sub-grade soil, vehicle damage factor consequent to number of commercial vehicles on the road corridor and considering life of the project as 20 years.

#### **4.3 DESIGN METHODOLOGY**

For the new lane and widening, the sub grade strength has been considered for the design. Wherever the CBR was found below 4%, the CBR was considered low and the sub grade material is to be obtained from borrow areas identified. For pavement reconstruction, the reconstructed pavements were considered to be placed on existing sub grade fill. The top 250 mm of the existing sub grade is loosened and compacted and new layers are placed on the compacted sub grade. For pavement strengthening by overlay both the forecast traffic volume, the existing crusts details, surface condition of the road and rebound deflection will influence the thickness of the pavement design.

If the Differential free Swell Index (DFS) of the sub grade material is more than 50%, then sub grade and the top 500 mm of the embankment material is to be obtained from borrow areas identified (Clause 305.2.1.2 of MoRST&H). Such type of soils whose DFS is more than 50% were found in few kilometers i.e. in Km 9/00 to 11.050, 18/00 to 19/00, 21/00 to 28/150 and 31/00 to 33/00 so, it is recommended to replace the existing swelling fill material with borrow material.

The BBD test results are based on the elastic deflection of the pavement under the wheel loads. It again depends upon sub grade soil type, its moisture content and compaction, thickness of different pavement layers and pavement temperature. Existing pavement crust consists of thin BT surface (mostly distressed) and WBM over boulder soling.



By using simple input parameters of given sub-grade strength (CBR) and design traffic in terms of MSA, the appropriate designs could be chosen.

For the design of pavements to carry traffic in the range of 1 to 10 MSA and for traffic in the range of 10 to 150 MSA for the CBR values of sub grade ranging from 2% to 10%, the thickness design charts are given in IRC: 37-2001. The thickness deduced from the chart for the design CBR value and design traffic is the total pavement thickness to be provided and consists of granular sub base, granular base and bituminous surfacing.

#### 4.3.1 Design Traffic

The intensity of repeated axle loading on a pavement over a given period of time is denoted by the cumulative number of million standard axles (MSA) during this period. As per IRC-37: 2001, the number of million standard axles for the design year is computed by the following equation.

$$N_s = \frac{365[(1+r)^n - 1]}{r} ADF$$

Where;

$N_s$  = Cumulative number of standard axles to be catered for in the design in terms of MSA.

A = Initial traffic for the design lane in terms of specified type of commercial vehicles per day;

D = Lane Distribution Factor

r = Annual growth rate of the specified types of commercial vehicles;

n = Design life in number of years;

F = Vehicle Damage Factor of the type of Commercial vehicle.

The traffic in the year of completion is estimated using the following formula.

$$A = P(1+r)^x$$

Where

P = Number of commercial vehicles as per last count.

x = Number of years between the last count and the year of completion of construction.

#### 4.3.2 Design CBR

The CBR is taken at an interval of 1 km along the stretch and the lower 10 percentile CBR is taken as Design CBR for the identified section; details of CBR at each km and Design CBR for the identified section are presented in Table 4.1. If the CBR is less than 4%, then new construction is adopted. If the CBR is more than 4% and if the deflection value is too high, reconstruction is adopted otherwise overlay is adopted.

From the field data analysis of the data collected through various surveys and investigations, the Consultant has designed the Berhampur - Taptapani (0/000 km - 41/000 km) Flexible Pavement for New construction, Reconstruction by using IRC: 37-2001 and Overlay using IRC: 81-1997. The Flexible pavement thickness of the different sections for new construction is presented in Table 4.2, pavement thickness of the different sections for

reconstruction is presented in Table 4.3 and pavement thickness of the different sections for Overlay is presented in Table 4.4.

**Table 4.1: Design CBR for Berhampur – Taptapani corridor**

KM		Characteristic Deflection	Design Deflection	Existing Sub grade CBR	Design CBR	Design CBR adopted	Type of Construction	Remarks
From	To							
0	1	6.00	-		6.00	6.00	Reconstruction	<b>Reconstruction with Design CBR(Deflection values are high)</b>
1	2	6.01		9.20				
2	3	5.97		6.20				
3	4	4.44		6.82				
4	5	5.17						
5	6	4.18		5.00				
6	7	4.31		15.00				
7	8	3.74	3.50	8.00	7.00	6.00	Overlay	<b>Overlay</b>
8	9	3.32		5.80				
9	10	12.08	-	8.50	7.00	6.00	Reconstruction	<b>Deflection value is high</b>
10	11	1.90	3.50	9.20	7.00	6.00	Overlay	<b>Overlay</b>
11	12	2.85						
12	13	2.85		8.50				
13	14	3.21						
14	15	2.43		8.90				
15	16	4.72	-	2.90	10.00	6.00	New construction	<b>New construction is done due to DFS problem and poor CBR problem</b>
16	17	3.79						
17	18	3.48		4.80				
18	19	3.06						
19	20	2.54		6.80				
20	21	3.93	3.90		6.00	6.00	Overlay	<b>Overlay</b>
21	22	3.56		6.80				
22	23	4.51	-	12.50	10.00	6.00	Reconstruction	<b>Reconstruction with Design CBR(Deflection values are high)</b>
23	24	6.56						
24	25	1.62		13.50				
25	26	5.63	-	13.50	10.00	6.00	Reconstruction	<b>Reconstruction with Design CBR(Deflection values are high)</b>
26	27	5.93						
27	28	2.51	3.13	8.50	7.00	6.00	Overlay	<b>Overlay</b>
28	29	3.39		7.60				
29	30	2.52						
30	31	2.08						
31	32	1.41		14.80				
32	33	5.47	-	8.70	9.00	6.00	Reconstruction	<b>Reconstruction with Design CBR(Deflection values are high)</b>
33	34	4.52						
34	35	4.50						
35	36	2.98		9.50				
36	37	1.99	-	9.50	10.00	6.00	New construction	<b>New construction is done due to DFS problem and poor CBR problem</b>
37	38	4.62						
38	39	3.09						
39	40	2.58						
40	41	4.30	-	9.30	9.00	6.00	Reconstruction	<b>Deflection value is high</b>

**Table 4.2: Crust details for New Construction with borrow material for the Berhampur – Taptapani as per IRC method**

S.No	PROP Chainage		Length in Km	Thickness Design (IRC-37)									Remarks
				Crust Details for new Construction									
	Surface Course			Base		Sub Base		Sub grade	Embankment	Total Thickness			
	BC	DBM		WMM1	WMM2	GSB1	GSB2						
1	14.850	20.000	5.150	40	75	100	150	110	150	500	500	1625	DFS>50%
2	36.150	40.180	4.030	40	75	100	150	110	150	500	500	1625	DFS>50%

**Table 4.3: Crust details for Reconstruction / widening for the Berhampur – Taptapani as per IRC method**

S.No	PROP Chainage		Length in Km	Thickness Design (IRC-37)														
				Crust Details for Reconstruction							Crust Details for Widening							
				Surface Course		Base		Sub Base		Total Thickness	Surface Course		Base		Sub Base		Sub grade	Total Thickness
				BC	DBM	WMM1	WMM2	GSB1	GSB2		BC	DBM	WMM1	WMM2	GSB1	GSB2		
1	0.000	14.000	14.000	40	75	100	150	110	150	625	40	75	100	150	110	150	500	1125
2	20.000	25.170	5.170	40	75	100	150	110	150	625	40	75	100	150	110	150	500	1125
3	25.170	27.170	2.000	40	50	100	150	110	150	600	40	75	100	150	110	150	500	1125
4	27.850	28.000	0.150	40	50	125	125	110	150	600	40	50	100	150	110	150	500	1100
5	29.100	30.850	1.750	40	50	125	125	110	150	600	40	50	125	125	110	150	500	1100
6	32.160	36.150	3.990	40	50	100	150	110	150	600	40	50	100	150	110	150	500	1100
7	40.180	43.000	2.820	40	50	100	150	110	150	600	40	50	100	150	110	150	500	1100

### 4.3.3 Overlay Design:

Overlay thickness design has been based on characteristic deflection determined for each relevant section of road and the design chart given in IRC: 81-1997. The following points describe the methodology adopted in arriving at the overlay thickness.

- Benkelman Beam Deflection test data was analyzed as per IRC guidelines and characteristic deflection was calculated for each km of the road.
- Characteristic deflection is estimated as mean rebound deflection plus twice the standard deviation as per IRC guidelines.
- Correction for temperature is done as per IRC: 81-1997.
- After de-marking the homogenous sections, characteristic deflection was calculated for each section as mean rebound deflection plus twice the standard deviation.
- Depending on the traffic loading, overlay thickness in terms of BM (Bituminous Macadam) layer was established as per design chart given in IRC: 81-1997 for each section.
- Equivalency factors given in IRC: 81-1997 was used to find out the layer thickness of BC (Bituminous Concrete), DBM (Dense Bituminous Concrete) and WMM (Wet Mix Macadam) layers. WMM layer was proposed as a granular overlay below the bituminous layer. Keeping in view all the constraints, this proposal is both cost effective and efficient.
- Profile corrective course with WMM layer was proposed in place of BM layer, to correct the existing camber as well as undulations in the existing surface.

**Table 4.4: Crust details for Overlay for the Berhampur – Taptapani as per IRC method (IRC: 81-1997)**

S.No	PROP Chainage		Length in Km	Thickness Design (IRC-81)				Thickness Design (IRC-37)							
				Crust Details for Overlay				Crust Details for Widening							
	Surface Course			PCC	Total Thickness	Surface Course		Base		Sub Base		Sub grade	Total Thickness		
	BC	DBM		WMM1		BC	DBM	WMM1	WMM2	GSB1	GSB2				
1	14.000	14.850	0.850	40	75	100	215	40	75	100	150	110	150	500	1125
2	27.170	27.850	0.680	40	50	125	215	40	50	125	125	110	150	500	1100
3	28.000	29.100	1.100	40	50	125	215	40	50	125	125	110	150	500	1100
4	30.850	32.160	1.310	40	50	125	215	40	50	125	125	110	150	500	1100

**CHAPTER – 5**  
**DRAINAGE SYSTEM AND PROTECTION**  
**WORKS**

---

## CHAPTER – 5

### DRAINAGE SYSTEM AND PROTECTION WORKS

#### 5.1 GENERAL

The road drainage is an important aspect for the durability and integrity of the structural strength of the pavement. An effective and an efficient drainage system is a primary requirement for a Road Project. A poor drainage system reduces the life and serviceability of the road. This aspect of road can be referred as the most neglected in the detailed design either due to the lack of engineering experience or due to lack of funds. The roadside drain can be divided in to two types i.e., Surface Drainage and Sub-Surface Drainage.

##### 5.1.1 Surface Drainage

Surface water drain off is to remove the water from carriageway, shoulders or footpath by providing sufficient cross slope. The cross slope is fixed in order to achieve a balance between effective runoff without compromising the comfort and safety of the road users.

##### 5.1.2 Sub-Surface Drainage

The sub-soil drainage represents the drainage of the water trapped in the subgrade, which may be due to percolation or infiltration of water from the pavement, shoulder, verges and also from the adjoining standing water through capillary action. It is important to drain off such water as it damages the road crust causing failure of the pavement by various reasons such as stripping of bitumen, subgrade weakening etc.

The proper planning and provision of roadside drains and its effect on the overall cost of the project is minimal considering the overall benefits and pavement durability. Thus the roadside drainage schemes needs to be studied and provided as improve and capitalize the benefits of the Project under consideration.

#### 5.2 EXISTING SCENARIO

The present project road section from Berhampur (km 0/00) to Taptapani (km 41/00) is a part of SH-17 Behrampur (0/000) – Bangi Junction (150/00), has no proper defined longitudinal drains except at certain built up areas. As Orissa receives an annual average rainfall of 1400-1500 mm, the drainage plan needs proper planning and maintenance. The built up sections (urban settlement section) is affected the most due to the water draining into the households. There is no functional roadside drain at any section of the Project Road. At present the surface water is being drained out directly to the adjoining land.

#### 5.3 DETAILED DESIGN

During the detailed investigation and design of the road components, the Consultant assessed the requirement of the roadside drains. The designs of the roadside longitudinal drains were done on the basis of the guidelines outlined in

IRC SP: 42-1994 and IRC SP: 50-1999. The cross sectional requirements of the drains with respect to hydraulic sufficiency, bed slope, drain types and construction techniques.

The roadside drain shall be provided as per the following,

- i. An effective drainage system for drainage of road shall be designed as per stipulations of IRC SP: 42-1994 and IRC SP: 50-1999.
- ii. The road side channel will be trapezoidal/ rectangular of adequate capacity to carry 100% surface runoff of drainage area of highway ROW and will be drained to the nearest available natural water course.
- iii. We propose to adopt trapezoidal section as it is more efficient and economical. This will be kuchha to drain out in the open field or to the defined outfall points. Lined rectangular drain will be adopted in urban areas.
- iv. The superstructure shall be drained with suitable drainage spouts and by means of a combination of drainage spouts and longitudinal drain supported from the superstructure and discharging through vertical drainpipes at pier locations.
- v. Suitable profiles of channels and pipe runs shall be provided at crossing with service needs and utilities to ensure that conflicts do not occur.

Accordingly to the requirements varying from location to location, two types of drains has been proposed for the present Project road. The two types of the drains are given below,

- i. RCC Box covered drains for the Built-up Sections
- ii. Unlined open trapezoidal drains for the rural sections.

### **5.3.1 RCC Box Covered Drains for Built-up Sections**


The RCC box covered drains of 1.5 m width and 1.05 m depth shall be provided on both side of the road in the built up sections identified and presented in Table 5.1. The covered drains are to be used as footpath for the pedestrian movement.




**Table 5.1: List of Built-up Sections**

Sl No.	Name of villages	Chainages		Length in KM	LHS/RHS
		Start	End		
1	Berhampur	0	820	0.82	Bothside
2	Ambagada	1600	2100	0.5	Bothside
3	Gunthabandha	2400	2600	0.2	Bothside
4	Dakhinpur	3090	3480	0.39	Bothside
5	Lanjia & Balkrishnapur	4410	4910	0.5	Bothside
6	Padarbali	7025	7270	0.245	Bothside
7	Bakjori	7745	7940	0.195	Bothside
8	Patitapabanpur	8200	8380	0.18	Bothside
9	Balipada	9845	10600	0.755	Bothside
10	Dengapadar	11665	11900	0.235	Bothside
11	Narayanpur	12725	13690	0.965	Bothside
12	Gania Nala	15645	15880	0.235	Bothside
13	Pitamabarpur	17200	17450	0.25	Bothside
14	Gokarnpur	18235	19100	0.865	Bothside
15	Anangapur	20600	20920	0.32	Bothside
16	Digapahandi	23200	25100	1.9	Bothside
17	Nua Maulabhanja	28200	28420	0.22	Bothside
18	Dengausta/ Govindnagar	31960	33330	1.37	Bothside
19	Kansamari	34100	34650	0.55	Bothside
20	Dharmapur	35700	36000	0.3	Bothside
21	Pudamari	36285	37200	0.915	Bothside
22	Kajnapali	38475	38600	0.125	Bothside
<b>Total Length = 12035 x 2 = 24070</b>					

The typical cross section is presented below in Figure 5.1 and Figure. 5.2. The details of the cross-section have been presented in Standard Drawings, Volume.




**Figure 5.1: Road Section at Built-up location**




**Figure 5.2: Detailed Urban Drain Section.**

### 5.3.2 Unlined Open Trapezoidal Drains for Rural Sections.

Open trapezoidal drains are proposed to be provided along both side of the highway to drain off the water to the nearest culvert locations or natural existing Streams/Nallas. The cross section details of the rural drain are presented in Figure 5.3 and Figure 5.4 below.



**Figure 5.3: Road Section at Rural location**



**Figure 5.4: Detailed Rural Drain Section.**

#### 5.4 DRAINAGE ON HIGH EMBANKMENT

Drainage on high embankment needs care and judicious considerations. The water from the carriageway and shoulder if let down directly on the high embankment slopes will damage the slopes severely with the formation of water cuts and will ultimately result in the failure of the slope. Chute drains and drain water collection piths shall be provided as per the guidelines detailed in IRC SP: 50-1999.

The surface runoff may be collected in collection piths and shall be drained through chute drains provided at suitable interval of 10m to 15m. The chute drains shall be lined with cement concrete.

The side slopes shall be protected with grass turfing in open areas for embankments more than 3m height. The slope protection on high embankments near approaches of bridges has been protected with stone pitching for a height upto HFL plus free board.

#### 5.5 LONGITUDINAL GRADIENT

The type of the drain, construction material and the properties of the soil present in the section will govern the longitudinal gradient of the roadside drains. Taking into account these factors a minimum longitudinal gradient of 0.3% is considered satisfactory as per the IRC guidelines.

# **CHAPTER – 6**

## **DETAIL DESIGN OF STRUCTURES**

---

**.CHAPTER – 6****DETAIL DESIGN OF STRUCTURES****6.1 GENERAL**

The different types of structures present are - Major Bridges – 1 No, Minor Bridges – 9 Nos and Culverts –142 Nos. Structures, which are structurally in poor condition or realigned, have been replaced with the new structures. Detailed hydrological calculations have been done to determine the waterway of proposed new bridges. Details of Hydrology have been presented in separate report.

Geo-technical investigations were carried out for all the new construction structures. The depth of foundation has been decided as per the results of the geo-technical investigations carried out and as per the hydrological investigations. Details of Geo-technical investigations are given in separate report.

The IRC codes given below have been referred for detail design of structures.

**Table 6.1: List of IRC Codes**

IRC:5-1998	Standard Specification & Code of practice for Road Bridges. Section – I General Features of Design (Seventh Revision)
IRC: 6-2000	Standard Specification & Code of practice for Road Bridges. Section – II Loads & Stresses (Fourth Revision)
IRC: 18-2000	Design Criteria for Prestressed Concrete Road Bridges (Post- Tensioned Concrete) (Third Revision )
IRC: 21-2000	Standard Specification & Code of practice for Road Bridges. Section – III Cement Concrete Plain & Reinforced (Second Revision)
IRC: 22-1986	Standard Specification & Code of practice for Road Bridges. Section – VI Composite Construction (First Revision)
IRC: 24-2001	Standard Specification & Code of practice for Road Bridges. Section – V Steel Road Bridges (Second Revision)
IRC:45-1972	Recommendations for Estimating the Resistance of soil below the maximum Scour Level in the Design of Well Foundations of Bridges.
IRC:73-1980	Geometric Design standards for Rural (Non-Urban) Highways.
IRC:78-1983	Standard Specification & Code of practice for Road Bridges. Section – VII Foundation & Substructure (First Revision)
IRC: 83-1999	Standard Specification & Code of practice for Road Bridges. Section – IX Bearings, Part-I Metallic Bearings (First Revision)
IRC: 83-1987	Standard Specification & Code of practice for Road Bridges. Section – IX Bearings, Part-II Elastomeric Bearings
IRC: 83-2002	Standard Specification & Code of practice for Road Bridges. Section – IX Bearings, Part-III POT, POT-CUM-PTTE, PIN & Metallic guide bearings.
IRC: 89-1997	Guidelines for Design & Construction of River training & control works for road bridges.
IRC:SP:13-2004	Guidelines for the Design of small Bridges and Culverts
IRC: SP:33-1989	Guidelines on supplemental Measures for Design, Detailing & Durability of Important Bridge Structures.
IRC: SP:35-1990	Guidelines for inspection and maintenance of Bridges
IRC: SP:37-1991	Guidelines for evaluation of load carrying capacity of Bridges.
IRC: SP:40-1993	Guidelines on Techniques for strengthening and rehabilitation of Bridges.

## 6.2 PROPOSED BRIDGES

Presently there are 10 bridges. Their location and existing span arrangements are as indicated in Table 6.2. The bridge at location 29/230 is major and remaining are minor bridges.

Bridge at location 11/270 is in poor condition and narrow in width, it is recommended for re-construction. The bridge at location 1/915 is slightly realigned and will be widened and the bridge at location 29/500 is realigned and narrow in width is, it is recommended for reconstruction.

The details of proposed major and minor bridges are as follows.

**Table 6.2: Proposed Bridges**

S. No.	Location/Chainage	Design Chainage	Existing Span Arrangement	Proposed Span Arrangement	Carriageway Width (m)	Overall Width of Bridge (m)	Remarks
1	1/915	1/925	2 x 6.6	-	-	-	Widening required due to change of alignment
2	4/400	4/370	3 x 6.75	-	-	-	Good, Rehabilitation required
3	11/270	11/286	1 x 6.35	1 x 10.4 Solid Slab (30° skew)	11.0	12.0	Reconstruction due to poor condition
4	11/660	11/735	3 x 6.8	-	-	-	Rehabilitation required
5	15/185	15/196	2 x 6.8	-	-	-	Good, Rehabilitation required
6	15/680	15/727	4 X 6.8	-	-	-	Good, Rehabilitation required
7	17/900	17/851	4 x 6.8	-	-	-	Good, Rehabilitation required
8	21/850	21/731	3 x 10.8	-	-	-	Good, Rehabilitation required
9	29/230	29/278	3 x 42.2	-	-	-	Good, Nothing to do
10	29/500	29/560	2 x 7.0	1 x 21.6 RCC T-beam	11.0	12.0	Reconstruction due to narrow in width, poor in condition and in realignment

## 6.3 WIDTH

In reference to clause 112 of IRC: 5-1998, width of proposed minor bridges have been kept equal to the formation width which is 12.0m. In built-up areas, raised footpath of 1.5m widths shall be provided on both sides for minor bridges keeping total width as 12m. The carriageway for these bridges shall be 7.5m. . All major bridges have been proposed for 2-lane carriageway with footpath making a total width of 12.0m.

## 6.4 DESIGN PHILOSOPHY

The superstructure for RCC T-beam and Solid slab bridges has been taken from MOST standard drawings ("Standard Plans For Highway Bridges"). Moving live loads were applied to determine the critical load combinations. Output of the STAAD has been used for further detailed design using standard Excel Spreadsheets. End cross-girders have been designed for bearing replacement condition supported on Jacks. Slab bridges have been designed for unit width by taking dispersion of live loads as per IRC:21-2000. The different components of Substructure and foundation have been designed for the loads coming from super structure & other loads using Excel Spreadsheets..

## 6.5 DESIGN LOADS

Following loads has been considered for design as per IRC:6-2000.

### 6.5.1 Dead Loads

Unit weight of different construction materials shall be taken as per IRC:6-2000. The weights of basic materials are as follows:

Cement Concrete – Plain	2.2 t/m <sup>2</sup>
Cement Concrete – Reinforced	2.4 t/m <sup>2</sup>
Cement Concrete – Prestressed	2.5 t/m <sup>2</sup>
Coursed Rubble Masonry	2.6 t/m <sup>2</sup>
Compacted Earth	1.8 t/m <sup>2</sup>

### 6.5.2 Live Loads

The carriageway width of proposed minor bridges is 11.0m. Hence these have been designed for three lane loading. The carriageway width of proposed major bridges is 7.5m and has been designed for two lane loading. Design live loads for different class of loadings and combination of live loads, impact factors, longitudinal forces, centrifugal forces for bridges on curves, etc. have been taken as per IRC:6-2000. The combination of different classes of live loads is as follows.

#### Minor Bridges:

- IRC class 70R tracked vehicle + IRC class-A one lane
- IRC class 70R wheeled vehicle + IRC class-A one lane
- IRC class-A three lanes

#### Major Bridges:

- IRC class 70R tracked vehicle
- IRC class 70R wheeled vehicle
- IRC class-A two lanes

### 6.5.3 Water current forces

HFL, velocity of flow, scour depth has been taken as per past data received from local enquiry and hydraulic calculations. The water current forces on substructure and foundation have been calculated as per IRC:6-2000.

On piers parallel to the direction of water current, the intensity of pressure is given by following equation.

$$p = 52KV^2$$

Where,  $p$  = intensity of pressure in  $\text{kg/m}^2$

$K$  = a constant, value depends on shape of pier

$V$  = velocity of current at point where pressure intensity is to be determined in m/s. (which is zero at the point of deepest scour and  $\sqrt{2}$  times maximum mean velocity at the free surface).

#### 6.5.4 Buoyancy forces

Full buoyancy (100%) has been considered for checking the stability of foundations. For checking stresses of the substructure components, 15% pore pressure uplift is considered in the design (as per clause 216.5 of IRC: 6-2000).

#### 6.5.5 Earth pressure

Lateral forces due to earth pressure for the design of abutments and retaining walls have been calculated as per IRC: 6-2000. Properties of backfill material are adopted as per IRC: 78-2000, Appendix-6.

Live load surcharge equivalent height of 1.2m for abutments and 0.6m for return/wing walls has also been considered.

#### 6.5.6 Seismic Force

Seismic forces for bridges meeting the following criteria as per IRC:6-2000 clause 222.1 are considered.

- a) Span is less than 15m
- b) Total bridges length is less than 60m.

Bridge at 29/500 meet this criteria, project road falls under Seismic Zone II.

### 6.6 MATERIAL SPECIFICATIONS

Detail specifications for material shall be given separately in bidding document. However, general design requirements adopted in detail designs are as follows.

#### 6.6.1 Concrete

In accordance with IRC: 21-2000 Table -5, following minimum grade of concrete has been used for moderate and severe conditions of exposure for different components:

Member	PSC/ Major Bridges	Other Minor Bridges & Culverts
<b>Moderate Conditions of Exposure</b>		
PCC Members	M 25	M 15
RCC Members	M 30	M 20
PSC Members	M 35	-



Severe Conditions of Exposure		
PCC Members	M 30	M 20
RCC Members	M 35	M 25
PSC Members	M 40	-

### 6.6.2 Reinforcement Steel

The grade of steel reinforcement Fe 415 for HYSD bars and Fe 240 for Mild Steel bars used in design.

### 6.6.3 Pre-stressing Cables

The pre-stressing cables shall be 12T13 or 19K13 type. Strands of 12.7 mm nominal dia 7 ply low relaxation confirming to IS:14268-95 shall be used. Multipull strand system of “Freyssinet” or “ISMAL CCL” or equivalent shall be used.

### 6.6.4 Bearings

Tarpaper bearing has been provided for RCC solid Slab superstructure of minor bridges upto 11m span. Elastomeric bearings have been provided for other type of simply supported superstructures and Slab super structures exceeding 10m span. These bearings have been designed as per IRC: 83 (Part-II)-1987.

POT fixed / POT PTFE sliding bearing has been proposed for long span simply supported super structures. Design loads' coming on the bearings has been provided to enable the manufacturer to design and supply.

### 6.6.5 Expansion joints

In accordance to MoRTH specification for road and bridge works – clause No. 2600 for solid Slab super structures up to 10 m span, the “Filler Type Expansion Joints” (20mm. thick joint filler) has been provided for bridge at Chainage 11/270.

“Single Strip Seal Expansion Joints” has been provided for superstructures with movement up to 80 mm (+/- 40 mm) for bridge at Chainage 29/500.

### 6.6.6 Wearing Course

Wearing course shall consist of 50 mm thick asphaltic concrete (two layers of 25 mm each) over a coat of mastic asphalt, 6 mm thick.

## 6.7 DETAIL DESIGN

Detailed structural analysis and designs for the new structures have been presented in the Detailed Project Report (DPR) in separate volume.

## 6.8 PROPOSED CULVERTS

A detailed inventory and condition survey was made and the results have been presented in Chapter-02. Culverts in good condition and adequate size, which meets the requirements of plan and profile in respect of highway geometry and levels, have been retained and been widened to make full formation width if narrow. The culverts,

which need replacement due to poor condition or inadequate size, have already been indicated in Chapter-02. The culverts, which are abundant due to change in horizontal alignment or change in vertical alignment, are proposed for replacement along new alignment. A list of proposed culverts is given below in Table 6.3.

**Table 6.3: Proposed Culverts**

S. No.	Location/Chainage	Proposed Chainage	Existing Span Arrangement	Type of Existing Culvert	Proposed Span Arrangement	Type of Proposed Culvert	Remarks
1	0/190	213.0	-	Choked	2 x 1.0	Pipe	Replaced due to insufficient vent
2	0/350	369.0	1 x 1.75	Slab	1 x 1.75	-	Good, to be widened
3	0/830	847.0	1 x 2.0	Slab	1 x 2.0	-	Good, to be widened
4	0/950	975.0	-	Choked	2 x 1.0	Pipe	Replaced due to insufficient vent
5	1/150	1146.0	1 x 1.5	Slab	1/23/0	RCC Box	Replaced due to poor condition
6	1/310	1310.0	1 x 1.5	Slab	1/22/0	RCC Box	Replaced due to raising in road level
7	1/785	1781.0	1 x 1.5	Slab	1/23/0	RCC Box	Replaced due to poor condition
8	2/140	2137.0	1 x 1.5	Slab	1/23/0	RCC Box	<b>Replaced due to poor condition, to be used as Wild Life Under Pass</b>
9	2/285	2332.0	1 x 1.5	Slab	1/22/0	RCC Box	Replaced due to insufficient vent
10	2/515	2515.0	3 x 0.9	Slab	1/43/0	RCC Box	Replaced due to poor condition
11	2/630	2629.0	1 x 1.5	Slab	1 x 1.5	-	Good, to be widened
12	2/745	2742.0	1 x 2.5	Slab	1/33/0	RCC Box	Replaced due to raising in road level
13	3/105	3095.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
14	3/265	3259.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
15	3/390	3382.0	1 x 1.4	Slab	1/23/0	RCC Box	Replaced due to poor condition
16	3/505	3498.0	1 x 2.5	Slab	1/33/0	RCC Box	Replaced due to raising in road level
17	3/775	3765.0	1 x 0.7	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition
18	3/895	3890.0	1 x 0.7	Stone Slab	2 x 1.0	Pipe	Replaced due to insufficient vent
19	4/115	4115.0	1 x 1.5	Slab	1/22/0	RCC Box	Replaced due to raising in road level
20	5/145	5127.0	1 x 1.5	Slab	1 x 1.5	-	Good, to be widened
21	5/230	5215.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition
22	5/535	5521.0	2 x 1.5	Arch	1/33/0	RCC Box	Replaced due to poor condition
23	5/775	5761.0	1 x 2.5	Slab	1/33/0	RCC Box	Replaced due to poor condition
24	6/090	6069.0	1 x 0.8	Pipe	1/22/0	RCC Box	Replaced due to poor condition
25	6/555	6497.0	-	Choked	1 x 1.0	Pipe	Replaced due to insufficient vent
26	6/590	6573.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition

S. No.	Location/Chainage	Proposed Chainage	Existing Span Arrangement	Type of Existing Culvert	Proposed Span Arrangement	Type of Proposed Culvert	Remarks
27	7/020	7000.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition
28	7/240	7217.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
29	7/540	7520.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition
30	7/630	7605.0	1 x 1.5	Slab	1 x 1.5	-	Good, to be widened
31	7/795	7769.0	1 x 1.5	Slab	1 x 1.5	-	Good, to be widened
32	8/030	8008.0	1 x 2.0	Slab	1/23/0	RCC Box	Replaced due to raising in road level
33	8/210	8193.0	2 x 1.0	Pipe	2 x 1.0	Pipe	Replaced due to poor condition
34	8/385	8363.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition
35	8/550	8530.0	1 x 3.0	Slab	1/33/0	RCC Box	Replaced due to poor condition
36	8/700	8685.0	-	Choked	2 x 1.0	Pipe	Replaced due to insufficient vent
37	9/175	9152.0	1 x 1.5	Slab	1/23/0	RCC Box	Replaced due to raising in road level
38	9/600	9538.0	1 x 0.5	Stone Slab	2 x 1.0	Pipe	Replaced due to poor condition
39	9/810	9786.0	1 x 1.5	Slab	1/23/0	RCC Box	<b>Replaced due to raising in road level, to be used as Wild Life Under Pass</b>
40	10/370	10340.0	-	Choked	1/22/0	RCC Box	Replaced due to insufficient vent
41	10/965	10933.0	2 x 1.5	Slab	2 x 1.5	-	Good, to be widened
42	11/120	11120.0	1 x 0.9	Arch	2 x 1.0	Pipe	Replaced due to poor condition
43	11/500	11500.0	1 x 1.5	Slab	1/23/0	RCC Box	Replaced due to poor condition
44	12/040	12065.0	2 x 0.8	Pipe	2 x 1.0	Pipe	Replaced due to insufficient vent
45	12/380	12407.0	1 x 1.0	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
46	12/585	12611.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
47	12/810	12836.0	3 x 1.2	Pipe	1/33/0	RCC Box	Replaced due to poor condition
48	12/880	12907.0	1 x 0.9	Pipe	1 x 0.9	-	Good, to be extended
49	13/110	13132.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition
50	13/265	13288.0	1 x 1.5	Slab	1/23/0	RCC Box	Replaced due to poor condition
51	13/450	13470.0	1 x 3.0	Slab	1/33/0	RCC Box	Replaced due to raising in road level
52	13/600	13619.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
53	13/790	13809.0	1 x 1.2	Pipe	1/22/0	RCC Box	Replaced due to poor condition

S. No.	Location/Chainage	Proposed Chainage	Existing Span Arrangement	Type of Existing Culvert	Proposed Span Arrangement	Type of Proposed Culvert	Remarks
54	13/895	13916.0	1 x 1.0	Pipe	1 x 1.0	-	Good, to be extended
55	14/135	14157.0	1 x 3.0	Slab	1 x 3.0	-	Good, to be widened
56	14/510	14531.0	1 x 0.6	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
57	14/855	14877.0	1 x 1.5	Slab	1/22/0	RCC Box	Replaced due to poor condition
58	15/430	15440.0	1 x 0.6	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
59	15/880	15897.0	NV	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
60	16/050	16068.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
61	16/400	16417.0	1 x 2.3	Slab	1/33/0	RCC Box	Replaced due to poor condition
62	16/505	16521.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
63	16/750	16770.0	NV	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
64	16/950	16970.0	1 x 0.6	Pipe	1 x 1.0	Pipe	Replaced due to submergence
65	17/650	17666.0	1 x 0.9	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
66	18/020	18028.0	2 x 1.7	Slab	1/43/0	RCC Box	Replaced due to raising in road level
67	18/105	18115.0	1 x 1.0	Slab	1/22/0	RCC Box	Replaced due to poor condition
68	18/470	18480.0	1 x 0.6	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition
69	19/240	19192.0	1 x 0.9	Slab	2 x 1.0	Pipe	Replaced due to poor condition
70	19/430	19382.0	1 x 0.6	Slab	1 x 1.0	Pipe	Replaced due to poor condition
71	19/570	19530.0	1 x 1.5	Slab	1/22/0	RCC Box	Replaced due to raising in road level
72	19/845	19799.0	1 x 1.0	Pipe	1 x 1.0	-	Good, to be extended
73	20/355	20361.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
74	20/610	20614.0	1 x 0.5	Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
75	20/930	20935.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
76	21/015	21005.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
77	21/230	21224.0	1 x 0.45	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
78	21/420	21411.0	1 x 1.0	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
79	21/875	21865.0	1 x 1.2	Pipe	1 x 1.2	-	Good, to be extended
80	22/210	22189.0	1 x 0.6	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
81	22/605	22582.0	1 x 1.6	Slab	1 x 1.6	-	Good, to be widened

S. No.	Location/Chainage	Proposed Chainage	Existing Span Arrangement	Type of Existing Culvert	Proposed Span Arrangement	Type of Proposed Culvert	Remarks
82	22/790	22761.0	1 x 1.0	Pipe	1 x 1.0	-	Good, to be extended
83	22/985	22961.0	1 x 0.9	Stone Slab	1 x 1.0	Pipe	Replaced due to poor condition
84	23/180	23147.0	1 x 0.7	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
85	23/300	23255.0		Choked	1/22/0	RCC Box	Replaced due to insufficient vent
86	23/515	23484.0	1 x 0.3	Pipe	1/22/0	RCC Box	Replaced due to insufficient vent
87	23/750	23713.0		Choked	1/22/0	RCC Box	Replaced due to insufficient vent
88	23/850	23821.0	1 x 1.5	Slab	1/23/0	RCC Box	Replaced due to raising in road level
89	24/365	24351.0	1 x 0.6	Pipe	1/34/0	RCC Box	Replaced due to insufficient vent
90	24/650	24636.0	1 x 1.5	Slab	1/22/0	RCC Box	Replaced due to poor condition
91	24/1020	25106.0	1 x 1.8	Arch	1/23/0	RCC Box	Replaced due to poor condition
92	25/050	25214.0	1 x 4.7	Slab	1 x 1.5	-	Good, to be widened
93	25/695	25861.0	1 x 1.85	Slab	1/22/0	RCC Box	Replaced due to poor condition
94	25/905	26072.0	1 x 0.95	Arch	1/22/0	RCC Box	Replaced due to poor condition
95	26/150	26314.0	1 x 0.5	Stone Slab	1/23/0	RCC Box	Replaced due to insufficient vent
96	26/430	26612.0	1 x 3.1	Slab	1/44/0	RCC Box	Replaced due to poor condition
97	26/850	27026.0	1 x 1.0	Arch	1/22/1	RCC Box	<b>Replaced due to poor condition, to be used as Bear Under Pass</b>
98	27/600	27743.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
99	27/850	28008.0	1 x 0.65	Stone Slab	1/23/0	RCC Box	Replaced due to insufficient vent
100	28/375	28547.0		Choked	1 x 1.0	Pipe	Replaced due to insufficient vent
101	28/800	28954.0	3 x 1.2	Pipe	1/33/0	RCC Box	Replaced due to poor condition
102	30/060	30241.0	1 x 3.0	Slab	1/33/0	RCC Box	Replaced due to raising in road level
103	30/460	30637.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
104	30/720	30889.0	1 x 1.8	Slab	1/23/0	RCC Box	Replaced due to raising in road level
105	31/960	32128.0	1 x 0.8	Stone Slab	1/22/0	RCC Box	Replaced due to poor condition
106	32/300	32465.0	NV	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
107	33/220	33402.0	1 x 1.5	Slab	1/22/0	RCC Box	Replaced due to poor condition
108	33/310	33476.0	1 x 1.6	Slab	1/22/0	RCC Box	Replaced due to poor condition

S. No.	Location/Chainage	Proposed Chainage	Existing Span Arrangement	Type of Existing Culvert	Proposed Span Arrangement	Type of Proposed Culvert	Remarks
109	33/806	33976.0	NV	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
110	33/900	34069.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
111	34/250	34463.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
112	34/525	34670.0	1 x 2.9	Slab	1/33/0	RCC Box	Replaced due to poor condition
113	34/640	34813.0	2 x 0.9	Pipe	1/23/0	RCC Box	Replaced due to insufficient vent
114	34/675	34858.0	1 x 2.1	Arch	1/33/0	RCC Box	Replaced due to poor condition
115	35/204	35378.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
116	35/350	35533.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
117	35/825	36003.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
118	36/060	36238.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
119	36/220	36358.0	-	Choked	1 x 1.0	Pipe	Replaced due to insufficient vent
120	36/500	36594.0	1 x 0.6	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
121	36/575	36758.0	1 x 0.8	Pipe	1 x 1.0	Pipe	Replaced due to poor condition
122	36/800	36961.0	NV	Pipe	1 x 1.0	Pipe	Replaced due to insufficient vent
123	36/990	37164.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
124	37/440	37619.0	1 x 0.8	Arch	1/23/0	RCC Box	Replaced due to poor condition
125	37/985	38157.0	1 x 0.5	Stone Slab	1 x 1.0	Pipe	Replaced due to insufficient vent
126	38/450	38483.0	1 x 1.5	Slab	1 x 1.5	-	Good, to be widened
127	38/600	38746.0	1 x 1.5	Slab	1/22/0	RCC Box	Replaced due to poor condition
128	38/810	39002.0	NV	Choked	1 x 1.0	Pipe	Replaced due to insufficient vent
129	38/960	39118.0	1 x 0.8	Arch	1/23/0	RCC Box	Replaced due to poor condition
130	39/195	39375.0	1 x 1.8	Arch	1/23/0	RCC Box	Replaced due to poor condition
131	39/340	39517.0	1 x 3.2	Slab	1 x 3.2	-	Good, to be widened
132	39/455	39671.0	1 x 0.8	Arch	1/23/0	RCC Box	Replaced due to poor condition
133	39/900	40090.0	1 x 0.85	Arch	1/23/0	RCC Box	Replaced due to poor condition
134	40/100	40280.0	1 x 1.35	Slab	1/22/0	RCC Box	Replaced due to poor condition
135	40/240	40437.0	2 x 0.45	Stone Slab	1/22/0	RCC Box	Replaced due to insufficient vent
136	40/420	40610.0	1 x 1.5	Slab	1/23/0	RCC Box	Replaced due to poor condition

S. No.	Location/ Chainage	Proposed Chainage	Existing Span Arrangement	Type of Existing Culvert	Proposed Span Arrangement	Type of Proposed Culvert	Remarks
137	40/815	41000.0	1 x 1.5	Slab	1/23/0	RCC Box	Replaced due to poor condition

Table 6.3a: Summary of Proposed Culverts

Type of Culvert	Nos.
Culverts Retained	Nil
Culverts Widened	
Pipe extension	5
Slab widening	12
Culverts Replaced	
New Single Pipe	51
New Double Pipe	9
New Single Box of 1/22/0	21
New Single Box of 1/22/1	1
New Single Box of 1/23/0	22
New Single Box of 1/33/0	12
New Single Box of 1/34/0	1
New Single Box of 1/43/0	2
New Single Box of 1/44/0	1
<b>Total</b>	<b>137</b>

Culverts at Chainages 2/140, 9/810 and 26/850 are used as wild life underpasses.

No culvert lies in do nothing, 17 culverts are proposed for widening to formation width of roadway i.e 12.0m and 120 culverts are proposed for replacement.

## 6.9 REHABILITATION OF STRUCTURES

A detailed inspection was made for repair and rehabilitation measures including replacement / retaining of existing bridges. The structures that are in distressed condition (reinforcement exposed and rusted, cracks in the structure, concrete falls by light hammering) have been suggested for Non destructive testing. NDT has been conducted at 2 Nos of bridges in the stretch and NDT report along with recommendations has been submitted to PIU. The rehabilitation proposals for the different structures are as detailed under in Table 6.4.



**Table 6.4: Rehabilitation of Minor Bridges**

S.No.	Location Km	Span Arrangement	General Condition	Recommendation
1	1/915	2 x 6.6	Good	<ul style="list-style-type: none"> <li>i. Abutments and piers shall be widened on right side</li> <li>ii. Existing slab shall be dismantled and new slab shall be constructed</li> <li>iii. Crash barrier shall be cast</li> <li>iv. Filler type expansion joints shall be provided</li> <li>v. 50mm BC laid over 6mm thick mastic asphalt</li> <li>vi. Drainage spouts shall be provided on each 5.0m distance on both sides</li> <li>vii. Tar paper bearing shall be provided</li> <li>viii. Approach slab to be constructed</li> <li>ix. Return walls shall be constructed on right side</li> <li>x. Bed protection &amp; curtain walls shall be provided on both u/s &amp; d/s sides</li> </ul>
2	4/400	3 x 6.75	Good	<ul style="list-style-type: none"> <li>i. Expansion joint shall be replaced by filler type</li> <li>ii. 8.0 mts of railing to be replaced</li> <li>iii. Touch up repair shall be done in wearing coat</li> <li>iv. Approach slab to be reconstructed</li> <li>v. Reinforcement exposed on pier P2 of area 0.01 sqmt to be gunited by 25 mm thick</li> <li>vi. Vegetation to be removed from the structure and bed.</li> </ul>
3	11/660	3 x 6.8	Fair	<ul style="list-style-type: none"> <li>i. Existing slab, abutment &amp; pier caps shall be dismantled and new slab, caps shall be constructed</li> <li>ii. Jacketing to be done in abutments and piers</li> <li>iii. Crash barrier shall be cast</li> <li>iv. Filler type expansion joint shall be provided</li> <li>v. 50 mm BC shall be laid over 6 mm thick mastic asphalt</li> </ul>

S.No.	Location Km	Span Arrangement	General Condition	Recommendation
				vi. Tar paper bearing shall be provided vii. Drainage spouts shall be provided on both sides viii. Approach slab to be reconstructed ix. Return walls to be constructed on right side (2 nos)
4	15/185	2 x 6.8	Good	i. Expansion joint shall be replaced by filler type ii. Touch up repair to be done in railings iii. Overlay of BT to be removed iv. Vegetation to be removed from the structure and bed
5	15/680	4 X 6.8	Good	i. Expansion joint shall be replaced by filler type ii. Overlay of BT to be removed iii. 2.0 mts of railings to be replaced iv. Vegetation to be removed from the structure and bed
6	17/900	4 x 6.8	Good	i. Expansion joint shall be replaced by filler type ii. Overlay of BT to be removed iii. 20.0 mts of railings and total guard posts to be replaced iv. Vegetation to be removed from the structure and bed
7	21/850	3 x 10.8	Good	i. Expansion joint shall be replaced by filler type ii. Vegetation to be removed from the structure and bed

## **CHAPTER 7**

# **ROAD SAFETY MEASURES**

---

## **CHAPTER 7**

### **ROAD SAFETY MEASURES**

#### **7.1 GENERAL**

Highways form an important lifeline for the movement of goods and passengers from one place to another, from a place of raw material to production and to the distribution end. Provision of traffic safety measures on highways gains significance with each year as the number of vehicles and traffic volume increases, hence the accident rates also increases. The road accident data reveals that one person is killed after every third road accident and one person is injured after every accident. Although pedestrians and cyclists are most vulnerable to road accidents but data are silent on these groups. Generally the findings on the basis of available accident data indicate that it is driver's behavior, which is mainly responsible for most of accidents, but it is not fair to ignore the technical aspects of road and traffic regulatory measures.

For higher traffic safety it is highly important to incorporate practical safety standards into the highway facilities at the design stage or during improvement and maintenance activities. The design and the safety measures should meet the expectations of the driver and guarantee from unexpected changes in the road conditions which might lead to a traffic accident.

Keeping into account the traffic safety drawbacks on the existing facility during the "Road Safety Review", traffic safety measures has been taken as a major criterion for the detailed design of the Project Highway and its features to provide a safe and a speedy road.

#### **7.2 ROAD SAFETY MEASURES**

To increase the traffic safety and to reduce traffic accidents, every component of the Highways and its users has been given equal importance. The road safety measures have been incorporated for the headers detailed below,

- i. The Road Geometric Components
- ii. Road Pavement Condition
- iii. Road Junctions
- iv. Road Furniture
- v. Highway Policing and Emergency Response

##### **7.2.1 The Road Geometric Components**

The road geometric components have been designed to meet the State Highway standards as specified in the IRC: 73-1980 "Geometric Design Standard for Rural (Non-urban) Highways" guidelines. The design has been done to match horizontal alignment and vertical grades as to eliminate elements of surprise to the drivers as discussed. Overtaking sight distances have been provided to increase safe overtaking opportunities and to reduce accidents. At heavy built up / village sections speed limits have been reduced to 50 kmph to 65 kmph considering the heavy pedestrian and local traffic movement by posting appropriate signs. In open

uninhabited areas where the existing alignment is safe enough to maintain a speed of 80 Kph, the design speed of 100 Kph has been adopted with minor changes to the alignment.

Superelevation is applied according to IRC guidelines with respect to the proposed centreline and the rate of introduction is kept more than the minimum of 1 in 150 as specified by IRC. For a curve without transition, two thirds of the Superelevation is achieved before the start of the circular curve in the straight part, 1/3rd of the Superelevation is achieved in the circular curve portion.

The provision of paved shoulders provides additional space for overtaking, slow moving and non-motorised traffic and for parking in the built up section. A wide cross-section (7.0 m carriageway + 1.5 m paved shoulder) has been used in to increase safety, by allowing separation of slower traffic, which can travel on the relatively wide paved shoulder, rather than completely in the main carriageway, which is now the case. This manner further helps to reduce accidents and increase road capacity.

All the narrow bridges (less than 7.5m carriageway) are proposed for development to minimum of 7.5m carriageway.

All the narrow culverts are proposed for development to full formation width i.e, 12.0 m.

## 7.2.2 Road Pavement Condition

The road pavement condition that influences the traffic safety includes evenness and grittiness of pavement surfaces, as these qualities influence the friction and skid resistance, which the pavement can offer in contact with the tire. This is a very important aspect for the braking distance. Poor antiskid performances increase the number of accidents. Therefore pavement condition shall be maintained so as to achieve acceptable serviceability indicators Level-2 of the road in accordance with the “Guidelines for Maintenance Management of Primary, Secondary and Urban Roads” of MoRST&H, 2004.

**Table 7.1: Serviceability Criteria**

SL NO	SERVICEABILITY INDEX	LEVEL-2 (AVERAGE)
1	Roughness by Bump Integrator (Max Permissible)	3000 mm/km
2	Potholes/km (Max Numbers)	2-3.
3	Cracking and Patch Repair (Max Permissible)	10 per cent
4	Rutting (20 mm) ((Max Permissible)	1.5 per cent
5	Skid Resistance	40 SN
6	Defective bridge deck area and bump at Approaches (Max Permissible)	10 per cent
7	User Information	Only major road signs, km stones, Some road markings in good condition

### 7.2.3 Road Junctions

As discussed in Para 2.7.3 Chapter-2, Traffic Safety Review, junctions if not improved to meet the design standards can become potential accident zones along the present project road. The Consultant has identified 26 junctions along the project road, out of which two are major intersections (0/000 and 24/590), the list of the junctions are shown in Table 7.2, which are required to be improved. The entire crossroads are BT roads. The minor junctions shall be developed as per the IRC guidelines and standard junction drawing presented in Drawings Volume separately. The major junctions shall be developed as per the drawings provided in Drawings Volume.

**Table 7.2: List of Junctions**

SL. NO.	CHAINAGE	SIDE	TYPE OF JUNCTION	CROSS ROAD TYPE
1	0/000	Major Junction	Y-Type	BT Road
2	1/946	LHS	T-Type	BT Road
3	2/538	RHS	T-Type	BT Road
4	3/011	LHS	Y-Type	BT Road
5	5/550	LHS	Y-Type	BT Road
6	7/205	LHS	T-Type	BT Road
7	8/335	RHS	Y-Type	BT Road
8	11/708	LHS	T-Type	BT Road
9	12/800	LHS	T-Type	BT Road
10	12/790	RHS	T-Type	BT Road
11	15/089	RHS	Y-Type	BT Road
12	15/846	RHS	T-Type	BT Road
13	16/422	LHS	Y-Type	BT Road
14	18/704	RHS	T-Type	BT Road
15	22/635	LHS	Y-Type	BT Road
16	24/590	Major Junction	Typical 4-Legged	BT Road
17	25/183	LHS	T-Type	BT Road
18	27/127	RHS	T-Type	BT Road
19	28/572	RHS	T-Type	BT Road
20	29/511	RHS	T-Type	BT Road
21	32/518	RHS	T-Type	BT Road
22	32/602	LHS	T-Type	BT Road
23	36/381	RHS	Y-Type	BT Road
24	36/748	-	Typical 4-Legged	BT Road
25	37/000	RHS	Y-Type	BT Road
26	37/519	LHS	Y-Type	BT Road

### Safety at Junction

The safety of a particular intersection design is best assured by studying the frequency with which types of accidents occur at particular type of intersection and its correlation with volume and types of traffic. Intersection improvement can be prioritised based on a simple equation as per IRC: SP-41- 1994. The equation relates the accident frequency with traffic volume. The equation is given below,

$$C = \frac{A}{(Qq)^{0.5}}$$

A=No of accidents a year,

Q=Traffic volume on Project road

q=Traffic volume on intersecting road (1000 veh per day)

The improved junctions shall be provided with standard road pavement markings, acceleration and deceleration lanes, adequate signboards etc.

### **Widths of Median Island**

A minimum width of 1.2m has been adopted where median islands are introduced in the absence of a continuous median. Minimum lengths of median islands are 20 m and maximum lengths are based on site requirements.

### **Channelising Islands**

Channelising islands have been provided depending on the volume of turning traffic and the importance of the road. The minimum area of these islands is 4.5 sq.m. At all intersections a minimum 0.3 to 0.6m island offset from normal vehicle paths is provided. The island shapes have been designed to ensure wheel path turning diagrams of design vehicles can negotiate the curves safely and clear of the islands.

### **Kerbs**

Kerbs at central and channelling islands are of the semi-barrier type in all project designed intersections.

### **Cross slope at Intersection**

Maximum cross slope of 0.5% is maintained to drain off surface water effectively from carriageway. The longitudinal gradient of not more than 0.5% at intersection and not steeper than 1.0% (1in100) shall be achieved beyond intersection for a distance of 100m on cross road or minor arm intersecting with project road at major or minor intersections.

### **Traffic Control Devices**

For both major and minor road intersections, the use of traffic control devices and other road furniture has been considered. The common types of traffic control devices, which are used to reduce accidents and improve flow conditions at junctions, are road markings, road signs and safety railings. These are as per IRC standards and specifications mentioned below:

- i. IRC: 35-1997 (Code of Practice for Road Markings)
- ii. IRC: 67-1977 (Code of Practice for Road Signs)
- iii. IRC: 79-1981 (Recommended Practice for Road Delineators)
- iv. IRC: 103-1988 (Guidelines for Pedestrian Facilities)

## 7.2.4 Road Furniture

Road Furniture details include:

- i. Road Markings
- ii. Traffic Sign (Cautionary, Mandatory and Informatory)
- iii. Kilometer Stones
- iv. 200m Stones and Boundary Stones
- v. Delineators and Object Markers
- vi. Bus Bays
- vii. Truck Lay Bys
- viii. Guard Posts
- ix. Crash Barriers
- x. Road Humps & Rumble Strips
- xi. Footpath Barriers
- xii. Reflective Pavement Markers (RPM)
- xiii. Chevron Signs Boards

The Standard Drawing and location schedule of different road furniture are presented in drawing volumes separately.

### Road Markings

Road markings perform the important function of guiding and controlling traffic on a highway. The markings serve as psychological barriers and signify the delineation of traffic paths and their lateral clearance from traffic hazards for safe movement of traffic. Road markings are therefore essential to ensure smooth and orderly flow of traffic and to promote road safety. The Code of Practice for Road Markings, IRC: 35-1997 has been used in the study as the design basis. Schedules of Road Markings are included in contract drawings.

The following road markings are provided:

<b>Longitudinal markings</b>	: Center Line
	: Edge Lines
	: Traffic Lines
	: Width Transition
	: Obstructions Ahead



**Intersections** : Stop Lines  
: Word “STOP”  
: Pedestrian Crossing  
: Approach to Intersection  
: Direction Arrows  
: Continuity Lines  
: Traffic island

**Parking** : Bus Stop  
: Emergency Parking

The road marking material will be hot applied thermoplastic reflective as per Clause 803 of MoSRTTH Specifications.

### **Traffic Sign (Cautionary, Mandatory and Informatory)**

Cautionary, mandatory and informatory signs are provided depending on the situation and function they perform in accordance with the IRC: 67-1997 guidelines for Road Signs. The different types of road signs are categorized and provided are:

- i. Mandatory / Regulatory
- ii. Cautionary / Warning
- iii. Directional
- iv. Hazard Markers
- v. Informatory

The Code of Practice for Road Signs, IRC: 67-1997, is followed for sizes, configuration, colour and location of all road signs and the Clause 801 of MoSRTTH Specifications for their construction. Retro-reflectorised type, which is made of high intensity, encapsulated lens types reflective sheeting fixed over aluminium sheeting for a better visibility at night and road users safety.

The signs should be placed at right angles to the line of travel of the approaching traffic. Signs relating to parking of vehicles during specified periods must, however, be fixed parallel to the carriageway. These signposts must be installed at an offset distance of 2m from the edge of the carriageway. The cautionary/warning signs are located at distances of 120m in plain and rolling terrain and 60m in hilly terrain in advance of hazard warnings in rural sections of State Highways, 50m in advance of hazard warnings in urban areas. Informatory signs such as advance direction sign boards, etc. are located at specified distances usually at major intersections on appropriate directions of travel.

Where light reflection from the sign face is encountered to such an extent as to reduce legibility, the sign should be turned slightly away from the road. On Horizontal curves, the sign should not be fixed normal to the carriageway but the angle of placement should be determined to the course of the approaching traffic.

The retro reflective sheeting used on the sign shall consist of white or coloured sheeting having a smooth outer surface, which has the property of retro-reflection over its entire surface. It shall be weather resistant and show colourfastness. It shall be new and unused and shall show no evidence of cracking, scaling, pitting, blistering, edge lifting or curling and shall have negligible shrinkage or expansion. A certificate of having tested the sheeting for these properties in an unprotected outdoor exposure facing the sun for two years and its having passed these tests shall be obtained from a reputed test laboratory.

The colour of the sheeting in case of wide-angle prismatic lens shall conform to the colour requirements determined by instrumental method in accordance with ASTM E-1164 on sheeting applied to aluminium test panels. Computation shall be done in accordance with E-308 for 2-degree observer. In case of Encapsulated lens type-sheeting specification shall conform with MoSRTTH, ASTM E-810.

### **Kilometer Stones**

The details of kilometre stones are in accordance with IRC: 8-1980 guidelines. Both ordinary and fifth kilometre stones are provided as per the schedule given in tender drawings. Kilometre stones are located on the left-hand side of the road as one proceeds from the station from which the kilometre count starts. Kilometre stones shall be fixed at right angles to the centre line of the carriageway.

### **200m Stones and Boundary Stones**

The details of 200m stones and boundary stones conform to IRC: 26-1967 and IRC: 25-1967. 200m stones are located on the same side of the road as the kilometre stones. The inscription on the stones shall be the numerals 2, 4, 6 and 8 marked in an ascending order in the direction of increasing kilometrage away from the starting station. The numerals shall be 80mm high. The colour of the numerals shall be black on a white background. Boundary stones shall be located on either side of the road opposite every 200m stone and kilometre stone. In addition these shall be fixed at all angular points of the boundary. Where the boundary is on a curve or the land is of significant value and likely to be encroached upon, the boundary stones, as required, shall be installed at closer intervals. Typical details design of 200m stones are provided in standard highway drawings.

The letter RB, indicating Road Boundary, shall be inscribed on each stone and below it the name of the authority in which the road rests i.e., PWD, C&B etc.

### **Delineators and Object Markers**

Reflective Delineators and Hazard Markers: Delineators and Hazard Markers are provided to guide the road users for the delineation of carriageway or particular topographical features like traffic island at intersection and junctions, sharp horizontal curves and steep gradients higher than 5%. Object markers are used to indicate hazards and obstructions within the vehicle flow path, for example, channelising islands close to the intersections.

The design, materials and locations of the road delineators are conforming to the Recommended Practice for Road Delineators - IRC: 79-1989 and relevant drawings.

They are basically driving aids and should not be regarded as substitutes for warning signs, road markings or barriers. Delineators are provided for all curves of radius less than 600m. They are not provided at locations where Chevron signboards are provided. Delineators and object markers are provided as per the details given in the drawings and are provided in accordance with the provisions of IRC: 79-1989.

### Bus Bays

Bus bays are proposed as per the recommendations of IRC: 80-1981. The following data was gathered during field visits.

- i. All though there were considerable through bus traffic movements, the number of buses stopping at existing bus stops was few.
- ii. People travelling from villages to nearby towns make use of taxicabs, jeeps and other light commercial vehicles including goods vehicles in preference to buses.
- iii. The number of trips made by other carriers was greater than those made by buses.
- iv. Local consultations were held to study the need for bus bays in specific villages by collecting details pertaining to the number of buses, frequency of buses stopping to pick up passengers, duration of bus stops, etc.
- v. The need for bus bays at religious places, educational institutions, public buildings, intersections of minor roads leading to interior villages, which are not connected to the bus route network, were studied.

With due consideration to the above data, bus bay locations are provided in all the upgradation links as required. The typical bus bay consists of deceleration and acceleration lanes of 45m length with stopping lane of 3.5m wide, 15m long. Adequate arrangements have also been made to drain off surface water. Typical bus bay layout and schedule of locations are included in the Drawings Volume. The Chainage locations of the bus bays are given in Table 7.3.

**Table 7.3: Schedule of Bus Bays**

Busbays Left			Busbays Right		
Start	Centre	End	Start	Centre	End
750	802.5	855	245	297.5	350
3015	3067.5	3120	3385	3437.5	3490
4940	4992.5	5045	4815	4867.5	4920
7935	7987.5	8040	8050	8102.5	8155
9750	9802.5	9855	10485	10537.5	10590
13175	13227.5	13280	13050	13102.5	13155
18590	18642.5	18695	18680	18732.5	18785

Busbays Left			Busbays Right		
Start	Centre	End	Start	Centre	End
20440	20492.5	20545	20955	21007.5	21060
23950	24002.5	24055	24370	24422.5	24475
28110	28162.5	28215	28440	28492.5	28545
32280	32332.5	32385	33065	33117.5	33170
34510	34562.5	34615	34225	34277.5	34330
36500	36552.5	36605	37100	37152.5	37205

### Truck Lay-byes

Truck lay bye is provided at location as specified in drawing. The following procedure was adopted in locating the Truck lay-bye:

- i. Surveys were carried out to identify the places where the trucks are regularly parked along the project roads. These places are usually near check posts, petrol bunks, town approaches, and restaurants/ dhabas and at locations where truck repair facilities were available. Rural sections of highway merely have any such locations.
- ii. There were no specific parking places for trucks along the project roads. This situation makes the truck drivers park vehicles at various locations in disorder that causes congestion for smooth flow of traffic particularly at town approaches.
- iii. Local consultations were held at the places of petty repair shops, restaurants/ dhaba etc. and subjective opinion of the drivers regarding necessity of truck lay bye was gathered.
- iv. Following information was collected during the inventory survey of truck lay-byes:
  - Location, chainage.
  - Timings of opening of shop – split hour/continuous.
  - Number of trucks parked during different hours a day (including peak hours)
  - Repair facilities available – vulcanising, minor repairs, major repairs
  - Other facilities available – rest rooms, dormitory facilities etc.
- v. The scenario of existing truck traffic on State Highways is entirely different from that on National Highways as only limited number of vehicles ply on the project roads from time to time and this trend changes during different seasons.
- vi. The facilities of vulcanising and minor repairs are generally not available at most of the repair shops.
- vii. Keeping in view all the above considerations, typical truck lay-bye design is proposed. It consists of deceleration and acceleration lane of length 25.0m with central parking area of 50m length and 14m wide with 1.2m wide

raised Kerb Island separating the carriageway and lay-bye. This can accommodate parking space (4.0m x 8.0m) for 13 trucks at an angular parking of 45 degrees. Sufficient working area and space for roadside establishments such as repair shops, vulcanising shops, service centre, spare parts shops, telephone booth and light refreshments with first aid facilities can be provided.

- viii. Cement concrete pavement is proposed to prevent damage caused by frequent application of brakes and parking of loaded trucks for minor repair works.

### Guard posts

Guard posts are proposed on embankments of height more than 1.5m, bridge approaches and horizontal curves of radius greater than 170m. The spacing of guard post shall be 1.0m c/c. Typical Guard post consists of pre-cast (M20) CC post of size 150mm diameter and height of 1000mm. They are encased in M15 cement concrete to a depth of 300mm below ground level. Guard posts are painted with alternate black and white reflective paint of 150mm wide bands. Typical details of guard post are provided in standard highway drawings provided.

**Table 7.4: Location of Guard Posts**

LEFT SIDE			RIGHT SIDE		
START	END	LENGTH (m)	START	END	LENGTH (m)
1/905	1/958	53	1/905	1/958	53
4/350	4/410	60	4/350	4/410	60
7/620	7/630	10	8/145	8/180	35
8/145	8/185	40	11/266	11/315	49
11/266	11/315	49	11/711	11/771	60
11/711	11/771	60	15/173	15/227	54
15/173	15/227	54	15/702	15/770	68
15/702	15/770	68	17/826	17/894	68
17/826	17/864	38	21/706	21/779	73
21/706	21/779	73	29/186	29/238	52
26/545	26/580	35	29/258	29/425	167
29/258	29/425	167	29/541	29/675	134
29/485	29/595	110	39/425	39/452	27
29/620	29/640	20			
40/740	40/810	70			
40/990	41/010	20			
Total Length of LHS		927	Total Length of RHS		900

### Road Humps and Rumble Strips

**Road Humps** are formed by providing a rounded hump of 3.7m width (17m radius) and 0.10m height for the preferred advisory crossing speed of 25kph for general traffic as per the IRC: 99–1988 guidelines. The basic material for construction is bituminous concrete formed to required shape. Road humps should be provided on minor roads at intersections of minor roads with major roads, School and Hospital zones. Proper signboards and markings are provided to advise the drivers in advance of the situation. Road humps are extended across carriageway up to the edge of

paved shoulder. The locations of the road humps are given in Schedule of Drawings separately. The schedule of road humps is presented in Table 7.5.

**Table 7.5: Schedule of Road Humps**

SL.NO.	CHAINAGE	DESCRIPTION	LHS/RHS
1	1/946	T-Type	LHS
2	2/538	T-Type	RHS
3	3/011	Y-Type	LHS
4	5/550	Y-Type	LHS
5	7/205	T-Type	LHS
6	8/335	Y-Type	RHS
7	11/708	T-Type	LHS
8	12/800	T-Type	LHS
9	12/790	T-Type	RHS
10	15/089	Y-Type	RHS
11	15/846	T-Type	RHS
12	16/422	Y-Type	LHS
13	18/704	T-Type	RHS
14	22/635	Y-Type	LHS
15	24/590	Typical 4-Legged	Both Side
16	25/183	T-Type	LHS
17	27/127	T-Type	RHS
18	28/572	T-Type	RHS
19	29/511	T-Type	RHS
20	32/518	T-Type	RHS
21	32/602	T-Type	LHS
22	36/381	Y-Type	RHS
23	36/748	Typical 4-Legged	Both Side
24	37/000	Y-Type	RHS
25	37/519	Y-Type	LHS
26	99/00	School Zone	
27	10/200	School Zone	
28	13/600	School Zone	
29	13/700	School Zone	
30	17/150	School Zone	
31	17/300	School Zone	
32	20/750	School Zone	
33	20/850	School Zone	
34	34/310	School Zone	
35	34/355	School Zone	
36	38/500	School Zone	
37	38/600	School Zone	

**Rumble Strips** are formed by a sequence of transverse strips laid across a carriageway. Maximum permitted height of 20mm. These rumble devices produce audible and vibratory effects to alert drivers to take greater care and do not normally reduce traffic speeds in themselves. The typical design details of rumble strips proposed are transverse strips of Pre-mix bituminous concrete 500mm wide and overall thickness 20mm laid across a carriageway up to the end of paved shoulder.

There will be 6 such transverse strips spaced at 2.0m c/c. Rumble strips are proposed at:

- i. Sharp curves with radius less than 170m.
- ii. Transition zones (speed limit zones).
- iii. Village/urban approaches.

Proper signboards and marking are proposed to advise the drivers in advance of the situation. The locations of the road humps are given in Schedule of Drawings separately.

### Footpath Barriers

Barriers can be used to alter patterns of pedestrian movements as part of any road safety measures. They are used in short lengths in front of school entrances, recreation grounds, and footpaths to prevent haphazard movement of pedestrians.

Covered drains of 1.5m wide have been provided at built-up section for the pedestrian movement.

Footpath barriers are formed of tubular steel sections (of designated weight in kilograms per running meter) in conformance with IS 1239. These barriers will have overall height of 1.0m above the kerb and length of 2.0m. They are difficult to climb, as there is no horizontal rails more than 100mm above the footway. These barriers are located at an offset of 150mm from the face of the kerb. The standard drawings are presented in Drawing Volume. The location and exact Chainages shall be determined at the stage of construction. The schedule of Pedestrian crossing is presented in Table 7.6.

**Table 7.6: Schedule of Pedestrian Crossing**

School Zone	Hospital Zone	Bus Bays	
CHAINAGE			
7750	-	803	298
10100	-	3068	3438
13664	-	4993	4868
17230	-	7988	8103
20800	-	9803	10538
34340	-	13228	13103
36680	-	18643	18733
38600	-	20493	21008
-	-	28163	28493
-	-	32333	33118
-	-	34563	34278
-	-	36553	37153

### Reflective Pavement Markers (RPM)

- i. Reflective Pavement Marker (RPM) or road stud is a device, which is bonded to or anchored within the road surface for lane marking and delineation for night time visibility. It reflects incident light in directions close to the direction from which it came.
- ii. Plastic body of RPM/road stud shall be moulded from ASA (Acrylic Strene Acrylonitrile) or HIPS - (High Impact Polystyrene) or ABS or any other suitable material approved by the Engineer-in-Charge. The markers shall support a load of 13635 Kg tested in accordance with ASTM D4280.
- iii. Reflective panels shall consist of number of lens containing single or dual prismatic cubes capable of providing total internal reflection of light entering the lens face. Lenses shall be moulded of methyl methacrylate conforming to ASTM D788 or equivalent.
- iv. Design details, Optical performance details and details of fixing and placement shall be in-accordance with **Ministry's letter No.RW/NH-33023 /10/ 97-DO III dated, the 11th June, 1997 on 'Technical Specifications for Reflective Pavement Markers (Road Studs)'**.

### Chevron Sign Boards

- i. The size of "Chevron" Signboard has to be 400mm x 550mm.
- ii. The signboard should be wide-angle micro-prismatic lens.
- iii. The retro – reflective surface after cleaning with soap water and in dry condition shall have the minimum co-efficient of retro–reflection (MoSRTH wide 801.3.2 clause) as indicated below for encapsulated lens.

Observation Angle (in deg)	Entrance Angle (in deg)	White	Yellow	Green/Red	Blue
0.2	-4	250 (430)	170 (325)	45 (325)	20 (20)
0.2	+30	150 (235)	100 (205)	25 (205)	11 (11)
0.5	-4	95 (250)	62 (240)	15 (240)	7.5 (10)
0.5	+30	65 (170)	45 (110)	10 (110)	5.0 (7)

*Note: Figure in brackets indicates co-efficient of retro-reflection ( $Cd/Lux/m^2$ ) for wide-angle micro prismatic lens type sheeting as per ASTM E:810 test method.*

- When totally wet, the sheeting shall not show less than 90% of the value of retro – reflective indicated in the table above. At the end of 7 years, the sheeting shall retain at least 75% of its original retro – reflectance.
- Chevron sign boards shall be installed at 10m c/c as shown in the drawings at all curves of radius less than 200 m along the outer edge facing the traffic of nearby lane.

### 7.2.5 Highway Policing and Emergency Response

The most important of all the traffic safety measures and which the enforcing officers often neglect are the Highway Policing and adequate facility for emergency response during accidents. Special training sessions for driver behavior orientation should be organized from time to time. The road users should be made aware of the



traffic signs, road pavement markings, hazards of rash driving etc. Driving during the effect of alcohol and other drugs should be fined and punished by the law.

The responsibilities of the State Highway Patrol will be,

- i. Quick response to move injured persons & disabled vehicles from state highway.
- ii. Record and maintain accident database.
- iii. Impose fine on spot for traffic rule violation.

**CHAPTER – 8**  
**SPECIFICATIONS AND CONSTRUCTION**  
**PLANS**

---

## CHAPTER – 8

### SPECIFICATIONS AND CONSTRUCTION PLANS

#### 8.1 SPECIFICATIONS

In general, the specifications laid down in “Specifications for Road and Bridge Works – Fourth Revision - by MoSRT&H” shall be followed. The detailed specifications have been given in Bidding Document prepared separately for each civil construction package.

#### 8.2 CONSTRUCTION PLANS

The different steps involved in construction are as under.

- i. The first operation in road construction involves site clearance and preparation of ground surface. The construction of structures is independent activity. New constructions/ Extensions of cross-drainage structures can be taken up simultaneously with clearance operations.
- ii. After clearances the next step is the preparation of the road shoulder on one side so that traffic can continue on this side while work on the other side proceeds. Specification Cl. 112 of MoSRT&H gives the requirements.
- iii. Start construction activities on other side of half width. Speed restrictions will be imposed on traffic in the stretch in which construction is going on.
- iv. For approved construction lengths of more than 500m, passing bays are specified (Cl. 112 of MoSRT&H specifications). Additional width shall be provided for passing bays. Passing bays are also useful for temporary parking of broken-down vehicles.
- v. Alternatively, the working lengths should be limited to about 1km stretches with minimum 0.5km spacing in between. This non-working zone will be used for overtaking and temporary stopping of vehicles.
- vi. In stretches where it is not possible to pass the traffic on part width of the carriageway, a temporary diversion shall be constructed.
- vii. The traffic should not be allowed to move on the space occupied for construction. Proper barriers should be provided between the working side and the traffic side. Necessary safety measures shall be adopted.
- viii. If the local conditions are such that two-way traffic cannot be maintained, one-way traffic movement should be operated with suitable controls at either end. In such cases working lengths should preferably not exceed 500m.

##### 8.2.1 Setting out of Work

- i. Establish working benchmarks at 250m intervals on the road in question with the help of Reference Bench Marks in the area.
- ii. Establish centre line of the carriageway and have it referenced by marker pegs and chainage boards set near the road land boundary at 50m intervals. (In hills and on curves in plains, the intervals of reference pegs should be 20m).

- iii. Prepare a schedule of reference dimensions and maintain the markers until the works reach finished formation level and are accepted by the Engineer.
- iv. Verify the dimensions and levels, shown on the drawings or mentioned in contract documents, on the site and inform the Engineer of any apparent errors or discrepancies.
- v. Prepare a profile along the centre line and cross-sections at intervals as specified in the drawings, otherwise as prescribed by the Engineer.
- vi. Obtain approval of the Engineer to the profile and cross-sections as these form the basis for measurements and payments for various items of work. The work can commence thereafter.
- vii. The lines and levels of formation, side slopes, drainage works, carriageway and shoulders should be carefully set out and frequently checked, care being taken to ensure that correct gradients and cross-sections are obtained everywhere.

### **8.2.2 Site Clearance**

- i. The road land should be cleared of all materials unsuitable for the work by cutting, removing and disposing of all materials, such as trees, bushes, shrubs, stumps, roots, grass, weeds, top organic soil not exceeding 150mm in thickness, rubbish, etc. This should be in advance of earthwork operations.
- ii. Excavation below the ground level arising out of removal of trees, stumps, etc be filled in layers with suitable material and compacted thoroughly.
- iii. All trees, stumps, etc falling within the excavation and embankment lines should be cut to such depth below ground level that in no case these fall within 500mm of the subgrade. Beyond these limits, they need to be cut down to 1m below ground level.

### **8.2.3 Excavation**

- i. The limits of excavation should be set out true to lines, curves, slopes, grades and sections as shown on the drawings. The work of excavation should be carried out in conformity with the drawings.
- ii. Undertake stripping of topsoil before excavation if so required under the contract and stack it suitably for reuse.
- iii. Keep the excavation dry.
- iv. After excavation, the sides of excavated area should be trimmed and the area contoured to minimize erosion and ponding, allowing natural drainage to take place.
- v. In case in-situ soil is to be used for subgrade, loosen the soil and compact to a thickness of 500mm with a suitable roller to 97 per cent modified proctor compaction density.

### **8.2.4 Embankment / Subgrade Construction**

The material to be used in embankment/ subgrade and its compaction shall meet the requirements as laid down in specifications. The maximum particle size shall not be more than two-thirds of the compacted layer thickness.

It shall be ensured that the subgrade material when compacted to the density requirements as per specifications shall yield the design CBR value of the subgrade.

#### **Widening of Existing Road Embankment**

When an existing embankment and/ or subgrade is to be widened and its slopes are steeper than 1 vertical on 4 horizontal, continuous horizontal benches, each at least 300mm wide, shall be cut into the old slope for ensuring adequate bond with the fresh embankment/ subgrade material to be added. The material obtained from cutting of benches could be utilized in the widening of the embankment/ subgrade. However, when the existing slope against which the fresh material is to be placed is flatter than 1 vertical on 4 horizontal, the slope surface may only be ploughed or scarified instead of resorting to benching.

#### **Embankment and Subgrade to be Placed Against Sloping Ground**

Where an embankment/ subgrade is to be placed against sloping ground, the latter shall be appropriately benched or ploughed/ scarified before placing the embankment/ subgrade material. Extra earthwork involved in benching or due to ploughing/ scarifying etc. shall be considered incidental to the work.

#### **Earthwork over Existing Road Surface**

Where the embankment is to be placed over an existing road surface, the work shall be carried out as indicated below:

- i. If the existing road surface is of granular or bituminous type and lies within 1m of the new subgrade level, the same shall be scarified to a depth of 50mm or more if specified, so as to provide ample bond between the old and new material ensuring that at least 500mm portion below the top of new subgrade level is compacted to the desired density.
- ii. If the existing road surface is of cement concrete type and lies within 1m of the new subgrade level the same shall be removed completely.

If the level difference between the existing road surface and the new formation level is more than 1m, the existing surface shall be permitted to stay in place without any modification.

#### **Earthwork for high embankment**

In the case of high embankment, the contractor shall normally use the material from the specified borrow area. In case he desires to use different material for his own convenience, he shall have to carry out necessary soil investigations and redesign the high embankment at his own cost. The contractor shall then furnish the soil test data and design of high embankment for approval of the Engineer, who reserves the right to accept or reject it.

### 8.3 TRAFFIC MANAGEMENT

All necessary safety measures shall be adopted for safety of moving traffic. The traffic moving on the road should face least disturbances due to construction activities. The safety measures should provide:

- i. Clear advance warning to road users;
- ii. Clear demarcated path for movement of vehicles in construction zone;
- iii. Proper devices to guide road users through Construction and Maintenance Zones.

#### 8.3.1 Construction and Maintenance Zones

The Construction and Maintenance Zones require special attention, as these are the zones where conflict can occur between the road users and the contractor. The basic components of Construction and Maintenance Zones are as under.

- i. **Warning Zone:** It warns in advance and prepares road users for an up-coming hazard. It is an essential part of any traffic control system. The warning system should prepare the road users well in advance by providing information regarding distance, extent and type of hazard so that they can gradually reduce their speed. The information in the zone is conveyed mostly through a series of traffic signs along the length of the zone;
- ii. **Transition Zones:** These are the areas in which the traffic is guided into and out of the diverted path around the work zone. They are the most crucial zones from the safety point of view, since most of the movements are turning movements. The traffic in this zone is diverted mostly with the help of barricades and channelisers.
- iii. **Working Zone:** This is the actual area where construction or maintenance activity is taking place and the main concern, therefore, is the safety of the workers at the site. The path of the traffic must, therefore, be clearly delineated to avoid intrusion of vehicles into the work area. Necessary buffer space shall be maintained between the workspace and moving traffic.

The distance between two work zones should be such that the flow of traffic can return to normal by permitting fast moving traffic to overtake slow moving vehicles for easy dissipation of queuing vehicles.

#### 8.3.2 Traffic Control Devices

Traffic control devices in the Construction and Maintenance Zones are required to warn, inform and guide the road users so that they as well as the workers are protected, and safe passage of traffic is possible. The primary traffic control devices used are signs, delineators, barricades, cones, pylons, pavement markings, flashing lights etc. They should be easily understood without any confusion, be clearly visible during both day and night, conform to the prevailing speeds in the immediate vicinity, be stable against sudden adverse weather conditions and be easy to install, remove and maintain. It is important that they are maintained in good visible and working condition.

### 8.3.3 Traffic Signs

Traffic signs will consist of:

- i. Ahead of the Roadwork (for both directions of traffic), on the shoulder on the side of the approaching traffic:
  - Men at Work/ Go Slow;
  - Road Narrows;
  - No Overtaking;
  - Keep Right (at merging end);
  - Diversion Ahead (for bridgework);
  - Road Closed (for bridgework);
  - Compulsory Keep Left/Right (for bridgework).
- ii. On the half-width of road where work is taking place, at each end of the Works:
  - 1 permanent barrier;
  - 1 flag man controlling successive flows of traffic in alternate directions, if one way trafficking is in operation;
  - Keep Left (at diverging end);
  - Delineators such as Chevron sign boards, traffic cones etc.
- iii. Along the length of the roadwork:
  - Continuous concrete barriers, permanent barricades, traffic cones and reflective tapes.  
  
(On long works sections, intermediate traffic controllers may also be required to transfer “Stop/Go” instructions. Alternatively portable traffic lights or hand radio sets could be used).
- iv. At the end of the roadwork (for both directions of traffic):
  - On the shoulder on the side of the traffic leaving the diversion, “Restriction Ends” signs should be placed approximately 200 meters beyond the traffic barrier.

### 8.3.4 Safety and Management Practices

Typical measures for providing safe movement of traffic in some of the most commonly occurring work zones on the roads are as follows:

- i. **Temporary Diversion:** In the cases of temporary off-road diversions running parallel to the highway, barricading may be required to prevent construction material falling on the diversion.

The warning for the construction ahead should be provided by the sign “Men at Work Ahead”. A supplementary plate indicating “Diversion” should also be provided. In addition to the sign for “Compulsory Turn Right/Left Sign”,

the “Detour” and “Sharp Deviation” signs should be used to guide the traffic into the diversion. Hazard markers should be placed at the point where the railing for the cross drainage structures on the diversion starts.

- ii. **Partial Closure for Work on a single Carriageway:** Care has to be taken to ensure that traffic is guided from the closed lane in to the operating lane without conflicting with traffic from the opposite direction.

## 8.4 CONSTRUCTION METHODOLOGY

The traffic management needs to be closely coordinated with the sequence of the construction operations. The ideal condition is that traffic should be diverted to a detour or to separate diversion but when it is not possible then the sequence of construction should be as under for concentric as well as eccentric widening.

### 8.4.1 Widening of Existing Road

- Stage 1: Treated shoulder shall be provided on the side on which work is not in progress. The treatment to shoulder shall consist of providing at least 150mm thick granular base course with bituminous surface dressing with a width of minimum 2.0m.
- Stage 2: Widening work on the other side of the carriageway is to be done right from sub-base level. While constructing sub base the shoulder need to be constructed simultaneously in layers matching the thickness of the sub base.
- Stage 3: Similarly base course layers are also be constructed in layers along with the shoulder matching the thickness of the base course layers.
- Stage 4: After completion of the compaction of base course the one layer of bituminous course is laid. The continuous length in which such work shall be carried out would be limited to 500m at a place, however, for longer stretches, passing places at least 20m long with additional paved width of 2.5m shall be provided at every 0.5km interval. The traffic arrangement shall be as per **Figure 8.1**.
- Stage 5: After completing one side in above steps the other side is taken up as per steps 2 to 4.
- Stage 6: The bituminous layers are laid in such a way that it overlaps the joint of widened portion. The work is taken up in half the carriageway whereas the other half is open to traffic. Diversion of traffic shall be as per **Figure 8.2**.

### 8.4.2 Raising of Existing Road

- Stage 1: Treated shoulder shall be provided on the side on which work is not in progress. The treatment to shoulder shall consist of providing at least 150mm thick granular base course with bituminous surface dressing with a width of minimum 2.0m



- Stage 2: Raising half the carriageway by doing earthwork for embankment and subgrade as per para 8.2.4.
- Stage 3: Execution of granular sub base, sub base and bituminous work along with the shoulders. Refer traffic management drawing in **Figure 8.1**.
- Stage 4: Diverting traffic on the newly constructed road. Refer **Figure 8.2** for diversion of traffic.
- Stage 5: Construction of remaining half as per Stage 2 & 3 above.

### 8.4.3 Strengthening of Existing Road

The sequence of construction should be as under:

- Stage 1: The shoulder adjacent to half the carriageway that is going to be used as diversion should be suitably strengthened to cater to the diverted traffic volume.
- Stage 2: Strengthening work shall be carried out in other half of the carriageway.
- Stage 3: Having completed operation in Stage 2 above, the strengthened pavement along with the hard shoulder shall be used as diversion while strengthening the other half. Diversion of traffic as per **Figure 8.2**.

### 8.4.4 Spur Road Development

All the Spur Roads connecting to Project Road shall be developed (upto 50.00m or 1 in 30 slope which ever is applicable) as given below.

Existing	Proposed Improvement
Earthen Road	Earthen Road
WBM Road	WMM + MSS
BT Road	GSB + WMM + PMC
Concrete Road	WMM + MSS

### 8.4.5 Passage of Traffic along a Temporary Diversion

In stretches where it is not possible to pass the traffic on part width of the carriageway, temporary diversion shall be constructed with 3.5 m carriageway and 1.0m earthen shoulders on each side (Total width of roadway 5.5m) with the following provision for road cruse in the 3.5 m width:

- (i) 100 mm WMM;
- (ii) 150 mm (compacted) GSB and
- (iii) Premix carpet.


### 8.4.6 Temporary Diversion of CD Works


Where the construction zone would close the road completely the remaining carriageway space would be insufficient for the traffic and create large delays, and there is no suitable alternative route, it will be necessary to construct a temporary carriageway for all or part of the traffic. This is most common situation in the case of

any major repair or reconstruction of cross drainage works. The diversion can be as given in **Figure 8.3**. The diversion shall be 3.5m carriageway with 1.0m earthen shoulders on each side with following provisions of road crust 100mm WMM, 150mm (compacted) GSB, and premix carpeting.

The temporary carriageway must satisfy the following requirements:

- i. It should have smooth horizontal and vertical profile with smooth vertical and horizontal curves;
- ii. It should not get overtopped by flood or drainage discharges under any conditions;
- iii. It should have adequate capacity to cater to the expected traffic;
- iv. It should be dust free and should ensure clear visibility at all times of day and night; and
- v. Barricading should be provided to prevent construction material falling on the diversion.








FIGURE 8.3: LAYOUT OF SIGNS AND CONTROL DEVICES FOR ROAD CLOSED WITH A DIVERSION

**CHAPTER - 9**  
**SOCIAL ASSESSMENT AND**  
**RESETTLEMENT ACTION PLAN**

---

## **CHAPTER – 9**

### **SOCIAL ASSESSMENT AND RESETTLEMENT PLAN**

#### **9.1 GENERAL**

The social Report (Social Assessment and Resettlement Action plan) will be submitted in separate volume. However the cost for social component has been incorporated in this report.

**CHAPTER - 10**  
**ENVIRONMENTAL ACTION AND**  
**ENVIRONMENTAL MANAGEMENT**  
**PLAN**

---



## **CHAPTER – 10**

### **ENVIRONMENTAL ACTION AND MANAGEMENT PLAN**

#### **10.1 GENERAL**

The social Report (Social Assessment and Resettlement Action plan) will be submitted in separate volume. However the cost for social component has been incorporated in this report.

## **CHAPTER – 11**

### **COST ESTIMATIVES**

---

## CHAPTER – 11

### COST ESTIMATES

#### 11.1 GENERAL

The cost estimate for detail engineering report has been framed on the basis of current rate analysis on labour rate and material rate schedule-2006 issued by the OWD. The approximate leads for different construction materials for respective sections were calculated by the field team. The production cost for various materials i.e. GSB, WMM and DBM at site are also calculated. The rate analysis is done using standard data book of MoSRT&H.

#### 11.2 METHODOLOGY

Estimation of the detailed quantity of each item of works is the important input required for the Cost Estimate. The quantities of the items under Site Clearance, Earth Works, Sub-base and Base Courses, Bituminous/Cement Concrete Courses, Road Junctions, Drainage and Protective Works, Bridges, Culverts and Rehabilitation etc. have been computed based on the design and drawings.

After the quantities are computed for each of the work items the amount of each item is evaluated by multiplying the respective quantities with the relevant unit rates and finally the total estimated cost is arrived accordingly.

#### 11.3 BILL OF QUANTITIES

The Bill of Quantities for the Item Rate contract was prepared under different Bills. The quantities and unit of the different work items under each bill were calculated based on the estimated quantities.

Besides the other relevant information like rate analysis, lead for various materials from different quarry locations were collected, which serves the basic guide for preparation of the tentative cost for all sections.

#### 11.4 UNIT RATES

The Unit Rate Analysis has been framed on the basis of the latest MoSRT&H Data Book.

##### 11.4.1 Basic Rates of Material

Market Rates of material have been considered invariably. The stone aggregate has been evaluated by way of installing crusher plant and manufacturing the required quantities of the different sizes of aggregate exclusively for use in the project work.

This would ensure considerable overall economy when compared with direct purchase of the finished products from the private crusher owners of the area.

For HYSD Bar, information on rates has been collected from the stockyard of SAIL/TISCO located at Bhubaneswar. Likewise the rates for High Tensile steel strands have also been adopted after market inquiry for pre-stressed work.

With regard to Bitumen, 60/70 grade is proposed and its rate is collected from the offices of the HPC/ IOC at Bhubaneswar.

Bitumen emulsion shall be used for primer coat and tack coat. The rate was also collected by inquiry from the offices of the Petroleum Companies at Bhubaneswar.

#### **11.4.2 Lead of Material**

Shortest average leads have been adopted in respect of stone aggregate, Moorum, sand etc from the quarries/ sources up to the proposed location of the Hot Mix plant, Pug Mill, Concrete Batching Plant as the Case may be. For HYSD bar, Bitumen and Bitumen Emulsion the leads are from Bhubaneswar, Visakhapatnam, Haldia are taken.

Extra lead for the mixed materials from the Hot Mix Plant/ Pug Mill/ Concrete Batching Plant as the case may be to work site is allowed as per MoSRTTH Data Book.

#### **11.4.3 Provision of Royalty**

Royalty has been added to the basic rates of the materials in the Rate Analysis as per prevailing Government Norms.

#### **11.4.4 Carriage Rates of finished Materials**

The carriage rates of materials, as stipulated in the State Schedule of Rates have been allowed in the analysis. However, in case of the mixed materials from the concerned plants to the workplace overall rate has been considered. The labour rates are taken from SSR-2006 of Orissa state with increase of Rs 15 as discussed with PIU. The machinery cost is taken from the MoSRT&H data book and SSR-2006.

### **11.5 COST ESTIMATES**

Detail costs have been worked out for the different items of road works and structures. Estimated total cost of this package is Rs 954.70 millions which includes engineering cost as Rs 753.478 millions. Estimated cost for provisional items, social, environmental and utility shifting costs as Rs 63.20 millions. The General Abstract of cost is appended here with.

## **ABSTRACT OF COST**

---

### General Abstract of Cost of Berhampur - Taptapani

Bill No.	Description	Amount in Rupees
1	Site clearance and Dismantling	8311814.00
2	Earth Work	85825564.00
3	Sub-base and base courses	159733370.00
4	Bituminous courses	186683169.00
5	Culverts & Underpasses	83003200.00
6	Bridges	24564654.00
7	Drainage & Protective works	108179807.00
8	Miscellaneous items	34382305.00
9	Maintenance, Repair and Rehabilitation works	8441133.00
10	Cost of Environmental Implementation Plan	21062708.00
11	Provisional Item	30640335.00
	<b>SubTotal (A)</b>	<b>750828059.00</b>
1	Total for Daywork : Labour	140400.00
2	Total for Daywork : Materials	1685343.60
3	Total for Daywork : Contractor's Equipment	375000.00
4	Specified Provisional Item	450000.00
	<b>Subtotal (B)</b>	<b>2650743.60</b>
	<b>Subtotal (C=A+B)</b>	<b>753478802.60</b>
1	Contingency (D=1% of C)	7534788.03
2	Quality Control (E = 1% of C)	7534788.03
	<b>Net Total (F = C+D+E)</b>	<b>768548378.65</b>
	Prorata (G = 16% of F)	122967740.58
	<b>Grand Total (H = F + G)</b>	<b>891516119.24</b>
	Add for ( i ) Social Cost(LAQ+R&R)	48,163,154.00
	(ii) Utility relocation, 2% of A	15,016,561.18
	<b>Total (I)</b>	<b>63179715.18</b>
	<b>Total Civil Construction Cost (I + H)</b>	<b>954695834.42</b>

**Detail Quantities****BILL NO.1 : SITE CLEARANCE**

Item No.	Description	Unit	Quantity	Rate	Amount
<b>BILL NO.1 : SITE CLEARANCE</b>					
1.01	Cleaning and Grubbing for road land complete as per Technical Specification Clause 201.The abstract area calculated from MX software is mentioned below and the detailed quantity is annexed herewith.	Hectare	69.00	29138.00	2010522.00
1.02	Dismantling structures and pavement including disposal of resulting material and/or salvaging useful materials complete as per Technical Specification Clause 202				
	a) Brick/ Stone Structures	Cum	618.46	112.00	69267.00
	b) Concrete/Reinforced concrete/ Prestressed concrete structures including cleaning straghtening & cutting of bars and separating them out from RCC/PSC.				
	For Slab Culverts & Box Culverts and Bridges				
	i)P.C.C.	Cum	1222.56	231.00	282411.00
	ii)R.C.C.	Cum	838.94	356.00	298662.00
	c) Dismantalling of Pavement course	Cum	41890.73	137.00	5739030.00
	d) Pipe, guard rail, edging kerbs, masonry parapet, gutters & fencing				
	Hume pipe	Lm	680.25	45.00	30611.00
	e) Kerb	Lm	59.60	7.00	417.00
	f) stone pitching	Cum	59.70	88.00	5254.00
	g) concrete railing	Lm	0.00	27.00	0.00
<b>SUB TOTAL</b>					<b>8,436,174.00</b>
<b>BILL NO.2 : EARTH WORKS</b>					
2.01	Roadway excavation necessary for construction of roadway complete as per Technical Specification Clause 301 calculated from Mx software and is annexed herewith.				
	a) Soil	Cum	438207.85	28.00	12269820.00
	b) softrock (blasting not required) (LS)	Cum	4494.44	37.00	166294.00
	c) Hard rock (blasting required) (LS)	Cum	6741.66	119.00	802258.00
2.02	Construction of embankment with approved material complete as per drawing and Technical Specification Clause 305 with all leads and lifts , calculated from MX software and annexed herewith.	Cum	100705.46	106.00	10674779.00

Item No.	Description	Unit	Quantity	Rate	Amount
2.03	Construction of subgrade and earthen shoulder with approved material as per drawing complete and Technical Specification Clause 305 with all leads and lifts calculated from MX Software and annexed herewith.	Cum	337999.00	129.00	43601871.00
2.04	Construction of granular/gravel shoulders with approved material as per drawing complete and Technical Specification Clause 305 with all leads and lifts	Cum	0.00	473.32	0.00
2.05	Construction of embankment and subgrade with suitable material deposited at site from roadway and drainage excavation all complete as per drawing and Technical Specification Clause 305 with all leads and lifts.	Cum	43821.00	57.00	2497797.00
2.06	Loosening and recompacting subgrade in all kinds of soil complete as per Technical Specification Clause 305	Cum	35375.00	40.00	1415000.00
2.07	Filling of median/island complete as per Technical Specitication Clause 407	Cum	1620.00	120.00	194400.00
2.09	Scarifying the existing bituminous surface layers complete as per Technical Specification Clause 305 calculated from MX Software and annexed herewith.	Sqm	20241.70	2.00	40483.00
2.10	Lime Stabilisation for Improving embankment (Laying and spreading available soil/excavated soil in the embankment on a prepared surface, pulverising, mixing the spread soil in place with rotavator with 3 % slaked lime having minimum content of 70% of CaO, grading with motor grader and compacting with the road roller at OMC to the desired density to form a layer of improved sub grade) as per Technial Specification Clause 402.	Sqm	0.00	141.00	0.00
2.11	Providing Geotextiles for improvement of sub-soil strength as per drawing and technical specification.	Sqm	0.00	0.00	0.00
<b>SUB TOTAL</b>					<b>71,662,702.00</b>



Item No.	Description	Unit	Quantity	Rate	Amount
<b>BILL NO.3 : SUB-BASE AND BASE COURSES</b>					
3.01	Construction of Coarse graded Granular Sub-base course complete as per Technical Specification clause 401 , calculated from MX software and annexed herewith.	Cum	130539.61	349.00	45558325.00
3.02	Construction of wet mix macadam complete as per Technical Specification clause 406 , calculated from MX software and annexed herewith.	Cum	9494.30	974.00	9247443.00
<b>SUB TOTAL</b>					<b>54,805,768.00</b>
<b>BILL NO.4 : BITUMINOUS COURSES</b>					
4.01	Providing Primer coat over granular surface complete all as per Technical specification clause 502, calculated from MX software and annexed herewith.	Sqm	401243.99	11.00	4413684.00
4.02	Providing Tack coat complete as per Technical Specification clause 503 as calculated from MX software	Sqm	401243.99	4.00	1604976.00
4.03	Providing dense bituminous macadamcourse complete as per Technical Specification Clause 507, calculated from MX software and annexed herewith.	Cum	27802.47	3881.00	107901381.00
4.04	Providing bituminous concrete wearing course using CRMB-55 complete as per Technical Specification Clause 512, calculated from MX software and annexed herewith.	Cum	16049.76	4374.00	70201648.00
4.05	Providing, laying mixed seal surfacing in spur roads complete as per technical specification clause 512.	Sqm	5512.50	88.00	485100.00
4.06	Providing dry lean cement concrete subbase complete as per Technical Specification Clause 601	Cum	0.00	1689.00	0.00
4.07	Providing cement concrete pavement complete as per Technical Specification Clause 602	Cum	0.00	4176.00	0.00
<b>SUB TOTAL</b>					<b>184,606,789.00</b>

Item No.	Description	Unit	Quantity	Rate	Amount
<b>BILL NO.5 : CULVERTS AND UNDERPASSES</b>					
5.01	Earthwork in excavation of foundation for structures complete as per drawing and technical specifications clause 304 including all leads and lifts.	Cum	9083.63	31.00	281593.00
5.02	Earth fill below pitching in quadrant portion with approved material complete as per drawing and Technical Specification Clause 305 with all leads and lifts.	Cum	2318.34	106.00	245745.00
5.03	Providing and filling behind abutment, wing wall and return wall etc. and below pipe bed in layers not exceeding 150mm thick including All leads and lifts complete as per drawings, direction of the Engineer and Technical specification clause 304.	Cum	3738.63	332.00	1241225.00
5.04	Providing filter media behind abutment, wing wall and return wall complete as per drawing and Technical Specification clause 305.	Cum	1945.79	1160.00	2257116.00
5.05	Cement Concrete M-15 grade in levelling course etc. including centering and shuttering all complete as per Drawings and Technical Specification Sections 1500 and 1700.	Cum	2221.94	2764.00	6141446.00
5.06	Cement Concrete M-15 grade in substructure & headwall including centering and shuttering all complete as per Drawings and Technical Specification Sections 1500 and 1700.	Cum	3312.06	2924.00	9684468.00
5.07	Reinforced cement concrete in all types of culverts as per drawing and technical specification Clause No.1700 & 2300.				
	a) M-20 Grade	Cum	6035.82	3845.00	23207734.00
	b) M-25 Grade	Cum	21.50	3845.00	82676.00
5.08	Reinforced cement concrete M-30 grade in approach slabs including cost of reinforcement all complete as per Drawing and Technical Specification Section 2700.	Cum	1425.69	5732	8172055.00
5.09	HYSD bar reinforcement complete as per drawing and technical specifications clause 1600	MT	406.28	42550.00	17287104.00
5.10	Providing laying and joining NP-4(I.S 458) hume pipes with culvert complete as per drawing Tech. Specification section 2900 and IRC special publication no.13				
	a) 1m dia. hume pipe in single row	Rm	850.000	3362.00	2857700.00
	b) 1m dia. hume pipe in double row	Rm	582.500	6773.00	3945273.00

Item No.	Description	Unit	Quantity	Rate	Amount
5.11	Providing and laying filter material underneath stone pitching in slopes complete as per drawings and technical specification section 2500.	Cum	1069.57	1160.00	1240699.00
5.12	Providing and laying stone Pitching on embankment slopes complete as per drawing and technical specification Clause 2504.	Cum	2019.85	665.00	1343199.00
5.13	Providing rubble stone flooring in Cement mortar (1 Cement:3 Sand) and joints complete as per Drawing and Technical Specification Section 1400 and 2500.	Cum	1448.74	2505	3629103.00
5.14	Providing weep holes in box portion, return wall, wing wall etc. all complete as per drawing and technical specification clause . 2706.	Nos	6365.20	100.00	636520.00
5.15	Supplying, fitting and fixing in position true to line and level bearings confirming to IRC-83 (para-II) section IX complete with all accessories as per drawings and technical specification clause 2605	Sqm	83.50		
5.16	Supplying and fixing the following types of expansion joints complete as per Drawing and Technical Specification Section 2600.	Rmt	1704.00	34.00	57936.00
5.17	Reinforced cement concrete railing complete as per Drawing and Technical Specification Section 2700 (Including cost of Reinforcement)	Rmt	1396.38	1143.00	1596062.00
5.18	Bituminous wearing course 56mm thick comprising 50mm thick asphaltic concrete in a single layer over Bituminous mastic course 6mm thick with a prime coat complete as per Drawing and Technical Specification Section 2700 and Clause 512.	Sqm	6962.50	470.50	3275854.00
5.19	Synthetic enamel painting of culvert no. and span arrangement as per IRC - 7 - 1971 and as directed by the Engineer.	No.	236.00	47.00	11092.00
<b>SUB TOTAL</b>					<b>87,194,600.00</b>

Item No.	Description	Unit	Quantity	Rate	Amount
<b>BILL NO.6 : BRIDGES</b>					
6.01	Earthwork in excavation of foundation for structures complete as per drawing and technical specification clause 304 including all leads & lift	Cum	2218.86	31.00	68785.00
6.02	Providing and filling foundation and at the back of abutment, wing wall and return wall etc. and below pipe bed in layers not exceeding 150mm thick including including all leads & lifts as per Technical specification Clause 304 and 305.	Cum	2742.11	332.00	910380.00
6.03	Providing Filter media behind abutment, wing wall and return wall complete as per drawing and technical Specification clause 305 and 2504	Cum	186.58	1160.00	216438.00
6.04	Cement concrete M-15 grade in levelling course etc including centering and shuttering all complete as per drwaing and Technical specification Section 1500 and 1700.	Cum	102.36	2764.00	282924.00
6.05	Cement concrete M-15 grade in foundation and substructure etc including centering and shuttering all complete as per drwaing and Technical specification Section 1500 and 1700.	Cum	509.22	2924.00	1488958.00
6.06	Reinforced cement concrete in foundation complete as per drawing & Technical specification sections 1700, 2100 & 2200				
	a) M-20 Grade	Cum	129.56	3302	427799.00
	b) M-25 Grade	Cum	0.00	3626	0.00
	c) M-30 Grade	Cum	0.00	3638	0.00
	d) M-35 Grade	Cum	385.236	3710	1429226.00
6.07	Reinforced cement concrete in substructure complete as per drawing & Technical specification sections 1700, 2100 & 2200				
	a) M-20 Grade	Cum	68.20	3494.00	238291.00
	b) M-25 Grade	Cum	0.00	3845.00	0.00
	c) M-30 Grade	Cum	259.36	3867.00	1002943.00
	c) M-35 Grade	Cum	0.30	4061.00	1218.00
	c) M-40 Grade	Cum	0.000	4414.00	0.00

Item No.	Description	Unit	Quantity	Rate	Amount
6.08	Reinforced cement concrete in super structure complete as per drawing and Technical specification section 1700 & 2200.				
	a) M-25 grade	Cum	424.54	4343.00	1843798.00
	b) M-30 grade	Cum	261.81	4395.00	1150634.00
6.09	Prestressed cement concrete in super structure complete as per drawing and Technical Specification Section 1800 and Clause 2305.				
	M-40 grade	Cum	0.00		
6.10	Reinforced cement concrete railing complete as per drawing and Technical specification section 2700 (Including cost of Reinforcement)				
	Hand Railing	Rmt	30.80	1143.00	35204.00
6.11	Bored cast-in-situ M-35 grade RCC Pile excluding reinforcement complete as per drawing and technical specification cl.1100 , 1600 , 1700 and removal of excavated earth with all leads and lifts.	Rmt	322.80	7661	2472971.00
6.12	A)HYSD bar reinforcement with Anti-corrosive treatment coating complete as per drawing and technical specifications clause 1600				
	a) in foundation	Tonne	84.08	42510.00	3574263.00
	b) in substructure		41.92	42550.00	1783629.00
	c) in superstructure		75.35	42934.00	3235131.00
	B)Providing and supplying High Tensile steel strands including all accessories for stressing, stressing operation and grouting complete as per Drawing and Technical Specification Section 1800.	Tonne	0.00		
6.13	Providing and fixing elastomeric bearings complete as per Drawing and technical specification 2000.				
	a) Elastomeric bearing	Cucm	50000.00	1.61	80500.00
	b) POT PTFE bearing	Tonne	0.00		
	c) Tar paper bearing	Sqm	72.791	50.00	3640.00
6.14	Reinforced cement concrete M-30 grade for in approach slabs including cost of reinforcement all complete as per Drawing and Technical specification section 2700.	Cum	107.10	5732.00	613897.00

Item No.	Description	Unit	Quantity	Rate	Amount
6.15	Bituminous wearing course 56mm thick comprising 50mm thick asphaltic Concrete in a single layer over Bituminous mastic course 6 mm thick with a prime Coat Complete as per drawing and Technical Specification Section 2700 and Clause 512.	Sqm	1411.49	470.50	664105.00
6.16	Providing and fixing Drainage Spouts Complete as per drawing and Technical Specification Clause 2705	No	30.00	733.00	21990.00
6.17	Providing and laying Stone pitching in slopes complete as per drawing and Technical Specification Section 2500	Cum	434.65	665.00	289044.00
6.18	Providing as laying fitter material underneath Stone pitching in slopes Complete as per drawing and Technical Specification Section 2500.	Cum	197.91	1208.00	239071.00
6.19	Providing weep holes in abutments, wing walls and return walls etc. as per drawing and Technical Specification Section 2700	Nos	429.00	100.00	42900.00
6.20	Providing rubble Stone flooring in Cement mortar (1Cement:3 sand) and joints Complete as per drawing and Technical Specification Section 1400 and 2500	Cum	39.96	665.00	26573.00
6.21	Supplying as fixing the following types of expansion joints Complete as per drawing and Technical Specification Section 2600 a) Filler type	Rm	246.13	34.00	8368.00
	b) Strip seal type of expansion joint including acceptance testing as Specified, to be installed under Supervision of the specialist manufacturer	Rm	24.00	11931.00	286344.00
6.22	Synthetic enamel painting of Bridge No and Span arrangements as per IRC-1971 and as directed by Engineer	No	20.00	47.00	940.00
6.23	Carrying and Confirmatory bores up to required depth as locations of bridges as directed by Engineer complete in all respects handling testing as per Technical Specification Section 2400 and interpretation of the bore data and presentation of the results  a) In all types of soil (except rock) i) depth from 0m to 10m ii) depth from 10m to 20m	Lm Lm	120.00 60.00	400.00 450.00	48000.00 27000.00

Item No.	Description	Unit	Quantity	Rate	Amount
	iii) depth from 20m to 30m	Lm	60.00	500.00	30000.00
	b) In soft rock				
	l) depth from 0m to 5m	Lm	60.00	600.00	36000.00
	ii) depth from 5m to 10m	Lm	60.00	650.00	39000.00
6.24	Providing and painting of flood gauge on substructure is fall height and 500mm width as per direction as the Engineer	Rm	45.00	830.00	37350.00
6.25	Providing HDPE Service pipe as approved quality in footpath as per drawing and direction of the Engineer	Rm	510.40	300.00	153120.00
6.26	Plastering with cement mortar (1:3 ) on brick work in sub-structure as per Technical Specifications Clause 1300 & 2200.	Sqm	0.00	583	0.00
6.27	Earth fill below pitching in quadrant portion with approved material complete as per drawing and Technical Specification Clause 305 with all leads and lifts.	Cum	1340.85	106	142130.00
6.28	Sand Filling in Foundation Trenches as per Drawing & Technical Specification Clause 304.	Cum	0.00	294	0.00
6.29	PCC in flooring as per Drawing & Technical Specification Clause 1500, 1700 & 2100.				
	a) M-15	Cum	93.24	2764	257715.00
	b) M-20	Cum	31.08	3206	99642.00
6.30	Provision of an Reinforced cement concrete crash barrier at the edges of the road, approaches to bridge structures and medians, constructed with M-40 grade concrete with HYSD reinforcement conforming to IRC:21 and dowel bars 25 mm dia, 450 mm long at expansion joints filled with pre-moulded asphalt filler board, keyed to the structure on which it is built and installed as per design given in the enclosure to MOST circular No. RW/NH - 33022/1/94-DO III dated 24 June 1994 as per dimensions in the approved drawing and at locations directed by the Engineer, all as specified				
		Lm	255.20	2237	570882.00
<b>SUB TOTAL</b>					<b>23,880,803.00</b>

**BILL NO.7 : RETAINING WALL, DRAINAGE AND PROTECTIVE WORKS**

7.01 Retaining Wall

Item No.	Description	Unit	Quantity	Rate	Amount
(a)	Earthwork in excavation for foundation complete as per drawing and Technical Specification Clause 304 in Retaining wall for high embankment stretches	Cum	1663.20	31.00	51559.00
(b)	Back filling behind wing wall with selected imported granular material of approved quality complete as per drawing and Technical	Cum	1195.92	368.00	440099.00
(c)	Filter medium behind wing wall complete as per drawing and Technical Specification Clauses 305 & 2504	Cum	2112.00	1160.00	2449920.00
(d)	Plain cement concrete M -15 in foundation levelling course etc. including centering and shuttering all complete as per drawing and Technical Clauses 1500 & 1700	Cum	138.60	2924.00	405266.00
(e)	Cement concrete M -25 for reinforced concrete in foundation including centering and shuttering all complete as per drawing and Technical Clauses 1500 & 1700	Cum	0.00	3626.00	0.00
(f)	Cement concrete M -25 for reinforced concrete in substructure including centering and shuttering all complete as per drawing and Technical Clauses 1500 & 1700	Cum	963.71	3845.00	3705465.00
(g)	providing steel reinforcement (HYSD) for retaining wall complete as per drawing and Technical Specification Clause 1600	Cum	57.82	42550.00	2460352.00
(h)	Reinforced cement concrete railing of grade M-30 complete as per drawings and Technical specifications section 2700 (including cost of reinforcement)	Lm	440.00	1143.00	502920.00
(I)	Providing weep holes in retaining wall complete as per drawing and Technical Specification Clause 2700	No.	880.00	100.00	88000.00
7.02	Providing and laying stone pitching on embankment slopes as per drawing and Technical Specification Clause 2504 Near Bridge approaches where separate embankment exists	Cum	738.000	665.00	490770.00
7.03	Providing and laying filter material underneath stone pitching on embankment slopes as per drawing and Technical Specification Clause 2504	Cum	369.000	1208.00	445752.00



Item No.	Description	Unit	Quantity	Rate	Amount
7.04	Turfing side slopes of main road and service road with grass sods complete as per Technical Specification Clause 307	Sqm	160058.000	12.00	1920696.00
7.05	Constructing lined surface drains/ sub surface drains to the required lines and grades as per drawing and Technical Specification Clause 309	Lm	22980.000	3718.00	85439640.00
7.06	Constructing box type drains to the required lines and grades as per drawing and technical specification	Lm	1120.000	8094.00	9065280.00
<b>SUB TOTAL</b>					<b>107,465,719.00</b>
<b>BILL NO-8 : MISCELLANEOUS ITEMS.</b>					
8.01	Providing and laying plain cement concrete kerb as per drawing and Technical Specifications Clauses 408 and section 1700.	Lm	336.483	148.00	49799.00
8.02	Providing service ducts with 150mm dia GI pipes over concrete base under existing and proposed carrigeways including cutting of trenches through existing roadway and reinstatement of the same as per design and specification of new construction (but exclud	Lm	378.000	1669.00	630882.00
8.03	Providing and fixing RCC boundry posts complete as per drawing and Technical Specification Clause 806 ( including cost of reinforcement )	No	449.000	260.00	116740.00
8.04	Providing and fixing RCC/PCC hectometre, Kilometre and 5th kilometre stones complete as per Technical Specification Clause 804 (including cost of reinforcement)				
	a) No of (200) Hectometre Stone	No	164.000	278.00	45592.00
	b) No of Kilometre stone	No	32.000	1036.00	33152.00
	c) No. of 5th Kilometre Stone	No	9.000	1702.00	15318.00
8.05	Constructing footpath/ paved separator / passenger platform / paved part of medians and islands complete a spe drawing and Technical Specifications Clause 409 and 407 For Toll Plaza	sqm	3693.000	2000.00	7386000.00
8.06	Providing passenger shelters for Bus Bays as per drawing and Technical Specifications Section 1700.	No	26.000	80000.00	2080000.00

Item No.	Description	Unit	Quantity	Rate	Amount
8.07	Construction of temporary diversion including Cross drainage works where necessary and maintenance thereof including traffic control and safety complete as per Technical Specification Clause 112.	Lm	5160.000	1498.00	7729680.00
8.08	(I) Pavement marking with hot applies thermoplastic paints confirming to ASTM D86 / BS 3262-Part as per drawing and Technical specifications Clause 803.				
	a) Lane line / Edge marking	sqm	11746.000	595.00	6988870.00
	b) Directional arrows and lettering etc.	No	192.000	39.00	7488.00
8.09	Supplying and fixing sign boards complete as per Technical Specifications Clause 801 and as directed by Engineer. Including the cost of Posts, Fitting & fixing. Sheeting will be retro reflective type of high intensively grade and messages / boarders will				
(a)	Informatory Signs				
	(i) Facility Information (800 x 600)mm	No	10.000	2880.00	28800.00
	(ii) Direction Signs (1200 x 700 mm)	No	2.000	8325.00	16650.00
	(iii) Advance Direction (size 1800 x 1200mm) ,	No	1.000	14256.00	14256.00
	Re-Assurance Sign (1800 X 1200 mm) ,	No	1.000	14256.00	14256.00
	Destination Sign (1500 X 900 mm) ,	No	2.000	12256.00	24512.00
	Place Identification (1500 X 900 mm) ,	No	1.000	12256.00	12256.00
	(iv) Route Marker Sign (450mm x 600mm)	No	4.000	3003.00	12012.00
	(v) Other Informatory Signs (2100mm x 1500mm)	No	2.000	14256.00	28512.00
(b)	CAUTIONARY SIGNS triangular 900mm side	No	20.000	3574.00	71480.00
(c)	MANDATORY SIGNS				
	Circular 600mm dia	No	70.000	3096.00	216720.00
	Octagon 900 mm height	No	85.000	5869.00	498865.00
	Triangular 900 mm side	No	121.000	3574.00	432454.00
8.10	Providing & fixing retro - reflectorised road delinators complete as per drawing , Technical specifications clause 805 and as directed by Engineer				
	( I ) Roadway delinator	No	391.000	787.00	307717.00
	( ii ) Hazard Marker	No	16.000	787.00	12592.00
	( iii ) Object Marker	No	26.000	787.00	20462.00
8.11	Providing and fixing RCC Guard post complete including end anchorage as per drawing and Technical Specifications Clause 810	No.	949.000	323.00	306527.00

Item No.	Description	Unit	Quantity	Rate	Amount
8.12	Supply of colour record photographs negative and two colour prints therefrom mounted in album as per Technical Specifications Clause 125 As per requirements	No	500.000	5.00	2500.00
8.13	Supply of additional prints of coloured photographs referred to above as per Technical Specifications Clause 125 As per requirements	No	800.000	5.00	4000.00
8.14	Supply of colour video cassette records during construction as per Technical Specifications Clause 126 As per requirement	set	2.000	200.00	400.00
8.15	Providing rumble strips complete as per drawing and technical specification.	No.	12.000	5521.00	66252.00
8.16	Providing road hump complete as per drawing and technical specification.	No.	39.000	13808.00	538512.00
8.17	Providing toll plaza as per drawing and technical specification.	No.	1.000	1170506.00	1170506.00
8.18	providing utility duct across the road in specified locations as per the schedule mentioned in drawing	No.	0.000	0.00	0.00
	<b>SUB TOTAL</b>				<b>28,883,762.00</b>

#### **BILL NO.9 MAINTENANCE, REPAIR AND REHABILITATION**

9.01	Carrying out routine maintenance of Highway as per Technical Specifications Clause 3002 and as per direction of the Engineer (excluding bituminous work)	Km-month	576.000	1500.00	864000.00
9.02	Carrying out treatment and repairs to pot-holes and any necessary patching to the existing bituminous carriageway surfacing as per Technical Specification Clause 3004 as per direction of the Engineer	Sqm	8000.000	73.00	584000.00
9.03	Providing and laying reinforced Cement Concrete of grade M- 30 in railings including dismantling of damaged railings, straightening and cleaning of the existing reinforcement as required Complete as per drawing and Specification Sections 1500,1600,1700,2200 & 2800.	Cum	24.888	2323.00	57814.24

Item No.	Description	Unit	Quantity	Rate	Amount
9.04	Plain Cement Concrete M- 20 grade for extension of masonry/ P.C.C. Abutment/Pile, foundation including cleaning of dismetalled face of existing structure and applying a coat of Cement slurry, costin fresh Concrete against the old Concrete face including cost of all materials, form work, centering , staging during all complete as per Technical Specification Sections 2100,2200 and 2300	Cum	0.000	3392.00	0.00
9.05	Removal of damaged expansion joint Complete and replacement with steel plate sliding expansion joint as per drawing as Technical Specification Sections 2600 & 2800	Lm	68.200	1659.00	113143.80
9.06	Replacement of existing wearing coat by Bituminous wearing course56mm thick comprasing 50mm thick asphaltic Concrete in a single layer over Bituminous mastic course 6 mm thick with a prime Coat Complete as per drawing and Technical Specification Section 2700 and Clause 512.	Sqm	37.969	527.50	20028.52
9.07	Reinforced Cement Concrete M- 30 grade approach slabs including cost of reinforcements Complete as per drawing and Technical Specification Section 2700	Cum	0.000	5732.00	0.00
9.08	Cement Concrete M-15 grade levelling Course below approach Slabs complete as per drawing and Technical Specification Section 1700	Cum	0.000	2924.00	0.00
<b>SUB TOTAL</b>					<b>1638987.00</b>
<b>BILL NO. - 10 : PROVISIONAL ITEMS</b>					
10.01	Cutting of trees including cutting of trunks, branches and removal of stumps including stacking of serviceable material within a lead of 1000 metres and earthfilling in the depression/pit				
	a) Girth From 300mm to 600mm	No	400.000	80.00	32000.00
	b) Girth From 600mm to 900mm	No	275.000	162.00	44550.00
	c) Girth From 900mm to 1800mm	No	150.000	285.00	42750.00
	d) Girth From 1800mm to Above	No	90.000	515.00	46350.00
10.02	A) Plantation of trees	No	9150.000	25.00	228750.00
	B) Planting of plants & shurbs in median/ verges	Lm	25000.000	12.00	300000.00

Item No.	Description	Unit	Quantity	Rate	Amount
10.03	Providing and installing Telephone connection with STD facility	No	0.000	2000.00	0.00
10.04	Boring for soil investigation including conducting necessary tests and preparation of report, as per direction of the Engineer and Technical Specification Clause 2400.	Lm	0.00	400.00	0.00
10.05	Co-ordination for Shifting of Utilities as per Technical Specification Clause 110 Total project length	Km	0.00	2000.00	0.00
10.06	Construction of building (plinth area 9 sq m.) and installation of weigh bridge including arrangement for electric supply, all electrical items like lights, exhaust fans, sockets, receptacles and complete wiring with necessary earthing etc. complete as directed by Engineer.	No	100.00	40500.00	4050000.00
10.07	Providing and fixing Pedestrian guard rails in 2m and 1m modules including painting wrth approved paint complete as per drawing and Technical Specification Clause 803,1008,1300 & 1700	Lm	0.00	3000.00	0.00

**SUB TOTAL**

**4744400.00**

**BILL NO. 12 : DAYWORKS**

**1. Labour**

D101	Labour	Hour	400	65	26000
D102	Mason	Hour	50	100	5000
D103	Carpenter	Hour	20	100	2000
D104	Steelworker Erector	Hour	70	100	7000
D105	Driver for vehicle up to 10 tons	Hour	50	100	5000
	Operator for excavator, dragline, shovel or crane			100	
D106		Hour	50		5000
D107	Operator for tractor with dozer blade or ripper	Hour	50	100	5000
D108	Operator grader	Hour	50	100	5000
D109	Operator in other construction equipment	Hour	50	100	5000
D110	Chowkidars for watch & ward	Hour	500	90	45000
			Subtotal		<b>110000.00</b>

**2. Material**

D201	Cement, ordinary Portland or equivalent in bags conforming to IS:269:1989 and IS 455:1989	Per Mt	20	4325.00	86500
D202	HYSD reinforcing bars upto 25 mm dia conforming to IS:1786:1989	Per Mt	5	29827.00	149135
D203	Bricks of class designation 75 as per IS:1077:1992	Per 1000 Nos	500	1859.50	929750

Item No.	Description	Unit	Quantity	Rate	Amount
D204	Anti Corrosive Bituminous paint	Per Lit	10	132.17	1321.65
D205	Enamel Paint of any shade & colour (IS:2932-1964 & IS 137-1975)	Per Lit	10	132.17	1321.65
D206	Coarse Sand as per IS 1542	Per Cum	50	171.50	8575
D207	R.R. Stone for masonry	Per Cum	50	2,382.00	119100
D208	Crusher broken stone aggregates up to 25 mm nominal size	Per Cum	50	578.00	28900
D209	Crusher broken stone aggregates Above 25 mm nominal size	Per Cum	50	489.60	24480
D210	Portable water at site	Per 1000 ltr	5000	50000	250000000
			Subtotal		<b>251349083</b>

### 3.Constructional Plant.

D301	Excavator, face shovel, or dragling: Up to and including 1 m <sup>3</sup>	Hour	50	840	42000
0.1					42000
0.2	Over 1 m <sup>3</sup> to 2 m <sup>3</sup>	Hour	30	840	25200
0.3	Over 2 m <sup>3</sup>	Hour	10	840	8400
D302	Tractor, including bull or angle dozer:				
0.1	Up to and including 150 kW	Hour	50	234	11700
0.2	Over 150 kW to 200 kW	Hour	30	234	7020
0.3	Over 200 kW to 250 kW	Hour	10	234	2340
D303	Tractor with ripper:				
0.1	Up to and including 200 kW	Hour	30	252	7560
0.2	Over 200 kW to 250 kW	Hour	10	252	2520
D304	Motor grader	Hour	40	1545	61800
D305	Crane- 5 tonne	Hour	40	230	9200
D306	Diesel Road Roller, or Vibratory Compactor upto 10 t	Hour	40	802	32080
D307	Trucks, or Truck tipper, or Truck with mounted water tank or truck with crane for removal of accidental vehicles.	Hour	100	200	20000
D308	Tractor with trolley, or tractor with water tanker trailer, tractor with ripper Tractor with hydraulic scraper				
(a)	upto 25 HP	Hour	40	252	10080
(b)	For 25-40 HP	Hour	30	252	7560
D309	Bitumen mixture (10-14 Cft.) C.C Mix tyre (10-14 Cft.)	Hour	20	1000	20000
D310	Water pumping sets mounted on trolley (diesel driven)with inlet & outlet pipes.				
a)	Sets up to 10 HP	Hour	10	200	2000
b)	Sets 11 to 20 HP	Hour	10	250	2500
c)	Sets above 20 HP	Hour	10	300	3000
D311	Generator sets mounted on trolley				
a)	Sets upto 5 Kva	Hour	10	50	500
b)	Sets 5-15 Kva	Hour	10	150	1500
D312	Mobile Crane / Power winch	Hour	10	230	2300
D313	Bull Dozer 100/110 Hp	Hour	10	2400	24000
D314	Plate compactors	Hour	10	100	1000

Item No.	Description	Unit	Quantity	Rate	Amount
D315	Jack hammers for dismantling	Hour	10	206	2060
D316	Utility Vehicles	Hour	10	50.00	500
D317	Mini Hot Mix Plant (5TPH)	Hour	10	8930	89300
					396120.00